

STATE OF OREGON  
 COUNTY OF YAMHILL  
 CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

TERRY L. & MARTHA A. CANNON  
 9165 SE HILLVIEW DR  
 AMITY OR 97101

BRUCE WIANECKI  
 9140 SE HILLVIEW DR  
 AMITY OR 97101

confirms the right to use the waters of TWO WELLS [NORTH WELL (YAMH 6976) AND SOUTH WELL (YAMH 3164)] in the SOUTH YAMHILL RIVER BASIN for IRRIGATION of 7.85 ACRES.

This right was perfected under Permit G-11245. The date of priority is JULY 23, 1990. The use is limited to not more than 0.082 CUBIC FOOT PER SECOND (CFS), being 0.033 CFS FROM THE NORTH WELL AND 0.049 CFS FROM SOUTH WELL, or its equivalent in case of rotation, measured at the wells.

The wells are located as follows:

Twp	Rng	Mer	Sec	Q-Q	DLC	Measured Distances
5 S	4 W	WM	14	NW SE	52	NORTH WELL (YAMH 6976) - 1507 FEET NORTH AND 2320 FEET WEST FROM SE CORNER, SECTION 14
5 S	4 W	WM	14	SW SE	52	SOUTH WELL (YAMH 3164) - 1053.5 FEET NORTH AND 2336.5 FEET WEST FROM SE CORNER, SECTION 14

The amount of water used for irrigation, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second per acre, or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 2.5 acre-feet per acre for each acre irrigated during the irrigation season of each year.

A description of the place of use is as follows:

Twp	Rng	Mer	Sec	Q-Q	DLC	Acres	Well
5 S	4 W	WM	14	NW SE	52	3.97	North (Cannon)
5 S	4 W	WM	14	SW SE	52	3.88	South (Wianecki)

**NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW**

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

To monitor the effect of water use from the SOUTH WELL (YAMH 3164) authorized under this right, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

The user shall submit seven consecutive annual reports of static water level measurements. Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The reference level against which any future measurements will be compared is 213.71 feet below land surface.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The wells shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge to determine the water level elevation in the wells at all times. When required by the Department, the water user shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of groundwater withdrawn.

The Director may require water level or pump test results every ten years.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.


This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The right to the use of the water for the above purpose is restricted to beneficial use on the lands or place of use described.

Issued MAR 27 2015.



Dwight Frisvold  
Water Right Services Division Administrator, for  
Thomas M. Byler, Director  
Oregon Water Resources Department