

STATE OF OREGON

COUNTY OF CURRY

CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

BLANCO BOGS
PO BOX 41
PORT ORFORD OR 97465

confirms the right to use the waters of ONE WELL AND ONE SUMP IN SIXES RIVER BASIN for IRRIGATION AND AGRICULTURAL USES ON 37.1 ACRES FOR CRANBERRY OPERATIONS AND SUPPLEMENTAL IRRIGATION AND AGRICULTURAL USE ON 33.0 ACRES FOR CRANBERRY OPERATIONS.

This right was perfected under Permit G-12993. The date of priority is SEPTEMBER 18, 1991. The amount of water to which this right is entitled is limited to an amount actually used beneficially, and shall not exceed 0.61 CUBIC FOOT PER SECOND (CFS), BEING 0.41 CFS FROM THE WELL AND 0.20 FROM THE SUMP, or its equivalent in case of rotation, measured at the well/sump.

The period of allowed use for water from the well is year round for agricultural use and March 1 through October 31 for irrigation.

The period of allowed use for water from the sump is November 1 through April 30 and during the month of July for agricultural use and March 1 through April 30 and during the month of July for irrigation.

The points of appropriation are located as follows:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
31 S	15 W	WM	32	NE SW	WELL - 2560 FEET NORTH AND 2430 FEET EAST FROM SW CORNER, SECTION 32
31 S	15 W	WM	32	NE SW	SUMP - 1600 FEET NORTH AND 2015 FEET EAST FROM SW CORNER, SECTION 32

The amount of water diverted for CRANBERRY OPERATIONS, together with amounts secured under any other rights existing for the same lands, is limited as follows: For temperature control, 0.15 cubic foot per second per acre; For flood harvesting or pest control, 0.05 cubic foot per second per acre; For irrigation of cranberries, ONE-FORTIETH of one cubic foot per second and 3.0 acre feet per acre for each acre irrigated during the irrigation season of each year. For the irrigation of any other crop, the amount of water diverted is limited to ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre feet per acre during the irrigation season of each year.

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

A description of the place of use is as follows:

CRANBERRY OPERATIONS					
Twp	Rng	Mer	Sec	Q-Q	Acres
31 S	15 W	WM	32	NE SW	16.4
31 S	15 W	WM	32	NW SW	0.6
31 S	15 W	WM	32	SW SW	2.2
31 S	15 W	WM	32	NW SE	1.7
31 S	15 W	WM	32	SW SE	16.2

SUPPLEMENTAL CRANBERRY OPERATIONS						
Twp	Rng	Mer	Sec	Q-Q	GLot	Acres
31 S	15 W	WM	32	NW SW		14.3
31 S	15 W	WM	32	SW SW		4.4
31 S	15 W	WM	32	NW SE		5.0
32 S	15 W	WM	5	NW NW	4	9.3

Measurement, recording and reporting conditions:

- A. The water user shall maintain the meter or measuring device in good working order.
- B. The water user shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the water user to keep and maintain a record of the amount (volume) of water used and may require the water user to report water use on a periodic schedule as established by the Director. In addition, the Director may require the water user to report general water use information, the periods of water use and the place and nature of use of water under the right. The Director may provide an opportunity for the water user to submit alternative reporting procedures for review and approval.

Groundwater production from the well shall be from no shallower than 60 feet below land surface.

Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements. The static water levels shall be measured in the month of March. The additional measurements may be required in a different month other than March. Reports shall be submitted to the Department within 30 days of measurement. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well if annual water level measurements reveal any of the following events:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The reference level for the well, against which any future measurements will be compared, is 7.66 feet below land surface.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The wells shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a useable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the wells at all times.

The Director may require water level or pump test results every ten years.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.


This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued APR 10 2015


Dwight French
Water Right Services Division Administrator, for
Director
Oregon Water Resources Department