

STATE OF OREGON

COUNTY OF LAKE

CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

ERNEST D. SHUFFIELD  
P.O. BOX 85  
SUMMER LAKE, OR 97640

confirms the right to use the waters of A WELL in the ANA RIVER BASIN for IRRIGATION OF 46.98 ACRES.

This right was perfected under Permit G-13246. The date of priority is MAY 28, 1996. The amount of water to which this right is entitled is limited to an amount actually used beneficially, and shall not exceed 0.587 CUBIC FOOT PER SECOND or its equivalent in case of rotation, measured at the well.

The period of use is March 1 through October 31.

The well is located as follows:

| Twp  | Rng  | Mer | Sec | Q-Q   | Measured Distances                                                     |
|------|------|-----|-----|-------|------------------------------------------------------------------------|
| 29 S | 17 E | WM  | 24  | SE NW | SOUTH 43° 40' 4" EAST 1923.52 FEET FROM<br>THE NW CORNER OF SECTION 24 |

The amount of water used for irrigation, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second, or its equivalent for each acre irrigated, and shall be further limited to a diversion of not to exceed 3.0 acre-feet per acre for each acre irrigated during the irrigation season of each year.

A description of the place of use to which this right is appurtenant is as follows:

| IRRIGATION |      |     |     |       |       |
|------------|------|-----|-----|-------|-------|
| Twp        | Rng  | Mer | Sec | Q-Q   | Acres |
| 29 S       | 17 E | WM  | 24  | NE NW | 22.50 |
| 29 S       | 17 E | WM  | 24  | SW NW | 1.98  |
| 29 S       | 17 E | WM  | 24  | SE NW | 22.50 |
| Total      |      |     |     |       | 46.98 |

This is a final order in other than a contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080, you may petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Measurement, recording and reporting conditions:

- A. The water user shall maintain the meter or other suitable measuring device in good working order.
- B. The water user shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the water user to keep and maintain a record of the amount (volume) of water used and may require the water user to report water use on a periodic schedule as established by the Director. In addition, the Director may require the water user to report general water use information, the periods of water use and the place and nature of use of water under the right. The Director may provide an opportunity for the water user to submit alternative reporting procedures for review and approval.

To monitor the effect of water use from the well authorized under this right, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The reference level against which any future measurements will be compared is 23.0 feet below land surface.

Measurements must be made according to the following schedule:

The water user shall submit seven consecutive annual reports of static water level measurements. All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of two or more feet per year for five consecutive years; or
- (B) A water level decline of 10 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 10 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The well shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge to determine the water level elevation in the well at all times.

The Director may require water level or pump test results every ten years.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

This right is for the beneficial use of water without waste on the lands or place of use described. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

This certificate corrects a scrivener's error for the correct Basin and location of the well, and describes that portion of the water right confirmed by Certificate 87790, State Record of Water Right Certificates, NOT modified by the provisions of an order of the Water Resources Director entered DEC 30 2015, approving Transfer Application T- 12089.

The issuance of this superseding certificate does not confirm the status of the water right in regard to the provisions of ORS 540.610 pertaining to forfeiture or abandonment.

WITNESS the signature of the Water Resources Director, affixed DEC 30 2015.



Dwight French, Water Right Services Administrator, for  
Thomas M. Byler, Director  
Oregon Water Resources Department