

STATE OF OREGON
COUNTY OF CLATSOP
CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

OREGON MILITARY DEPARTMENT
PO BOX 14350
SALEM OR 97309-5047

confirms the right to the use of water perfected under the terms of Permit G-16125. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the point of diversion from the source. The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-16514

SOURCE OF WATER: WELL 2 AND WELL 3 IN NEACOXIE CREEK BASIN

PURPOSE OR USE: QUASI-MUNICIPAL USE

The maximum rates and periods of use allowed are as follows:

Period of Use	Maximum Rate (CFS)
November 1 through June 30	0.668
July 1 through July 31	0.443
August 1 through August 31	0.289
September 1 through September 30	0.41
October 1 through October 31	0.485

PERIOD OF USE: YEAR ROUND

DATE OF PRIORITY: AUGUST 23, 2005

The wells are located as follows:

Twp	Rng	Mer	Sec	Q-Q	DLC	Measured Distances
7 N	10 W	WM	5	NE NE	46	WELL 2 - 720 FEET SOUTH AND 400 FEET WEST FROM NE CORNER, SECTION 5
7 N	10 W	WM	5	NE NE	46	WELL 3 - 358 FEET SOUTH AND 475 FEET WEST FROM NE CORNER, SECTION 5

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

A description of the place of use is as follows:

Twp	Rng	Mer	Sec	Q-Q	DLC
7 N	10 W	WM	4	NW NE	47
7 N	10 W	WM	4	SW NE	47
7 N	10 W	WM	4	SW NE	46
7 N	10 W	WM	4	NE NW	47
7 N	10 W	WM	4	NW NW	46
7 N	10 W	WM	4	NW NW	47
7 N	10 W	WM	4	SW NW	46
7 N	10 W	WM	4	SE NW	46
7 N	10 W	WM	4	SE NW	47
7 N	10 W	WM	4	NE SW	46
7 N	10 W	WM	4	NW SW	46
7 N	10 W	WM	4	SW SW	45
7 N	10 W	WM	4	SW SW	46
7 N	10 W	WM	4	SE SW	45
7 N	10 W	WM	4	SE SW	46
7 N	10 W	WM	4	NW SE	46
7 N	10 W	WM	4	SW SE	45
7 N	10 W	WM	4	SW SE	46
7 N	10 W	WM	5	NE NE	46
7 N	10 W	WM	5	NW NE	46
7 N	10 W	WM	5	SW NE	46
7 N	10 W	WM	5	SE NE	46
7 N	10 W	WM	5	NE SE	46
7 N	10 W	WM	5	SE SE	45
7 N	10 W	WM	5	SE SE	46
7 N	10 W	WM	8	NE NE	45
7 N	10 W	WM	9	NW NE	45
7 N	10 W	WM	9	NE NW	45
7 N	10 W	WM	9	NW NW	45
8 N	10 W	WM	32	SW SE	37
8 N	10 W	WM	32	SE SE	37
8 N	10 W	WM	33	SW SW	37
8 N	10 W	WM	33	SW SW	38
8 N	10 W	WM	33	SE SW	38

Measurement, recording and reporting conditions:

- A. The water user shall maintain the totalizing flow meter(s) in good working order as identified in OAR 690-507-645(1) through (3). The water user shall keep a complete record of the amount of water used each month. The water user shall submit a report which includes the recorded water use measurements to the Department at its request. The water user may be required to report annually or more frequently as may be required by the Director. Further, the Director may require the water user to report general water use information, including the place and nature of use of water under the right.
- B. The water user shall allow the watermaster access to the meter or measuring device; provided however, where any meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

The wells shall produce groundwater only from the unconsolidated sand groundwater reservoir.

The combined quantity of water diverted at the new points of appropriation shall not exceed the quantity of water lawfully available at the original points of appropriation.

To monitor the effect of water use from the well(s) authorized under this right, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of April. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Following the first year of water use, the user shall submit seven consecutive annual reports of static water level measurements. Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

The reference levels against which any future measurements will be compared is 53.84 feet below land surface for Well 2 and 61.38 feet below land surface for Well 3.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) Annual water level measurements reveal an average water level decline of three or more feet per year for five consecutive years; or
- (B) Annual water level measurements reveal a water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) Annual water level measurements reveal a water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non or restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The water user shall measure and report to the Water Resources Department water levels for each well in January, April, July, and October of each year for the first seven years of each well's use.

The water user shall measure, record, and report to the Water Resources Department specific conductance values for groundwater samples pumped from each well in January, April, July, and October of each year for the first seven years of each well's use.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this right, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interference.

The wells shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine the water level elevation in the well at all times.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to the agreement.

The Director may require water level or pump test results every ten years.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.


This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued MAR 09 2016



Dwight French
Water Right Services Division Administrator, for
Thomas M. Byler, Director
Oregon Water Resources Department