

STATE OF OREGON
 COUNTY OF KLAMATH
 CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

THE DIAMOND PEAKS AT LEISURE WOODS I AND II HOMEOWNERS ASSOCIATION INC.
 PO BOX 1021
 CRESCENT LAKE OR 97733

confirms the right to the use of water perfected under the terms of Permit G-17618. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the point of diversion from the source. The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17445

SOURCE OF WATER: A WELL (KLAM 340) IN CRESCENT CREEK BASIN

PURPOSE OR USE: QUASI-MUNICIPAL

MAXIMUM RATE: 0.13 CUBIC FOOT PER SECOND, WITH A MAXIMUM VOLUME OF 12.6 ACRE FEET

PERIOD OF USE: YEAR-ROUND

DATE OF PRIORITY: DECEMBER 22, 2010

The well is located as follows:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
24 S	7 E	WM	7	NE SW	120 FEET SOUTH AND 1065 FEET WEST FROM C1/4 CORNER, SECTION 7

A description of the place of use is as follows:

Twp	Rng	Mer	Sec	Q-Q
24 S	7 E	WM	7	NW NE
24 S	7 E	WM	7	SW NE
24 S	7 E	WM	7	SE NE
24 S	7 E	WM	7	NE NW
24 S	7 E	WM	7	SE NW
24 S	7 E	WM	7	NE SE
24 S	7 E	WM	7	NW SE
24 S	7 E	WM	7	SE SE

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

Measurement, recording and reporting conditions:

- A. The water user shall maintain the totalizing flow meter at each point of appropriation in good working order. The water user shall keep a complete record of the amount of water used each month, and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the water user to report general water-use information, including the place and nature of use of water under the right.
- B. The water user shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice. The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on this right. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Static Water Level Conditions

The water user shall report annual March static water-level measurements. The static water level shall be measured in the month of March. Annual measurements are required whether not the well is used. The Director may require the water user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- (A) Associate each measurement with an owner's well name or number a Department well log ID; and
- (B) Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method of measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- (B) Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- (C) Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The reference level against which any future measurements will be compared is 19.5 feet below land surface.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

Groundwater Mitigation Conditions:

- 1. Mitigation Obligation: 5.0 acre-feet of mitigation water in the Little Deschutes Zone of Impact
- 2. Mitigation Source: 5.0 mitigation credits from mitigation project MP-168, established by instream water right certificate 90238, within the Little Deschutes Zone of Impact.

3. Regulation of the use and/or cancellation of this right or subsequent certificate(s) will occur if the required mitigation is not maintained.
4. The water user shall provide additional mitigation if the Department determines that average annual consumptive use of the subject appropriation has increased beyond the originally mitigated amount.
5. If mitigation is from a secondary right for stored water from a storage project not owned or operated by the water user, the use of water under this right is subject to the maintenance and terms and conditions of a valid contract or satisfactory replacement, a copy of which must be on file in the records of the Water Resources Department.
6. Failure to comply with these mitigation conditions shall result in the Department regulating this certificate or subsequent certificate(s), and proposing to cancel the certificate or subsequent certificate(s).

Scenic Waterway Condition:

Use of water under authority of this right may be regulated if analysis of data available after the right is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right, or as those quantities may be reduced subsequently. However, the use of ground water allowed under the terms of this right will not be subject to regulation for Scenic Waterway flows, provided the required mitigation is maintained.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this right, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The wells shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine the water level elevation in the well at all times.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to the agreement.


The Director may require water level or pump test results every ten years.

This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued SEP 01 2017


Dwight French
Water Right Services Division Administrator, for
Thomas M. Byler, Director
Oregon Water Resources Department