

STATE OF OREGON

COUNTY OF HARNEY

CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

CHARLES EGGERT
 LOUANNA EGGERT
 18555 SW TETON AVE
 TUALATIN OR 97062

NORTHWEST FARM CREDIT SERVICES
 650 HAWTHORNE AVE SE SUITE 210
 SALEM OR 97301

confirms the right to the use of water perfected under the terms of Permit G-17991. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the point of diversion from the source. The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17146

SOURCE OF WATER: TEN WELLS IN HARNEY LAKE BASIN

PURPOSE or USE: IRRIGATION USE ON 37.6 ACRES

MAXIMUM RATE: 0.47 CUBIC FOOT PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: NOVEMBER 24, 2008

The wells are located as follows:

Twp	Rng	Mer	Sec	Q-Q	GLot	Measured Distances	Owner Well #
26 S	30 E	WM	03	NW NW	4	HARN 51765 – 6310 FEET SOUTH AND 415 FEET EAST FROM NW CORNER, SECTION 34, TOWNSHIP 25S RANGE 30E	10
26 S	30 E	WM	03	NW NW	4	HARN 51760 – 6340 FEET SOUTH AND 330 FEET EAST FROM NW CORNER, SECTION 34, TOWNSHIP 25S RANGE 30E	11
26 S	30 E	WM	04	NE NW	3	HARN 51445 – 6415 FEET SOUTH AND 2745 FEET WEST FROM NE CORNER, SECTION 33, TOWNSHIP 25S RANGE 30E	13
25 S	30 E	WM	29	SW SE		HARN 52121 – 635 FEET NORTH AND 1605 FEET WEST FROM SE CORNER, SECTION 29	16
25 S	30 E	WM	29	SW SE		HARN 52170 – 785 FEET NORTH AND 1630 FEET WEST FROM SE CORNER, SECTION 29	18

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

Twp	Rng	Mer	Sec	Q-Q	GLot	Measured Distances	Owner Well #
25 S	30 E	WM	33	SE NW		HARN 51817 – 2690 FEET SOUTH AND 2890 FEET WEST FROM NE CORNER, SECTION 33	12
25 S	30 E	WM	33	SE SE		HARN 51871 – 4314 FEET SOUTH AND 870 FEET WEST FROM NE CORNER, SECTION 33	14
25 S	30 E	WM	33	SE SE		HARN 51970 – 4314 FEET SOUTH AND 920 FEET WEST FROM NE CORNER, SECTION 33	15
25 S	30 E	WM	34	SE SW		HARN 51272 – 4725 FEET SOUTH AND 1877 FEET EAST FROM NW CORNER, SECTION 34	7
26 S	30 E	WM	03	NW NW	4	HARN 52154 – 6300 FEET SOUTH AND 440 FEET EAST FROM NW CORNER, SECTION 34, TOWNSHIP 25S RANGE 30E	17

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 3.0 acre-feet for each acre irrigated during the irrigation season of each year.

A description of the place of use is as follows:

Twp	Rng	Mer	Sec	Q-Q	Acres
25 S	30 E	WM	34	SW NW	0.2
25 S	30 E	WM	34	SE NW	8.2
25 S	30 E	WM	34	NE SW	26.2
25 S	30 E	WM	34	NW SW	3.0

Measurement, recording, and reporting conditions:

- A. The water user shall maintain, in good working order, a totalizing flow meter or other suitable measuring device as approved by the Director at each point of appropriation.
- B. The water user shall allow the watermaster access to the meter or measuring device; provided however, where any meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the water user to keep and maintain a record of the amount (volume) of water used, and may require the water user to report water use on a periodic schedule as established by the Director. In addition, the Director may require the water user to report general water-use information, the period of water use and the place and nature of use of water under the right.
- D. The Director may provide an opportunity for the water user to submit alternative measuring and reporting procedure for review and approval.

The quantity of water diverted at the new points of appropriation (wells), together with that diverted at the old point of appropriation, shall not exceed the quantity of water available from the original point of appropriation located as follows:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
25 S	30 E	WM	33	SE SW	HARN 51448 – 4423 FEET SOUTH AND 2750 FEET WEST FROM NE CORNER, SECTION 33

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the right. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The water user shall report annual March static water-level measurements whether or not the well is used. The reference level against which future measurements will be compared is 97.88 feet below ground surface for Well HARN 51448. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045.

The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The water user shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

The well(s) shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine the water level elevation in the well at all times.

The use may be restricted if the quality of the downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.


The Director may require water level or pump test results every ten years.

This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued OCT 01 2021.



Dwight French
Water Right Services Division Administrator, for
Thomas M. Byler, Director
Oregon Water Resources Department