

STATE OF OREGON
COUNTY OF HARNEY
CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

JUNIPER BASIN RANCH LLC
ATTN: JON WARREN
PO BOX 491942
REDDING CA 96049-1942

confirms the right to the use of water perfected under the terms of Permit G-16975. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the wells. The specific limits and conditions of the use are listed below.

SOURCE: THREE WELLS (HARN 51409 AND HARN 51783) AND WELL 3 IN SAGE HEN CREEK BASIN

USE: IRRIGATION OF 240.0 ACRES

RATE: 3.0 CUBIC FEET PER SECOND (CFS), FURTHER LIMITED TO 1.69 CFS FROM WELL 1 (HARN 51409) AND 1.33 CFS FROM WELL 2 (HARN 51783), AND 1.82 CGS FROM WELL 3, A MAXIMUM CUMULATIVE TOTAL FROM ALL WELLS NOT TO EXCEED 3.0 CFS

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

PRIORITY DATE: JANUARY 25, 2008

The wells are located as follows:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
25 S	31 E	WM	18	SW SE	WELL 2 (HARN 51783) (ORIGINAL) - 660 FEET NORTH AND 2935 FEET EAST FROM SW CORNER, SECTION 18
25 S	31 E	WM	19	NW NE	WELL 1 (HARN 51409) (ORIGINAL) - 830 FEET SOUTH AND 3033 FEET EAST FROM NW CORNER, SECTION 19
25 S	31 E	WM	19	NW NE	WELL 3 (ADDITIONAL) - 885 FEET SOUTH AND 3060 FEET EAST FROM NW CORNER, SECTION 19

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ~~ONE-EIGHTIETH~~ of one cubic foot per second and 3.0 acre-feet per acre for each acre irrigated during the irrigation season of each year.

A description of the place of use is as follows:

IRRIGATION						
Twp	Rng	Mer	Sec	Q-Q	GLot	Acres
25 S	31 E	WM	18	NE SW		14.1
25 S	31 E	WM	18	SE SW		36.0
25 S	31 E	WM	18	NW SE		0.8

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.482. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.482. Pursuant to ORS 183.482, ORS 536.075 and OAR 137-003-0675, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

IRRIGATION						
Twp	Rng	Mer	Sec	Q-Q	GLot	Acres
25 S	31 E	WM	18	SW SE		29.6
25 S	31 E	WM	18	SE SE		26.9
25 S	31 E	WM	19	NE NE		33.6
25 S	31 E	WM	19	NW NE		37.5
25 S	31 E	WM	19	SW NE		3.2
25 S	31 E	WM	19	SE NE		1.9
25 S	31 E	WM	19	NE NW		29.2
25 S	31 E	WM	19	NW NW	1	8.9
25 S	31 E	WM	19	SW NW	2	5.4
25 S	31 E	WM	19	SE NW		12.9

The quantity of water diverted at the new additional point of appropriation (Well 3), together with that diverted at the original points of appropriation (Well 1 (HARN 51409) and Well 2 (HARN 51783)), shall not exceed the quantity of water lawfully available at the original points of appropriation (Well 1 (HARN 51409) and Well 2 (HARN 51783)),

Water use measurement conditions:

- a) The water user shall maintain a totalizing flow meter or other suitable measuring device, as approved by the director, in good working order, at each point of appropriation (new and existing).
- b) The water user shall keep a complete record of the amount of water used each month, and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the water user to report general water-use information, including the place and nature of use of water under the right.
- c) The water user shall allow the watermaster access to the meters or measuring devices; provided however, where the meters or measuring devices are located within a private structure, the Watermaster shall request access upon reasonable notice.
- d) The Director may provide an opportunity for the water user to submit alternative measuring procedures for review and approval.

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the right. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The water user shall report annual March static water-level measurements. Annual measurements are required whether or not the well is used. The reference level against which future measurements will be compared is 140.84 feet below ground surface for Well 1 (HARN 51409) and 161.00 feet below ground surface for Well 2 (HARN 51783). The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with a well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the wells if any of the following events occur:

- A. Annual water-level measurements reveal an average water level-decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

The water user shall ensure that the well has been assigned an OWRD Well ID Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall not be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this right, then use of water from the wells shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The wells shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge to determine the water level elevation in the well at all times.

The use may be restricted if the quality of downstream waters decrease to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

The Director may require water level or pump test results every ten years.

This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.


Water shall be acquired from the same aquifer (water source) as the original points of appropriation.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

This certificate is issued to confirm an ADDITIONAL POINT OF APPROPRIATION approved by an order of the Water Resources Director entered May 18, 2021, at Special Order Volume 120, Page 600, approving Transfer Application T-13202, supersedes Certificate 94108, State record of Water Right Certificates.

NOV 17 2023

Issued _____

A handwritten signature in dark ink, appearing to read "Dwight French", is written over a horizontal line.

Dwight French
Water Right Services Division Administrator, for
Douglas E. Woodcock, Acting Director
Oregon Water Resources Department