

STATE OF OREGON
 COUNTY OF CROOK
 CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

SHOTGUN RANCH LLC
 ATTN: JOE PAPINEAU
 40791 SE SHOTGUN RD
 POST OR 97752

confirms the right to the use of water perfected under the terms of Permit G-18479. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the point of diversion from the source. The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-18112

SOURCE OF WATER: WELL 4, WELL 5, AND WELL 6 IN DRAKE CREEK BASIN

PURPOSE OR USE: SUPPLEMENTAL IRRIGATION OF 41.0 ACRES

MAXIMUM RATE: 0.386 CUBIC FOOT PER SECOND (CFS), FURTHER LIMITED TO 0.32 CFS FROM WELL 4, 0.386 CFS FROM WELL 5, AND 0.386 CFS FROM WELL 6, NOT TO EXCEED A COMBINED RATE OF 0.386 CFS BETWEEN THE WELLS

PERIOD OF USE: APRIL 15 THROUGH OCTOBER 15

DATE OF PRIORITY: JUNE 29, 2015

WELL LOCATIONS:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
17 S	20 E	WM	3	SW SW	WELL 4 (ORIGINAL) - 1180 FEET NORTH AND 5 FEET WEST FROM SW CORNER, SECTION 3
17 S	20 E	WM	3	SW SW	WELL 5 (ADDITIONAL) - 1070 FEET NORTH AND 960 FEET EAST FROM SW CORNER, SECTION 3
17 S	20 E	WM	3	SW SW	WELL 6 (ADDITIONAL) - 1040 FEET NORTH AND 840 FEET EAST FROM SW CORNER, SECTION 3

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 3.0 acre-feet for each acre irrigated during the irrigation season of each year.

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SUPPLEMENTAL IRRIGATION					
Twp	Rng	Mer	Sec	Q-Q	Acres
17 S	20 E	WM	3	SW SW	6.2
17 S	20 E	WM	4	SE SE	30.4
17 S	20 E	WM	9	NE NE	4.2
17 S	20 E	WM	10	NW NW	0.2

Measurement, recording and reporting conditions:

- A. The water user shall maintain a totalizing flow meter or other suitable measuring device approved by the Director in good working order, at each point of appropriation.
- B. The water user shall allow the Watermaster access to the meters or measuring devices; provided however, where the meters or measuring devices is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The water user shall keep a complete record of the volume of water diverted each month, and shall submit a report which includes water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the water user to report general water-use information, including the place and nature of use of water under the right.
- D. The Director may provide an opportunity for the water user to submit alternative measuring and reporting procedures for review and approval.

The combined quantity of water diverted at the new additional point of appropriation (Well 5 and Well 6), together with that diverted at the old point of appropriation (Well 4), shall not exceed the quantity of water lawfully available at the original point of appropriation (Well 4).

Water shall be acquired from the same aquifer as the original point of appropriation.

Static Water Level Condition

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the right. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The water user shall report annual March static water-level measurements whether or not the well is used. The reference level against which future measurements will be compared are 304.92 feet below ground surface for Well 4, 203.7 feet below ground surface for Well 5, and 145.3 feet below ground surface for Well 6. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The Department may require the discontinuance of groundwater use, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

Well Construction Condition

The well must be continuously cased and continuously sealed to at least 50 feet below land surface to ensure the well is completed in bedrock.

Groundwater production shall be from no shallower than 50 feet below land surface.

Well Identification Tag Condition

The water user shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

If substantial interference with a surface water or a senior water right occurs due to withdrawal of water from any well listed on this right, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port adequate to determine water level-elevation in the well at all times.

The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.


The Director may require water-level or pump-test data every ten years.

This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued **FEB 16 2024**



Dwight French
Water Right Services Division Administrator, for
Douglas E. Woodcock, Acting Director
Oregon Water Resources Department