

STATE OF OREGON

COUNTY OF LAKE

CERTIFICATE OF WATER RIGHT

THIS CERTIFICATE ISSUED TO

SURPRISE VALLEY ELECTRIFICATION CORP
800 W 12TH STREET
ALTURAS CA 96101

confirms the right to the use of water perfected under the terms of Permit G-17434. The amount of water used to which this right is entitled is limited to the amount used beneficially, and shall not exceed the amount specified, or its equivalent in the case of rotation, measured at the point of diversion from the source. The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17890

SOURCE OF WATER: SVE-4 WELL (LAKE 52506/L111501) IN CHEWAUCAN RIVER BASIN

PURPOSE OR USE: INDUSTRIAL/MANUFACTURING USES

MAXIMUM RATE: 0.393 CUBIC FOOT PER SECOND

PERIOD OF USE: YEAR-ROUND

DATE OF PRIORITY: SEPTEMBER 9, 2014

WELL LOCATIONS:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
33 S	18 E	WM	23	SW NE	PRODUCTION WELL - SVE-4 WELL (LAKE 52506) - 60 FEET NORTH AND 1680 FEET WEST FROM E1/4 CORNER, SECTION 23
33 S	18 E	WM	23	SW NE	MONITORING WELL - SVE-5 WELL (LAKE 52683) - 70 FEET NORTH AND 1580 FEET WEST FROM E1/4 CORNER, SECTION 23

THE PLACE OF USE IS LOCATED AS FOLLOWS:

Twp	Rng	Mer	Sec	Q-Q
33 S	18 E	WM	23	NE SE

NOTICE OF RIGHT TO PETITION FOR RECONSIDERATION OR JUDICIAL REVIEW

This is an order in other than a contested case. This order is subject to judicial review under ORS 183.484 and ORS 536.075. Any petition for judicial review must be filed within the 60-day time period specified by ORS 183.484(2). Pursuant to ORS 183.484, ORS 536.075 and OAR 137-004-0080, you may petition for judicial review and petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied. In addition, under ORS 537.260 any person with an application, permit or water right certificate subsequent in priority may jointly or severally contest the issuance of the certificate within three months after issuance of the certificate.

Measurement devices, and recording/reporting of annual water use conditions:

- A. The water user shall maintain the totalizing flow meter in good working order at each point of appropriation.
- B. The water user shall allow the watermaster access to the device; provided however, where any device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The water user shall keep a complete record of the volume of water diverted each month, and shall submit a report which includes water-use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the water user to report general-water use information, including the place and nature of use of water under the right.
- D. The Director may provide an opportunity for the water user to submit alternative reporting procedures for review and approval.

The monitoring Well SVE-5 is located within 100 feet east of production Well SVE-4.

At minimum, the static groundwater level at the monitoring well shall be measured monthly by hand to the nearest 0.10 foot and reported to the Department monthly on forms provided by or specified by the Department. Any use of a non-hand measurement water-level recorder device (shaft encoder, transducer, or other device) shall be in addition to the monthly hand measurement.

The reference level against which future measurements for Well SVE-4 will be compared is 92.59 feet below ground surface.

All measurements shall be made monthly by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, a hydrogeologist in the Department's Groundwater Section located in Salem. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The Department may require the discontinuance of groundwater use, or reduce the rate or volume of withdrawal, from the well(s) if any of the following events occur:

- A. A monthly measurement is not made; or
- B. The monthly measurement is not submitted to the Department monthly or received by the Department monthly; or
- C. Annual water-level measurements reveal an average water-level decline of two or more feet per year for five consecutive years; or
- D. Annual water-level measurements reveal a water-level decline of 10 or more feet in fewer than five consecutive years; or
- E. Annual water-level measurements reveal a water-level decline of 10 or more feet; or
- F. Hydraulic interference leads to a decline of 10 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this right. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

Dedicated Measuring Tube: Wells with pumps shall be equipped with a minimum 3/4-inch diameter, unobstructed, dedicated measuring tube pursuant to figure 200-5 in OAR 690-200.

The maximum volume allowed per month shall be equal to or less than 228.5 gallons per minute (43,986 cubic feet per day = 1.01 acre-feet per day) times the number of days in the month.

The water user shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

Failure to comply with any of the provisions of this right may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the right.

If substantial interference with surface water or a senior water right occurs due to withdrawal of water from any well listed on this right, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port adequate to determine water-level elevation in the well at all times.

The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

The Director may require water-level or pump-test data every ten years.

This right is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The right to the use of the water for the above purpose is restricted to beneficial use on the place of use described.

Issued JUL 14 2026.



Katherine Ratcliffe
Water Right Services Division Administrator, for
Ivan Gall, Director
Oregon Water Resources Department