

C
O
L
U
M
B
I
A
R
I
V
E
R

CITY
OF
RAINIER

FIELD NOTES OF THE
FOX CREEK PIPE LINE
by Orrin Backus

STA.	BEARING	DISTANCE
0		
1	N 60° 30' E	490'
2	N 20° 30' E	146'
3	N 4° 0' E	242'
4	N 1° 0' E	160'
5	N 5° 25' E	100'
6	N 18° 45' E	120'
7	N 11° 30' W	242'
8	N 24° 45' W	635'
9	N 29° 30' W	288'
10	N 18° 30' W	354'
11	N 1° 30' W	158'
12	N 18° 0' W	673'
13	N 9° 0' W	673'
14	N 11° 10' E	945'
15	N 15° 30' E	220'
16	N 15° 10' E	170'
17	N 11° 7' E	173'
18	N 13° 38' W	222'
19	N 22° 7' E	120'
20	N 46° 37' E	96'
	Reservoir Inlet	

CITY RESERVOIR 125 MG RECEIVING TANK

8" PIPE LINE FROM DAM

LIMITS OF DISTRIBUTION SYSTEM SERVED BY FOX CREEK SUPPLY

Sec 22 Sec 27
Sec 21 Sec 28

Sec 21 Sec 28
Sec 20 Sec 29

Sec 16 Sec 21
Sec 17 Sec 20

I WARRIN W. CLARK of SALEM, OREGON, do hereby certify that the location of the Monument for the new dam was made from notes taken during an actual survey made by me on JANUARY 28, 1952; that the monument shown on this map consisting of a 1 inch iron pipe is 3730.62' EAST, 1240.11' SOUTH from N.W. COR. of SEC. 28, T7 N, R2 W, W.M. U.S. LAND SURVEY

NOTE: THIS MAP IS A REPRODUCTION OF A MAP PREPARED BY ORRIN BACKUS, CIVIL ENGINEER, IN APRIL 1911, TO ACCOMPANY APPLICATION NO. 1300, PERMIT 674, NOW FILED IN THE OFFICE OF THE STATE ENGINEER. THE AREA OF USE HAS BEEN EXTENDED OVER THE ORIGINALLY SHOWN AND THE LOCATION OF A DAM TO BE CONSTRUCTED HAS BEEN ADDED. THE NEW DAM LOCATION IS THE SAME AS THE DAM NOW IN USE, WHICH DAM WAS CONSTRUCTED ABOUT 1931.

CITY OF RAINIER, ORE.
LOCATION MAP
WATER SUPPLY & DISTRIBUTION

SCALE 1"=400'	DATE: JAN. 30, 1952	J.O. 5113-45
DSGN.	CLARK & GROFF ENGINEERS	SHEET 1
DWG.	3245 S COMMERCIAL STREET	OF 1
CHK	SALEM, OREGON	