SPAUR RANCH SMALL CONDUIT EXEMPTION

LOCATED IN THE SOUTHWEST ONE-QUARTER OF SECTION 31 TOWNSHIP 1 NORTH, RANGE 43 EAST WILLAMETTE MERIDIAN

> MAG. DEC. 17°30' EAST

(1990)

SCALE: 1"=10"

WALLOWA COUNTY, OREGON

RECEIVED

DEC 16 2010

WATER RESOURCES DEPT SALEM, OREGON

LOCATION MAP

NOT TO SCALE

CERTIFICATION:

THIS DRAWING IS PART OF THE APPLICATION FOR LICENSE MADE BY THE UNDERSIGNED THIS DAY OF

SURVEY POINTS

POINT NUMBER NORTHING

PROJECT AREA AND BOUNDARY

SPAUR RANCH

POWERHOUSE (PROJECT

BOUNDARY)

DESCRIPTION

COORDINATE VALUES EXPRESSED IN INTERNATIONAL FEET

688,482 INT.FT. 688,470 INT.FT. 688,458 INT.FT. 688,470 INT.FT.

8,972,513 INT.FT. 8,972,525 INT.FT. 8,972,514 INT.FT. 8,972,502 INT.FT.

BUILDING CORNER BUILDING CORNER BUILDING CORNER BUILDING CORNER

REGISTERED **PROFESSIONAL** LAND SURVEYOR AB/ku

OREGON JANUARY 20, 1998 MICHAEL B. POSADA

EXPIRES: 12-31- /O DATED: 04-05-10


SURVEY DATUM

THE HORIZONTAL DATUM FOR THE COORDINATE VALUES SHOWN IS THE OREGON STATE PLANE COORDINATE SYSTEM, NORTH ZONE NAD 83.

- THE COORDINATE VALUES SHOWN ARE POSITIONALLY ACCURATE TO WITHIN ± 40 FEET.
- THE PHYSICAL ADDRESS OF SPAUR RANCH IS 68832 ALLEN CANYON LOOP, LOSTINE OR. 97857
- THE WALLOWA COUNTY TAX LOT PARCEL NUMBER IS OIN 43E TL# 8400
- SPAUR RANCH IS LOCATED IN THE SOUTHWEST ONE-QUARTER OF SECTION 31, TOWNSHIP I NORTH, RANGE 43 EAST, WILLAMETTE MERIDIAN.



IS DRAWING HAS BEEN REDUCED 50%. ADJUST SCALE ACCORDINGLY. BARSCALE SHOWN IS ACCURATE



VICINITY MAP

APRIL 5, 2010

EXHIBIT: G FIGURE: 1 PROJECT NAME: SPAUR RANCH SMALL CONDUIT EXEMPTION

PROJECT AREA AND **BOUNDARY SCALE: 1" = 10"**





Spaur Ranch Small Conduit Hydroelectric Project

PROJECT INTRODUCTION, DESIGN, AND ENVIRONMENTAL IMPACT ALEM, OR

Project Introduction

Over the past year, Spaur Ranch in conjunction with Renewable Energy Solutions, has undertaken feasibility analyses to determine the economic viability of installing a micro- hydroelectric facility on Spaur Ranch in Wallowa County, Oregon. The project would be located in SW ¼ Township 1 N, Range 43 E, Section 31, W.M, Wallowa County, Oregon (see enclosed maps). The proposed facility would be located on an existing, piped-irrigation conduit and would generate electricity via non-consumptive use of irrigation water flowing through the Ranch. No additional water would be diverted for the project.

System Design

The proposed Spaur Ranch Microhydro Project will include: (1) an existing 800-yard-long, 15-inch-diameter pipe that reduces to an existing 200-yard-long, 10-inch-diameter pipe, conveying water from the West Side Irrigation Ditch into an existing building containing an 11 kW pelton wheel turbine; (2) a short tailrace, conveying the water back into the irrigation canal; (3) appurtenant facilities. The power from the proposed project will be net metered, connected to the interstate grid through Pacific Power. The proposed project will not occupy any tribal or federal lands.

The meter is currently located at the building that also the terminus of the 10 inch water conveyance. Therefore transmission lines will not be necessary.

Environmental Impact

The West Side Ditch that conveys the water used in the project originates at the Lostine River, whose drainage area is 70.9 square miles. Monthly stream flow data follows. The project does not include additional civil work at the point of diversion at the river, and will not use any water storage. No additional piping or civil work is necessary at the project site. The project will use water already flowing through the existing conveyance.

There are multiple fish screens on the project. The West Side Ditch Company maintains a Fish Wheel at the diversion point from the Lostine River. The Ditch Company President responsible for maintenance is Leonard Post. An additional fish screen is located at the 15" pipe intake. The project owner, Vern Spaur, and other individuals on the irrigation conduit maintain the screen twice per day during the irrigation season. The screen is maintained via a broom and/ or a flush gate. The existing screens are effective and well-maintained. There are no additional screens proposed for the project.

Project Source Flow Data

No additional water will be withdrawn from the Project Source. The project is a non-consumptive use of water.

