

Registration Statement

OF CLAIMANT OF RIGHT TO APPROPRIATE GROUND WATER

TO THE STATE ENGINEER OF OREGON:

I, Sister Dolores Mary
of Marylhurst County of Clackamas
(Mailing address)

State of Oregon, do hereby make application for a certificate of registration as evidence of a right to appropriate ground water.

1. Source from which water is withdrawn is pump well
(Flowing well, pump well, infiltration trench, or tunnel)

2. Location is: 1 (one) mile south of Oswego
(Approximate distance and direction from nearest city or town)

and is more particularly described as follows:

(a) 1,076.3 feet S. 19°28'W. to 1/4 Corner common to Sections 11 & 14
(Give distance and bearing to corner of section or other legal subdivision)

being within NE 1/4 of NW 1/4 of Sec. 14, Twp. 2 S. Rge. 1 E.
(Smallest legal subdivision) (N. or S.) (E. or W.)

or (b) within limits of recorded platted property, town or city:

in Lot _____, Block _____ of _____
(Name of plat or addition)

County of _____
(If within city or town, give name)

3. Construction Work was begun on March 10, 1927; was completed on September 29, 1927
(Date) (Date)

and the ground water claimed was first used for the purposes set out below on October 1927
(Date)

since which time the water has been used continuously
(Continuously or intermittently)

from October 1927 to July 1958
(Date) (Date)

4. Quantity of water claimed and used is 55 gallons per minute; 74 acre feet per year.

5. Purpose or Purposes for which water is used domestic and irrigation

(Domestic, irrigation, municipal, manufacturing, industrial, etc.)

6. Description of Well: Depth 500 feet. Type dug
(Dug or drilled)

diameter 12 inches. Elevation of ground at well site 144 feet, mean sea level.
(As near as known)

Depth to water table 280 feet.

7. Capacity of Well: 55 g.p.m. with not known feet drawdown. (no air line)

_____ g.p.m. with _____ feet drawdown.

Date of test July 9, 1958
October 1927 : 500 g.p.m.

If Flowing Well: Measured discharge _____ g.p.m. on _____
(Date)

Shut-in pressure at ground surface _____ lbs. per sq. in. on _____
(Date)

Water is controlled by _____
(Cap, valve, etc.)

8. Casing: (Give diameter, commercial specifications and depth below ground surface of each casing size.)

12 inch diameter steel pipe from surface to 38½ feet
 inch diameter from to feet
 inch diameter from to feet
 inch diameter from to feet

Describe and show depth of shoe, plug, adapter, liner or other details:

9. Perforated Casings or Screens:

(Number per foot and size of perforations, or describe screen) from to
 from to
 from to
 from to

10. Log of Well: (Describe each stratum or formation clearly, indicate if water bearing, and give thickness and depth as indicated.)

MATERIAL	Thickness (Feet)	Depth to Bottom (Feet)
Soil	20	20
Sandy soil	13	33
Shale	5½	38½
Gray basalt	13½	52
Black basalt	11	63
Gray basalt	17	80
Honeycomb rock	4	84
Gray basalt	20	104
Black basalt	8	112
Honeycomb rock	9	121
Shale and coal	3	124
Gray basalt	12	136
Porous gray basalt	169	305
Black basalt	9	314
Brown volcanic honeycomb	21	335
Hard brown volcanic	22	357
Red volcanic honeycomb	21	378
Hard gray basalt	31	409
Black honeycomb	15	424
Brown honeycomb	26	450
Hard brown rock	34	484
Black basalt	14	498
Black honeycomb	2	500

8. Casing: (Give diameter, commercial specifications and depth below ground surface of each casing size.)

12 inch diameter steel pipe from surface to 30½ feet
 inch diameter from to feet
 inch diameter from to feet
 inch diameter from to feet

Describe and show depth of shoe, plug, adapter, liner or other details:

9. Perforated Casings or Screens:

(Number per foot and size of perforations, or describe screen) from to
 from to
 from to
 from to

10. Log of Well: (Describe each stratum or formation clearly, indicate if water bearing, and give thickness and depth as indicated.)

MATERIAL	Thickness (Feet)	Depth to Bottom (Feet)
Soil	20	20
Sandy soil	13	33
Shale	5½	38½
Gray basalt	13½	52
Black basalt	11	63
Gray basalt	17	80
Honeycomb rock	4	84
Gray basalt	20	104
Black basalt	8	112
Honeycomb rock	9	121
Shale and coal	3	124
Gray basalt	12	136
Porous gray basalt	169	305
Black basalt	9	314
Brown volcanic honeycomb	21	335
Hard brown volcanic	22	357
Red volcanic honeycomb	21	378
Hard gray basalt	31	409
Black honeycomb	15	424
Brown honeycomb	26	450
Hard brown rock	34	484
Black basalt	14	498
Black honeycomb	2	500

If log of well is not available, give name and address of driller.....

11. Infiltration Trench: Covered or open.....

Dimensions: Length..... ft. Minimum depth..... ft. Maximum depth..... ft.

Bottom width..... ft. Discharge..... g.p.m. Date of test.....

12. Tunnel: Type of lining.....

Dimensions:.....
(Length, course, and cross sectional size)

Position of water bearing stratum with reference to portal of tunnel.....

Log of tunnel: (Preceding table for log of well may be used, if desired. Give footage from portal and character of materials, as pertinent.)

13. Pumping Equipment:

(a) Pump..... Pomona..... Capacity..... 300..... g.p.m.
(Make, type and size)


(b) Motor..... Westinghouse 30 hp.....
(Type and horsepower)

14. Location of area irrigated or to be irrigated, or place of use if for purposes other than irrigation.

Township North or South	Range E. or W. of Willamette Meridian	Section	Forty-acre Tract	Number Acres To Be Irrigated	Date of Reclamation
2 S	1 E	14	SW $\frac{1}{4}$ of NE $\frac{1}{4}$	Domestic: College 8 Buildings including Heating Plant and Swimming pool. Irrigation: 4 acres including cemetery.	October 1927
2 S	1 E	14	NW $\frac{1}{4}$ of NE $\frac{1}{4}$	Domestic: Convent, Rosecliff Hall, Sewage treatment plant. Irrigation: 9 acres	October 1927
2 S	1 E	14	NE $\frac{1}{4}$ of NW $\frac{1}{4}$	Domestic: Christie School, Laundry, Heating Plant, Men's Lodge, Chaplain's Residence, Farm Cottage, Swimming pool, Cattle barn. Irrigation: 7 acres.	October 1927
2 S	1 E	14	SE $\frac{1}{4}$ of NW $\frac{1}{4}$	Irrigation: 5 acres	October 1927

15. If the ground water supply is supplemental to an-existing water supply, identification of any application for a permit, permit, certificate or adjudicated right to appropriate water made or held by the registrant.

Township 2 S Range 1 E W.M. North 1/4 SEC. COR., 11 & 14



Locate well and acreage of irrigated land on plat.
Scale: 2" = 1 Mile

STATE OF OREGON

County of Clackamas } ss.

I, Sister Dolores Mary, being first duly sworn, do hereby certify that I have read the foregoing Registration Statement and that all of the items therein contained are true to the best of my knowledge and belief.

Sister Dolores Mary
(Signature of Registrant)

Subscribed and sworn to before me this 19th day of July, 1958.

My commission expires February 7, 1959 E. M. Henson (Notary Public)

(SEAL)

CERTIFICATE OF REGISTRATION

STATE OF OREGON

County of Marion } ss.

This is to certify that the foregoing Registration Statement was received in the office of the State Engineer on the 21 day of July, 1958, at 8:00 o'clock A.M. and has been duly recorded in said office in Book No. 10 of Registration Statements on page GR-2210

Witness my hand this 10th day of March, 1959

Lewis A. Stanley
(State Engineer)

By _____ (Deputy)

\$ 25.00

GR - 2210