

Registration Statement

RECEIVED
 JUL 21 1955
 STATE ENGINEER
 RECEIVED
 STATE ENGINEER

OF CLAIMANT OF RIGHT TO APPROPRIATE GROUND WATER

TO THE STATE ENGINEER OF OREGON:

I, MARK INDUSTRIES, INC.

of 9701 S. E. McLoughlin Blvd County of Clackamas

State of Oregon, do hereby make application for a certificate of registration as evidence of a right to appropriate ground water.

1. Source from which water is withdrawn is Pump well
(Flowing well, pump well, infiltration trench, or tunnel)
2. Location is: Milwaukie, Oregon
(Approximate distance and direction from nearest city or town)

and is more particularly described as follows:

(a) 466' S 50°36' E of S. E. Corner Lot 11 Milwaukie Industrial Park
(Give distance and bearing to corner of section or other legal subdivision)

being within SE 1/4 SE 1/4 of Sec. 20, Twp. 25 / S, Rge. 1E
(Smallest legal subdivision) (of. or S.) (E. or W.)

or (b) within limits of recorded platted property, town or city:

in Lot _____, Block _____ of _____
(Name of plat or addition)

County of _____
(If within city or town, give name)

3. Construction Work was begun on February 1955; was completed on April 18, 1955
(Date) (Date)

and the ground water claimed was first used for the purposes set out below on approximately July, 1955
(Date)

since which time the water has been used continuously as required by the weather
(Continuously or intermittently)

from July, 1955 to July, 1958
(Date) (Date)

4. Quantity of water claimed and used is 275 gallons per minute; _____ acre feet per year.

5. Purpose or Purposes for which water is used Air conditioning
(Domestic, irrigation, municipal, manufacturing, industrial, etc.)

6. Description of Well: Depth 381 feet. Type drilled
(Dug or drilled)

diameter starts 12 inches. Elevation of ground at well site: about 25 feet, mean sea level.
(As near as known)

Depth to water table 277 feet. Static water level close to surface.

7. Capacity of Well: 322 g.p.m. with 300 feet drawdown.

277 g.p.m. with 240 feet drawdown.

Date of test April 17, 1958

If Flowing Well: Measured discharge none g.p.m. on _____
(Date)

Shut-in pressure at ground surface _____ lbs. per sq. in. on _____
(Date)

Water is controlled by _____
(Cap, valve, etc.)

8. Casing: (Give diameter, commercial specifications and depth below ground surface of each casing size.)

12 inch diameter steel from surface to 96 feet
 10 inch diameter steel from surface to 267 feet
 8 inch diameter steel from 265 to 381 feet
 inch diameter from to feet

Describe and show depth of shoe, plug, adapter, liner or other details: 12-inch casing grouted in place to seal off upper water. Top of 8-inch casing fitted with transition to 10 inches.

9. Perforated Casings or Screens:

8-inch casing perforated (detail not known) from 271 to 361
(Number per foot and size of perforations, or describe screen)
 from to
 from to
 from to

10. Log of Well: (Describe each stratum or formation clearly, indicate if water bearing, and give thickness and depth as indicated.)

From	To	MATERIAL Formation	Thickness (Feet)	Depth to Bottom (Feet)
Surface	4	Topsoil and gravel		
4	5	Gravel		
5	20	Boulders and gravel		
20	29	Mucky sand		
29	43	Hard Broken rock		
43	75	Cemented gravel		
75	89	Conglomerate		
89	140	Medium hard grey rock with red seams		
140	179	Mixed colored rock mostly grey and red		
179	196	Hard grey rock		
196	213	Conglomerate		
213	217	Soft grey rock with red seams		
217	219	Conglomerate		
219	223	Soft grey rock		
223	237	Conglomerate		
237	240	Rough broken grey rock		
240	257	Shale, broken brown		
257	262	Grey rock		
262	273	Grey rock with shale seams		
273	296	Medium hard grey rock		
296	318	Grey rock with red seams (water bearing)		
318	331	Medium hard rough grey rock		
331	381	Hard rough grey rock (water bearing)		

Township 15 Range 1E W.M.
North

26

R

Locate well and acreage of irrigated land on plat.
Scale: 2" = 1 Mile.

STATE OF OREGON

County of Clackamas } ss.

I, Christe Han, being first duly sworn, do hereby certify that I have read the foregoing Registration Statement and that all of the items therein contained are true to the best of my knowledge and belief.

Christe Han Cristalle
(Signature of Registrant)

Subscribed and sworn to before me this 13 day of January, 1960

My commission expires December 20, 1963
Vernon A. Benton
(Notary Public)

(SEAL)

CERTIFICATE OF REGISTRATION

STATE OF OREGON

County of Marion } ss.

This is to certify that the foregoing Registration Statement was received in the office of the State Engineer on the 28 day of July, 1958, at 8:00 o'clock A.M. and has been duly recorded in said office in Book No. 16 of Registration Statements on page R-3911

Witness my hand this 15th day of February, 1960

Lewis A. Stanley
(State Engineer)

By _____
(Deputy)

GR 3911

\$20.00