

# Registration Statement

## OF CLAIMANT OF RIGHT TO APPROPRIATE GROUND WATER

(Under Chapter 708, Oregon Laws 1955.)

TO THE STATE ENGINEER OF OREGON:

I, Gordon Seely  
of Rt. 2, Box 40, Woodburn County of Marion

State of Oregon do hereby make application for a certificate of registration as evidence of a right to appropriate ground water.

- 1. Source from which water is withdrawn is Pump well  
(Flowing well, pump well, infiltration trench, or tunnel)
- 2. Location is: 4 mi. east of Woodburn  
(Approximate distance and direction from nearest city or town)

and is more particularly described as follows: 275 ft. South of North line and 1228 ft. West of Eastline of property. At NNW 1/4 corner.

(a) Meets & Bounds Description accompanies this statement  
(Give distance and bearing to corner of section or other legal subdivision)  
being within NW 1/4 of NW 1/4 of Sec. 27, Twp. 5S, Rge. 1W  
(Smallest legal subdivision) (N. or S.) (E. or W.)

or (b) within limits of recorded platted property, town or city:  
in Lot \_\_\_\_\_, Block \_\_\_\_\_ of \_\_\_\_\_  
(Name of plat or addition)

County of \_\_\_\_\_  
(If within city or town, give name)

3. Construction Work was begun on 1953; was completed on January, 1953  
(Date) (Date)

and the ground water claimed was first used for the purposes set out below on April, 1953  
(Date)

since which time the water has been used Intermittently  
(Continuously or Intermittently)

from May to October  
(Date) (Date)

4. Quantity of water claimed and used is 260 gallons per minute; 30 acre feet per year.

5. Purpose or Purposes for which water is used Irrigation  
(Domestic, irrigation, municipal, manufacturing, industrial, etc.)

6. Description of Well: Depth 134 feet. Type Drilled  
(Dug or drilled)  
diameter 8 inches. Elevation of ground at well site 175 feet, mean sea level.  
(As near as known)  
Depth to water table 12 feet.

7. Capacity of Well: 260 g.p.m. with 58 feet drawdown.  
\_\_\_\_\_ g.p.m. with \_\_\_\_\_ feet drawdown.

Date of test January, 1953

If Flowing Well: Measured discharge \_\_\_\_\_ g.p.m. on \_\_\_\_\_  
(Date)

Shut-in pressure at ground surface \_\_\_\_\_ lbs. per sq. in. on \_\_\_\_\_  
(Date)

Water is controlled by \_\_\_\_\_  
(Cap, valve, etc.)

8. Casing: (Give diameter, commercial specifications and depth below ground surface of each casing size.)

8 inch diameter :..... from top..... to 134..... feet  
 ..... inch diameter ..... from ..... to ..... feet  
 ..... inch diameter ..... from ..... to ..... feet  
 ..... inch diameter ..... from ..... to ..... feet

Describe and show depth of shoe, plug, adapter, liner or other details: Hardened shoe on the bottom

9. Perforated Casings or Screens:

4 rows  $2 \times 1\frac{1}{2}$  from 55 to 90  
 (Number per foot and size of perforations, or describe screen)  
 4 rows  $2 \times 1\frac{1}{2}$  from 105 to 134  
 ..... from ..... to .....  
 ..... from ..... to .....

10. Log of Well: (Describe each stratum or formation clearly, indicate if water bearing, and give thickness and depth as indicated.)

MATERIAL	Thickness (Feet)	Depth to Bottom (Feet)
Sandy loam	4	4
Brown silt	19	23
Blue silt	22	45
Brown Sand	7	52
Brown gravel	19	71
Sand & gravel (blue)	9	80
Blue clay	22	102
Gravel with clay binder	32	134

Beginning at an iron bar in the Northeast corner of the Northwest quarter of the Northwest quarter of Section 27 in T. 5 S. R. 1 W. of the Willamette Meridian in Marion County, Oregon; thence South 48' East 7.54 chains; thence West 42.535 chains to the East line of the S. P. P. R. right of way; thence North 9° 35' West along said right of way 7.592 chains to a harrow tooth; thence East along the North line of Section 28, 3.785 chains to a stone in an angle in the County Road; thence North 62.5 links to an iron pipe; thence East, 39.90 chains to an iron bar; thence South 4' East 62.5 links to the point of beginning, containing 35 acres of land in Sections 21, 22, 27 and 28 in T. 5 S. R. 1 W., in Marion County, State of Oregon.

Save and except the land described in the deed from B. H. Hughes and Alice Hughes, his wife, to D. M. Dryden, dated January 20, 1922, and recorded May 22, 1922, in Vol. 166, Page 573 Deed Records for Marion County, Oregon.



