

RECEIVED

APR 2 1957
STATE ENGINEER
SALEM, OREGON

Registration Statement

REGISTRATION NO. CR 426
CERTIFICATE NO. CR 412

OF CLAIMANT OF RIGHT TO APPROPRIATE GROUND WATER

(Under Chapter 708, Oregon Laws 1955.)

TO THE STATE ENGINEER OF OREGON:

I, WADE STROWGER

of 100 N.W. Tuality Way, Portland County of Multnomah

State of Oregon, do hereby make application for a certificate of registration as evidence of a right to appropriate ground water.

1. Source from which water is withdrawn is Pump Well
(Flowing well, pump well, infiltration trench, or tunnel)

2. Location is: 1 Mile West Portland City Limit
(Approximate distance and direction from nearest city or town)

and is more particularly described as follows:

(a) About 630 ft. East and 40 ft. North from the S.W. Corner of Section 36
(Give distance and bearing to corner of section or other legal subdivision)

being within S.W. Quarter of S.W. Quarter of Sec. 36, Twp. 1-N, Rge. R.1.W. WM
(Smallest legal subdivision) (N. or S.) (E. or W.)

and (b) within limits of recorded platted property, town or city:

in Lot all, Block 4 & 5 of Rosary, and adjacent vacated streets
(Name of plat or addition)

County of Multnomah, Oregon
(If within city or town, give name)

3. Construction Work was begun on Aug. 18, 1949; was completed on Oct. 15, 1949
(Date) (Date)

and the ground water claimed was first used for the purposes set out below on 7-10-1950
(Date)

since which time the water has been used continuously
(Continuously or intermittently)

from 7-10-50 to date of application and at present.
(Date) (Date)

4. Quantity of water claimed and used is 500 gallons per hour acre per year.
feet per year.

5. Purpose or Purposes for which water is used Domestic use, stock watering, pasture, garden, and holly irrigation approximately 4 acres.
(Domestic, irrigation, municipal, manufacturing, industrial, etc.)

6. Description of Well: Depth 432 feet. Type Drilled
(Dug or drilled)
diameter 4-1/4" inches. Elevation of ground at well site 875 feet, mean sea level.
(As near as known)
Depth to water table 341 feet.

7. Capacity of Well: 525 hr. g.p.m. with 25 feet drawdown.
500 hr. g.p.m. with 40 feet drawdown.

Date of test Oct. 15, 1949

If Flowing Well: Measured discharge g.p.m. on g.p.m. on
(Date) (Date)

Shut-in pressure at ground surface lbs. per sq. in. on lbs. per sq. in. on
(Date) (Date)

Water is controlled by Cap, valve, etc.
(Cap, valve, etc.)

8. Casing: (Give diameter, commercial specifications and depth below ground surface of each casing size.)

6" inch diameter steel casing pipe from surface to 30-1/2 feet
 4-1/4" inch diameter - do - from 165' 10" to 247-1/2 feet
 inch diameter from to feet
 inch diameter from to feet

Describe and show depth of shoe, plug, adapter, liner or other details:

4-1/4" pipe installed to shut off wet clay strata struck at 215' to 245' driven into hard rock

9. Perforated Casings or Screens:

from to
 (Number per foot and size of perforations, or describe screen)
 from to
 from to
 from to

10. Log of Well: (Describe each stratum or formation clearly, indicate if water bearing, and give thickness and depth as indicated.)

MATERIAL	Thickness (Feet)	Depth to Bottom (Feet)
Clay	From 0'	to 19'
Rock (Med. Grey, then grey, then red, then grey)	" 19'	" 193'
Clay (Red, then yellowish brown)	" 193'	" 245'
Rock (Grey, then red, then grey, then red)	" 245'	" 432'
235' Some water - 15 gal. per hr. Yellowish brown rock		
363' " " - red rock		
412' More " - " "		
432' " " - " "		

If log of well is not available, give name and address of driller.

A. L. Ziesing, 9200 S. E. 82nd Ave., Portland 6, Oregon -- now deceased

11. Infiltration Trench: Covered or open

Dimensions: Length _____ ft. Minimum depth _____ ft. Maximum depth _____ ft.
Bottom width _____ ft. Discharge _____ g.p.m. Date of test _____

12. Tunnel: Type of lining

Dimensions: _____
(Length, course, and cross sectional size)
Position of water bearing stratum with reference to portal of tunnel _____

Log of tunnel: (Preceding table for log of well may be used, if desired. Give footage from portal and character of materials, as pertinent.)

13. Pumping Equipment:

(a) Pump 9" Stroke pump Gould - Cid Capacity 9 g.p.m.
(Make, type and size)
(b) Motor 3 hp single phase Westinghouse Lifeline Induction
(Type and horsepower)

14. Location of area irrigated or to be irrigated, or place of use if for purposes other than irrigation.


Township North or South	Range E. or W. of Willamette Meridian	Section	Forty-acre Tract	Number Acres To Be Irrigated	Date of Reclamation
<u>1 N</u>	<u>1 W</u>	<u>36</u>	<u>SW 1/4 of SW 1/4</u> <u>See reverse</u>	<u>Approx. 1/4</u>	<u>7-10-50</u>

15. If the ground water supply is supplemental to an existing water supply, identification of any application for a permit, permit, certificate or adjudicated right to appropriate water made or held by the registrant.

None

Township 1 N Range 1 W W.M.

North



Rosary tract is
330' X 1320' with
longest length running
N - S.

West line of Rosary is
330' East of Section
36 West Line. Irrig-
ated portion is
South 1/4 acres of
Rosary

Locate well and acreage of irrigated-land on plat.

Scale: 2" = 1 Mile

STATE OF OREGON

County of Multnomah } ss.

I, Wade Strowger, being first duly sworn, do hereby certify that I have read the foregoing Registration Statement and that all of the items therein contained are true to the best of my knowledge and belief.

Wade Strowger
(Signature of Registrant)

Subscribed and sworn to before me this 1st day of April, 1957

My commission expires Dec. 11, 1959

Lila B. Elliott
(Notary Public)
My Commission Expires Dec 11, 1959

(SEAL)

CERTIFICATE OF REGISTRATION

STATE OF OREGON

County of Marion } ss.

This is to certify that the foregoing Registration Statement was received in the office of the State Engineer on the 2nd day of April, 1957, at 8:100 o'clock A. M. and has been duly recorded in said office in Book No. 3 of Registration Statements on page GR-412 C

~~Construction shall be completed by~~ ~~X-X~~ ~~and the water completely applied to~~ ~~beneficial use by~~ ~~X-X~~

Witness my hand this 26th day of June, 1957

Lewis A. Stanley
(State Engineer)

By _____ (Deputy)

#15.00