

**BEFORE THE WATER RESOURCES DEPARTMENT
OF THE
STATE OF OREGON**

In the Matter of Instream Lease Application) DETERMINATION and FINAL ORDER ON
SL-61, Wallowa County) PROPOSED INSTREAM LEASE

Authority

Oregon Revised Statute (ORS) 537.348 establishes the process in which a water right holder may submit a request to lease an existing water right for instream purposes. Oregon Administrative Rule (OAR) Chapter 690, Division 077 implements the statutes and provides the Department's procedures and criteria for evaluating instream lease applications.

Lessor

Podunk
Elinor T. Newman, Owner
901 Center Street
Santa Cruz, CA 95060
nell@nellnewman.com

Lessee

Trout Unlimited
Jessica Humphreys, Project Manager
401 NE First Street
Enterprise, OR 97828
Jessica.humphreys@tu.org

Findings of Fact

1. On May 24, 2022, Elinor Newman of Podunk and Trout Unlimited filed an application to lease a portion of Certificates 3031 and 3049 for split season instream use. The Department assigned the application number SL-61.
2. On July 7, 2022, the Department notified the Lessee that 42.1 acres were identified by the Watermaster that would not be able to be leased for instream use due to roads, buildings, and marsh areas. On July 11, 2022, the Lessee submitted a revised application omitting the acreage that was not allowed to be leased.

3. The portion of the right to be leased is as follows:

Certificate: 3031 in the name of C. E. Glenn (confirmed by the Wallowa River Decree) of record in the Order Records in Volume 5 at Page 168

Use: Irrigation of 111.3 acres

Priority Date: 1883

Limit: The amount of water to which this right is entitled is limited to an amount actually beneficially used and shall not exceed 1.5 acre feet per acre during any period of 30 days prior to July 31 of each year, and thereafter not to exceed 1 acre foot per acre during the entire remainder of the irrigation season.

This is a final order in other than contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Source: South Fork of the Wallowa River (aka Lostine River), tributary to the Wallowa River

Authorized Point of Diversion (POD): None Listed

Authorized Place of Use:

Twp	Rng	Mer	Sec	Q-Q	Acres
1 N	43 E	WM	33	SE NW	35.8
1 N	43 E	WM	33	NE SW	38.4
1 N	43 E	WM	33	NW SW	4.0
1 N	43 E	WM	33	SE SW	33.1
Total					111.3

4. The portion of the right to be leased is as follows:

Certificate: 3049 in the name of J. F. Haun, John McDonald, Leonard Couch (confirmed by the Wallowa River Decree) of record in the Order Records in Volume 5 at Page 172

Use: Irrigation of 10.6 acres

Priority Date: 1883

Limit: The amount of water to which this right is entitled is limited to an amount actually beneficially used and shall not exceed 1.5 acre feet per acre during any period of 30 days prior to July 31 of each year, and thereafter not to exceed 1 acre foot per acre during the entire remainder of the irrigation season.

Source: South Fork of the Wallowa River (aka Lostine River), tributary to the Wallowa River

Authorized Point of Diversion (POD): None Listed

Authorized Place of Use:

Twp	Rng	Mer	Sec	Q-Q	Acres
1 N	43 E	WM	33	SW NW	10.6

5. Certificates 3031 and 3049 do not provide a full description of the point of diversion of the Fitzpatrick Ditch. However, based upon additional information provided by the Lessee and the Department records, the location of the point of diversion for purposes of this instream lease is described as follows:

Twp	Rng	Mer	Sec	Q-Q	Latitude / Longitude
1 S	43 E	WM	9	NE NE	FITZPATRICK DITCH: 615 FEET SOUTH AND 980 FEET WEST OF THE NE CORNER OF SECTION 9

6. Certificates 3031 and 3049 do not specify the irrigation season; however, pursuant to the Wallowa River Decree the irrigation season is from May 1 to October 1 and shall be used to establish when water may be protected instream.
7. There are supplemental irrigation water rights, Certificates 95647 and 94160, appurtenant to all or a portion of the lands described in Findings of Fact No. 3 and 4. The Lessor and Lessee have requested that these water rights not be included as part of this lease

application. During the term of the lease, water use for the lands covered under this lease for these rights will also be suspended during the instream use period.

8. The lease application includes the information required under OAR 690-077-0076(3). The Department provided notice of the lease application pursuant to OAR 690-077-0077(1). No comments were received.

9. The instream lease application, as proposed, is a split season lease.

Use of water under the water right included in this lease may continue for the existing use up to the rates and volumes specified in the below table consistent with the water right limitations identified in Findings of Fact No. 3 and 4.

Certificate	On-Farm Rate (CFS)	On-Farm Volume (AF)	On-Farm Use Period
3031	2.81	511.98	May 1 through July 31
3049	0.27	48.76	

10. Within the proposed reach, a portion of the water diverted at the point of diversion returns to the Lostine River (20%) and is available to downstream water right holders. To prevent injury to downstream water right holders and enlargement, the quantity of water that may be protected instream requires modification and return flows should be accounted for immediately below the point of diversion. OAR 690-077-0015(8).

11. The instream use has been modified from the lease application to prevent injury and enlargement and is as follows:

Instream Point: At the Fitzpatrick Ditch POD

Certificate	Priority Date	Instream Rate (CFS)	Instream Volume (AF)	Period Protected Instream
3031	1883	0.92	111.30	August 1 through September 30
3049	1883	0.09	10.60	

Instream Reach: From immediately below the Fitzpatrick POD to the Mouth of the Lostine River at the confluence with the Wallowa River, into the Wallowa River to the Mouth at confluence with the Grande Ronde River

Certificate	Priority Date	Instream Rate (CFS)	Instream Volume (AF)	Period Protected Instream
3031	1883	0.18	22.26	August 1 through September 30
3049	1883	0.02	2.12	

12. The amount and timing of the proposed instream flow is allowable within the limits and use of the original water right.

13. The protection of flows within the proposed reach is appropriate, considering:

a. The instream water use begins at the recorded point of diversion;

- b. The location of confluences with other streams downstream of the point of diversion.
 - c. There are no known areas of natural loss of streamflow to the river bed downstream from the point of diversion; and
 - d. Return flows resulting from the exercise of the existing water right would re-enter the river within the reach of the instream water right below the POD. The quantity of water to be protected instream in the Instream Reach has been reduced to account for return flows.
14. The total monthly quantities of water to be protected under the existing and proposed instream rights in the reach will provide for a beneficial purpose.
 15. The total monthly quantities of water to be protected instream under existing and proposed instream rights in the reach do not exceed the estimated average natural flow.
 16. If approved, this instream lease is not reasonably expected to significantly affect land use as prescribed by ORS 197.180, OAR Chapter 660, Divisions 30 and 31, and OAR Chapter 690, Division 5.
 17. Based upon review of the application, information provided by the Department's Watermaster, and other available information, the Department finds that the lease will not result in injury or enlargement. The order approving this instream lease may be modified or revoked under OAR 690-077-0077 if the Department later finds that the lease is causing injury to any existing water right or enlargement of the original right.
 18. If a right which has been leased is later proposed to be leased again, transferred and/or reviewed under an allocation of conserved water, a new injury review shall be required. For example, instream transfers will be subject to a full and complete review to determine consistency with the requirements of OAR Chapter 690, Division 380 and Division 077. Approval of this lease does not establish a precedent for approval of any future transactions.
 19. The Lessor and Lessee have requested that the lease terminate on October 1, 2022. The lease may commence upon approval of this order.

Conclusions of Law


The Department concludes that the lease will not result in injury or enlargement, OAR 690-077-0077. The lease conforms to the applicable provisions of OAR 690-077-0015.

Now, therefore it is ORDERED:

1. The Lease as described herein is APPROVED.

2. During the term of this lease, the place of use will continue to receive water as identified in Finding of Fact No. 9 during the period May 1 through July 31 for irrigation. For the remainder of the irrigation season, during the term of this lease, the former place of use will not receive water as part of this right, any supplemental rights (including Certificates 95647 and 94160), or any other layered water rights for irrigation use, including groundwater registrations
3. The term of the lease will upon approval and terminate on October 1, 2022.

Dated at Salem, Oregon this day AUG 01 2022



Lisa J. Jaramillo, Transfer and Conservation Section Manager, for
Thomas M. Byler, Director, Oregon Water Resources Department

Mailing date: AUG 02 2022

This document was prepared by Sarah Henderson. If you have any questions, please call 503-979-9872.