

**BEFORE THE WATER RESOURCES DEPARTMENT
OF THE
STATE OF OREGON**

In the Matter of Instream Lease Application) DETERMINATION and
IL-1420, Deschutes County) FINAL ORDER ON PROPOSED
) INSTREAM LEASE

Authority

ORS 537.348 establishes the process in which a water right holder may submit a request to lease an existing water right for instream purposes. OAR Chapter 690, Division 077 implements the statutes and provides the Department's procedures and criteria for evaluating instream lease applications.

Lessor

Central Oregon Irrigation District (COID)
1055 SW Lake Ct
Redmond, OR 97756
lauraw@coid.org

Lessee

Deschutes River Conservancy (DRC)
P.O. Box 1560
Bend, Oregon 97709
gen@deschutesriver.org

Findings of Fact

1. On June 20, 2014, COID and the DRC filed an application to lease a portion of Certificate 83571 for instream use. The Department assigned the application number IL-1420.
2. On August 5, 2014, the Department requested additional ownership information and an amended map from the Lessor. On August 13, 2014, the Lessor provided the requested information.
3. Interest in a portion of the water right to be leased instream has been conveyed from the original land owners. The lease application identifies Central Oregon Irrigation District as the interest holder in the portion of the water right to be leased. Individual agreements, along with supporting documentation, identify that interest in a portion of the right to be leased is held by Central Oregon Irrigation District. For the purpose of this instream lease, the Department has determined that Central Oregon Irrigation District is an interest holder in the right and is authorized to lease the pertinent portion of the water right instream.
4. The portion of the right to be leased has been modified from the lease application and is as follows:

Certificate: 83571 in the name of Central Oregon Irrigation District
Use: Irrigation of 0.4 acre, 4.2 acres equivalent of Pond Maintenance, and 3.0 acres equivalent of Quasi-Municipal from POD No. 1; and Irrigation of 22.46 acres from POD No. 11

This is a final order in other than contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.

Season of Use: April 1 through October 31, further limited as follows:
 April 1 through April 30 & October 1 through October 31
 May 1 through May 14 & September 16 through September 30
 May 15 through September 15

Priority Date: October 31, 1900 & December 2, 1907

Maximum Quantity (Rate) that can be applied to an acre:

Season 1: limited to 1/80th cubic foot per second (CFS) per acre
 Season 2: limited to 1/60th CFS per acre
 Season 3: limited to 1/32.4th CFS per acre

Maximum Duty that can be applied to an acre:

Not to exceed 9.91 acre-feet (AF) per acre per year.
 The above listed rates and duty reflect allowance of a 45% transmission loss on the main canals (POD No. 1 & 11) as determined by decree of the Circuit Court of Deschutes County, dated March 24, 1933. Those lands not served from the district main canal systems, but by direct pumping from the Deschutes River, are not allowed the 45% transmission loss.

Source: Deschutes River tributary to the Columbia River

Authorized Point of Diversion (POD):

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
18 S	11 E	WM	13	SW NE	POD No. 1 (CENTRAL OREGON CANAL): 1520 FEET SOUTH AND 1535 FEET WEST FROM THE NE CORNER OF SECTION 13
17S	12E	WM	29	SE NE	POD No. 11 (C.O.I.D. NORTH CANAL): 850 FEET NORTH AND 630 FEET WEST FROM EAST CORNER OF SECTION 29

Authorized Place of Use:

Twp	Rng	Mer	Sec	Q-Q	POD	Acres	Additional Place of Use Description Provided in Application - Tax Lot
Pond Maintenance							
15 S	14 E	WM	27	SE NE	1	0.5	101
17 S	13 E	WM	20	NE SW	1	3.7	403
Quasi-Municipal							
16 S	14 E	WM	15	NE SW	1	3	N/A
16 S	14 E	WM	15	NW SW	1		
16 S	14 E	WM	15	SW SW	1		
16 S	14 E	WM	15	SE SW	1		
16 S	14 E	WM	15	NE SE	1		
16 S	14 E	WM	15	NW SE	1		
16 S	14 E	WM	15	SW SE	1		
16 S	14 E	WM	15	SE SE	1		
16 S	14 E	WM	22	NE NE	1		
16 S	14 E	WM	22	NW NE	1		
16 S	14 E	WM	22	SW NE	1		
16 S	14 E	WM	22	SE NE	1		
16 S	14 E	WM	23	NW NW	1		

Twp	Rng	Mer	Sec	Q-Q	POD	Acres	Additional Place of Use Description Provided in Application - Tax Lot
16 S	14 E	WM	23	SW NW	1		
Irrigation							
14 S	13 E	WM	6	NW SE	11	0.2	100
14 S	13 E	WM	32	SW SW	11	5.5	901
15 S	13 E	WM	4	NE NE	11	2.22	700
15 S	13 E	WM	19	NE NE	11	12.83	705
17 S	12 E	WM	2	SW SE	11	1.5	604
17 S	12 E	WM	14	NE NW	11	0.21	301
18 S	12 E	WM	2	SW SW	1	0.4	900

5. Certificate 83571 is a deficient water right. If water were diverted simultaneously to all authorized lands and uses described in the right at the maximum rates and duty allowed (described in Finding of Fact No. 4), the total rate and duty for the water right would be exceeded. In the event water were diverted simultaneously to all authorized lands and uses described in the right at the maximum rates and duty allowed at the POD (described in Finding of Fact No. 4), the portion of the right involved in this instream lease would be limited as described in the table below. These rates and duty are also the quantities by which the diversion at POD No. 1 and No. 11 under Certificate 83571 shall be reduced, if this instream lease is approved.

POD No. 1

Irrigation of 0.4 acres				
Priority Date	Season 1	Season 2	Season 3	Total Volume
October 31, 1900	0.005 CFS	0.007 CFS	0.009 CFS	3.94 AF
December 2, 1907			0.003 CFS	
Pond Maintenance of 4.2 acres				
Priority Date	Season 1	Season 2	Season 3	Total Volume
October 31, 1900	0.052 CFS	0.070 CFS	0.092 CFS	41.39 AF
December 2, 1907			0.037 CFS	
Quasi-Municipal of 3.0 acres				
Priority Date	Season 1	Season 2	Season 3	Total Volume
October 31, 1900	0.037 CFS	0.050 CFS	0.066 CFS	29.57 AF
December 2, 1907			0.026 CFS	
Total				
Priority Date	Season 1	Season 2	Season 3	Total Volume
October 31, 1900	0.095 CFS	0.126 CFS	0.166 CFS	74.90 AF
December 2, 1907			0.067 CFS	

POD No. 11

Irrigation of 22.46 acres				
Priority Date	Season 1	Season 2	Season 3	Total Volume
October 31, 1900	0.256 CFS	0.350 CFS	0.477 CFS	211.94 AF
December 2, 1907			0.191 CFS	

6. The season of use described in Certificate 83571 contains scrivener errors. Consistent with the Decree for the Deschutes River (Volume 12, Page 282), the irrigation season should be:
Season of Use: April 1 through October 31, further limited as follows:
 April 1 through April 30 & October 1 through October 31 described herein as Season 1
 May 1 through May 14 & September 15 through September 30 described herein as Season 2
 May 15 through September 14 described herein as Season 3
7. There is a supplemental irrigation water right, Certificate 76714, appurtenant to all or a portion of the lands described in Finding of Fact No. 4. The Lessor and Lessee have requested that this water right not be included as part of this lease application. During the term of the lease, water use under this right will also be suspended.
8. The lease application includes the information required under OAR 690-077-0076(3). The Department provided notice of the lease application pursuant to OAR 690-077-0077(1). No comments were received.
9. The Lessor and Lessee have requested to protect water from Pond Maintenance use from POD No. 1 to the Madras Gage. Pond Maintenance water shall not be protected below the Madars Gage to the mouth of the Deschutes River.
10. The Lessor and Lessee have requested to protect water originating from irrigation and quasi-municipal uses instream from the PODs (described in Finding of Fact No. 4) to the mouth of the Deschutes River. A portion of the water diverted at the PODs for these uses returns to the Deschutes River within the proposed reach and is available to downstream water right holders. Return flows from the existing use generally return to the river system once river flows reach the Madras Gage. To prevent injury to downstream water right holders and enlargement, the quantity of water that may be protected instream has been modified to account for return flows at the Madras Gage.
11. The instream use has been modified from the lease application to prevent injury and enlargement and is as follows:
 Deschutes River, tributary to the Columbia River

Instream Reach No. 1: From the Central Oregon Canal POD No. 1 to the C.O.I.D. North Canal POD No. 11 (as described in Finding of Fact No. 4)

Certificate	Priority Date	Instream Rate (cfs)	Instream Volume (AF)	Period Protected Instream
83571	10/31/1900	Season 1: 0.052	41.42	April 1 – October 26
		Season 2: 0.070		
		Season 3: 0.129		

Instream Reach No. 2: From C.O.I.D. North Canal POD No. 11 (as described in Finding of Fact No. 4) to the Madras Gage

Certificate	Priority Date	Instream Rate (cfs)	Instream Volume (AF)	Period Protected Instream
-------------	---------------	---------------------	----------------------	---------------------------

83571	10/31/1900	Season 1: 0.206	163.84	April 1 – October 26
		Season 2: 0.276		
		Season 3: 0.510		

Instream Reach No. 3: From the Madras Gage to the mouth of the Deschutes River

Certificate	Priority Date	Instream Rate (cfs)	Instream Volume (AF)	Period Protected Instream
83571	10/31/1900	0.118	48.85	April 1 – October 26

12. Other conditions to prevent injury and enlargement are:

The amount of water to be leased instream under Certificate 83571 does not include a 45% transmission loss associated with this right when used for its originally authorized purpose. The transmission loss may not be leased and protected instream.

Within the specified stream reach, the amount of water to which this right is entitled shall not exceed the quantity of water legally available at the original point of diversion. Stream channel losses and gains calculated based on available data and the use of water by senior appropriators will determine the amount of water to which this right is entitled downstream from the original points of diversion within the specified stream reach.

13. The amount and timing of the proposed instream flow is allowable within the limits and use of the original water right.

14. The protection of flows within the proposed reach is appropriate, considering:

- a. The instream water use begins at the recorded point of diversion;
- b. The location of confluences with other streams downstream of the point of diversion.
- c. There are no known areas of natural loss of streamflow to the river bed downstream from the point of diversion; and
- d. Return flows resulting from the exercise of the existing water right would re-enter the river downstream from the POD within the reach of the instream water right. As such, the rate and volume of water protected instream has been reduced in Instream Reach No. 3 to prevent injury and enlargement (Finding of Fact No. 11).

15. The total monthly quantities of water to be protected under the existing and proposed instream rights in the reach will provide for a beneficial purpose.

16. The total monthly quantities of water to be protected instream under existing and proposed instream rights in the reach do not exceed the estimated average natural flow.

17. If approved, this instream lease is not reasonably expected to significantly affect land use as prescribed by ORS 197.180, OAR Chapter 660, Divisions 30 and 31, and OAR Chapter 690, Division 5.

18. Based upon review of the application, information provided by the Department's Watermaster, and other available information, the Department finds that the lease will not result in injury or enlargement. The order approving this instream lease may be modified or revoked under OAR 690-077-0077 if the Department later finds that the lease is causing injury to any existing water right or enlargement of the original right.
19. If a right which has been leased is later proposed to be leased again, transferred and/or reviewed for an allocation of conserved water, a new injury review shall be required. For example, instream transfers will be subject to a full and complete review to determine consistency with the requirements of OAR Chapter 690, Division 380 and Division 077. Approval of this lease does not establish a precedent for approval of any future transactions.
20. The Lessor and Lessee have requested that the lease terminate on October 31, 2014. The lease may commence on the date this final order is signed.


Conclusions of Law

The Department concludes that the lease will not result in injury or enlargement, OAR 690-077-0077. The lease conforms to the applicable provisions of OAR 690-077-0015.

Now, therefore it is ORDERED:

1. The Lease as described herein is APPROVED.
2. During the term of the lease, the former place of use will no longer receive water as part of these rights, any supplemental rights, or any other layered irrigation water rights, including ground water registrations and permits.
3. The term of the lease will commence upon approval of the instream lease and terminate on October 31, 2014.

Dated at Salem, Oregon this 14 day of August, 2014.



Dwight French
Water Right Services Division Administrator, for
Director, Oregon Water Resources Department

*This document was prepared by
Lanaya Blakely and if you have any
questions, please call 503-986-0888.*

Mailing date: AUG 15 2014