

*Enlargement Permit No. 94

APPLICATION FOR A PERMIT TO APPROPRIATE THE PUBLIC WATERS OF THE STATE OF OREGON

I, Fred LaFollette (Name of Applicant) of Crescent (Postoffice), County of Klamath State of Oregon, do hereby make application for a permit to appropriate the following described public waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

- 1. The source of the proposed appropriation is East Fork DesChutes River (Name of stream)
2. The appropriation to be made by the enlargement (or extension) of Ringo Irrigating Ditch (Give name of canal or works to be enlarged) owned by Jos. L. Ringo
3. The amount of water which the applicant intends to apply to beneficial use is 1 5/8 cubic feet per second, which amount is in addition to the present claimed appropriation.
4. The use to which the water is to be applied is Irrigation (Irrigation, power, mining, manufacturing, domestic supplies, etc.)

Location and Description of Ditch or Works which it is Proposed to Enlarge or Extend

5. (a) The point of diversion from the stream is S 69° 33' W 637 ft. from 1/4 cor. between Secs. 33 & 34 (Give distance and bearing to section corner)

(b) The headgate is located within the NE 1/4 SE 1/4 (Smallest legal subdivision) of Sec. 33, Tp. 24 S, R. 8 E, W. M., in the county of Klamath (No. N. or S.) (No. E. or W.)

(c) Said Ditch is 2 miles in length and terminates in the SE 1/4 NE 1/4 (Smallest legal subdivision) of Sec. 35, Tp. 24 S, R. 8 E, W. M., the proposed location being shown throughout on the accompanying map.

(d) The dimensions of said ditch just below the headgate are: Width on top (at water line) 5 feet; width on bottom 3 feet; depth of water 1 foot; grade 1 foot fall per 1000 feet, having a maximum safe capacity of 4 cubic feet per second.

(e) Said ditch now serves to irrigate the following described land: Not yet completed but will irrigate 15 acres in SE 1/4 NW 1/4, 15 acres in S 1/4 NE 1/4 and SE 1/4 NE 1/4 Sec 35 T. 24 S. R. 8 E. W.M. containing 70 acres.

*A different form of application is provided for new appropriations, and where storage works are contemplated. These forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

Completed L. A.

(f) The total area now irrigated from said ditch is None acres.

(g) The diversion works of said ditch are described as follows:

Height 5 ft. length on top 30 ft. on bottom 25 ft. Constructed of logs, rock, brush,
(If any, give character of dam, height, length on top and bottom; spillway over or around dam)
etc. Wasteway over dam.

Description of Proposed Enlargement—

6. (a) The diversion dam, after enlargement.....
Will remain unchanged. (Will remain unchanged,
or if changed, give height, length, character of material, etc.)

(b) The dimensions of ditch just below the headgate, when enlarged to be: Width on top (at
water line).....feet; width on bottom.....feet; depth of water.....feet;
grade.....Unchanged
feet fall per 1000 feet.

(c) At.....2 miles from headgate: Width on top (at water line).....4 feet;
width on bottom.....2 feet; depth of water.....1 feet; grade.....1 feet fall
per 1000 feet. At 3 miles from headgate 3 ft. on top 1 ft. on bottom. The remainder
of the ditch will be used on the land. (Give further dimensions at points where changed in dimensions)

(d) The ditch or canal as enlarged to be.....3 3/4 miles in length, terminating in
the.....W 1/2 W 1/2 SW 1/4 NE 1/4 of Sec. 31, Tp. 24 S, R. 9 E, W. M.
(Give smallest legal subdivision)

(e) The head of the proposed extension is located.....N 75° 58' W, 1359 ft. from 1/4 corner
between Sec. 35 & 36, T. 24 S. R 8 E. W. M.

(If proposed work is extension of the original ditch or a ditch tapping same, locate by tie to Government corner)

Fill in the Following Information, where the Water Appropriated is to be Used for:

Irrigation—

7. The land to be irrigated by the proposed extension or enlargement has a total area of 130.....

acres, located in each smallest legal subdivision, as follows:.....NW 1/4 NW 1/4, S 1/2 NW 1/4 (or Lot
2 and SE 1/4 NW 1/4) W 1/2 W 1/2 SW 1/4 NE 1/4 Sec. 31, T 24 S. R. 9 E. W. M.

(Give estimated irrigable acreage in each smallest legal subdivision of land which it is proposed to irrigate)

(If more space required, attach separate sheet)

Power, Mining, Manufacturing or Transportation Purposes—

8. (a) Total amount of power to be developed..... horsepower.

(b) Total fall to be utilized..... feet.

(Head)

(c) The nature of the works by means of which the power is to be developed.....

located in....., Sec....., Tp....., R....., W. M.
(Legal subdivision)

(d) The use to which the power is to be applied is.....

(e) The nature of the mines to be served.....

Municipal Supply—

9. To supply the city of.....

.....County, having a present population of..... and an
estimated future population of..... in 19.....

10. Estimated cost of the proposed extension or enlargement \$..... 200.⁰⁰.....

11. Construction work will begin on or before..... October 1, 1911.....

12. Construction work will be completed on or before..... October 1, 1912.....

13. The water will be completely applied to a beneficial use on or before..... October 1, 1913.....

Duplicate maps of the original canal or other works, showing also the enlargement or extension, prepared in accordance with the rules of the Board of Control, accompany this application.

Fred LaFollette
(Name of Applicant)

Signed in the presence of us as witnesses:

(1) Jos. L. Ringo, Crescent, Oregon
(Name) (Address of Witness)
(2) G. E. LaFollette, Crescent, Oregon
(Name) (Address of Witness)

Remarks:

STATE OF OREGON,

County of Marion

} ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion, as follows:

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before....., 19.....

WITNESS my hand this..... day of....., 19.....

State Engineer.

Compared S. A.

Application No. 1368

Enlargement Permit No. 94

PERMIT

To appropriate the public waters of the State of Oregon

Division No. 2 District No.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the 19 day of April

1911, at 8:00 o'clock A.M.

Returned to applicant for correction

Corrected application received

Approved

May 2 1911

Recorded in Book No. 1 of Enlargements

on Page 94

John H Lewis

State Engineer

19.50

1368

Office of STATE ENGINEER

RECEIVED

APR 19 1911

Salem Oregon

Crescent, Oregon, April 14, 1911

I, Jos. L. Ringo, the sole owner of the Ringo Irrigating Ditch taking water from the East Fork Deschutes River in the NE 1/4 Sec. 33, Tp. 6 S., R. 8 E. W. M., do hereby give my free and voluntary consent to the enlargement or extension of, and to the use of water through, the said ditch by Fred LaFollette according to the terms of this enlarged permit.

Jos. L. Ringo.

STATE OF OREGON,

County of Marion

ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions:

The appropriation for irrigation purposes shall be limited to one-eightieth of one cu. ft. per sec. for each acre irrigated.

The amount of water appropriated shall be limited to the amount which can be applied to beneficial use and not to exceed one & 5/8 (1.625) cubic feet per second.

Actual construction work shall begin on or before May 2 1912

and shall thereafter be prosecuted with reasonable diligence and be completed on or before

May 2 1913

Complete application of the water to the proposed use shall be made on or before

May 2 1915

WITNESS my hand this 2nd day of May, 19 11

John H Lewis

State Engineer.