

STATE OF OREGON

COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

MONTE J. CARPENTER DBA CARPENTERS DAIRY  
910 CASCADE HIGHWAY N.E.  
SALEM, OREGON 97301

503-364-5643

to use the waters of TWO WELLS in the PUDDING RIVER BASIN for IRRIGATION OF 35.7 ACRES AND AGRICULTURAL USE FOR DAIRY OPERATIONS.

This permit is issued approving Application G-12855. The date of priority is APRIL 2, 1992. The use is limited to not more than 0.5 CUBIC FOOT PER SECOND (CFS) FROM WELL 2, BEING 0.45 CFS FOR IRRIGATION AND 0.05 CFS FOR AGRICULTURAL USE, WITH WELL 1 BEING BACKUP WELL FOR AGRICULTURAL USE, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

NE 1/4 SW 1/4, SECTION 34, T 7 S, R 1 W, W.M.; 820 FEET NORTH AND 120 EAST, 760 FEET NORTH AND 260 FEET EAST, BOTH FROM THE REENTRY CORNER OF DLC 39.

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre-feet for each acre irrigated during the irrigation season of each year. The periods of allowed use are March 1 through October 31 for irrigation and year round for agricultural use.

This right is limited to any deficiency in the available supply of any prior right existing for the same land.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

SE 1/4 NW 1/4 4.3 ACRES DAIRY USE  
NE 1/4 SW 1/4 31.4 ACRES DAIRY USE  
SECTION 34  
TOWNSHIP 7 SOUTH, RANGE 1 WEST, W.M.

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

Application G-12855

Water Resources Department

PERMIT G-11733

T-8846 ΔUSE

- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

The permittee shall obtain a static water-level measurement for each well during April of each year and report the measurement to the Department within thirty days. The measurement shall be made by a certified water-rights examiner, registered professional geologist, or professional engineer. Water levels shall be reported as depth-to-water below ground level and shall be accompanied by supporting calculations. If a well listed on this permit displays a total static water-level decline of 25 or more feet over any period of years, as compared to the reference level, then the permittee shall discontinue use of, or reduce the rate or volume of withdrawal from, the well. Such action shall be taken until the water level recovers to above the 25-foot decline level or until the Department determines, based on the permittee's or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The reference level for water-level declines shall be the second annual measurement taken after water use begins under the terms of this permit. The permittee shall in no instance allow excessive decline to occur within the aquifer as a result of use under this permit.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before May 10, 1995 and shall be completed on or before October 1, 1996. Complete application of water shall be made on or before October 1, 1997.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director of the Water Resources Department has found that the proposed use of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Issued this date, May 10, 1994.

/s/ A. REED MARBUT

Water Resources Department  
Martha O. Pagel  
Director

Application G-12855      Water Resources Department      PERMIT G-11733  
Basin 2      Volume 13 Pudding River & Misc.      District 16  
MGMT.CODE 4GG