

STATE OF OREGON

COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

OREGON DEPARTMENT OF TRANSPORTATION  
329 TRANSPORTATION BUILDING-BRIDGE SECTION  
SALEM, OREGON 97310

503-378-4662

to use the waters of A WELL in the NORTH FORK SILVER CREEK BASIN for INDUSTRIAL USE (HEATING).

This permit is issued approving APPLICATION G-13598. The date of priority is JANUARY 18, 1994 for 75 GALLONS PER MINUTE (GPM) AND MAY 9, 1994 FOR 125.0 GPM. The use is limited to not more than 200.0 GPM, or its equivalent in case of rotation, measured at the well.

The wells are located as follows:

SW 1/4 SW 1/4 SECTION 7, TOWNSHIP 8 SOUTH, RANGE 2 EAST, W.M.; 650 FEET SOUTH AND 280 FEET EAST OF THE NORTHWEST CORNER OF THE SW 1/4 SW 1/4 OF SECTION 7.

The use of water for heating in excess of 5000 gallons per day shall be subsequent in priority to future beneficial consumptive use unless a two well system is constructed and all water wasted from the system recharged to the same ground water reservoir from which it was withdrawn.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

A description of the proposed place of use under this permit is as follows:

SW 1/4 SW 1/4  
SECTION 7  
TOWNSHIP 8 SOUTH, RANGE 2 EAST, W.M.

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

The water user shall report a March static water level in the well to the Groundwater/Hydrology Section of the Water Resources Department by April 15 of each year. The measurement shall be made and calculations detailed by a certified water rights examiner, registered professional geologist, certified engineering geologist, professional engineer, licensed water well driller, licensed pump installer, licensed land surveyor or the permittee/appropriator.

Use of water from the well shall not be allowed if the well displays an (A) average water level decline of 3 or more feet per year for 5 consecutive years, or (B) a water level decline of 15 or more feet in fewer than 5 consecutive years, or (C) a water level decline of 25 or more feet, or (D) a hydraulic interference decline of 25 or more feet in any neighboring well with senior priority which provides water for an authorized use.

The Water Resources Department has determined that the initial water level in the well are those of the initial March report. That is the level from which the cited declines in (A), (B) and (C) above will be referenced.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Actual construction work shall begin on or before DECEMBER 6, 1995 and shall be completed on or before October 1, 1996. Complete application of the water shall be made on or before October 1, 1997.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for beneficial use of water without waste. The water user is advised that new regulations may require use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director of the Water Resources Department has found that the proposed use of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Issued this date, December 6, 1994.

/s/ MARTHA O. PAGEL

Water Resources Department  
Martha O. Pagel  
Director