

STATE OF OREGON  
COUNTY OF KLAMATH

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

U.S. FREMONT NATIONAL FOREST  
524 NORTH G STREET  
LAKEVIEW, OREGON 97630

PHONE: (541) 947-6238

The specific limits for the use are listed below along with conditions of use.

APPLICATION FILE NUMBER: G-14006

SOURCE OF WATER: A WELL IN THE SPRAGUE RIVER BASIN

PURPOSE OR USE: AGRICULTURAL USE (ROAD WATERING AND FIRE PROTECTION)

RATE OF ALLOWED USE: 0.178 CUBIC FOOT PER SECOND

PERIOD OF ALLOWED USE: YEAR ROUND

DATE OF PRIORITY: MARCH 8, 1995

POINT OF DIVERSION LOCATION: NE 1/4 SE 1/4, SECTION 12, T 38 S, R 15 E, W.M.; NORTH 77 DEGREES 37 MINUTES 49 SECONDS WEST, 623.97 FEET FROM THE S 1/16 CORNER OF SECTIONS 12 AND 7

THE PLACE OF USE IS LOCATED AS FOLLOWS:

ALL  
SECTION 22 FIRE PROTECTION ONLY  
ALL  
SECTION 23  
ALL  
SECTION 26  
ALL  
SECTION 34 FIRE PROTECTION ONLY  
ALL  
SECTION 35  
ALL  
SECTION 36  
TOWNSHIP 37 SOUTH, RANGE 15 EAST, W.  
ALL  
SECTION 29  
SECTION 30 FIRE PROTECTION ONLY  
ALL  
SECTION 31  
ALL  
SECTION 32

PLACED IN U.S. MAIL

NOV 8 1996

OREGON WATER RESOURCES DEPT.

ALL  
SECTION 33  
TOWNSHIP 37 SOUTH, RANGE 16 EAST, W.M.

ALL  
SECTION 1  
ALL  
SECTION 2  
ALL  
SECTION 3 FIRE PROTECTION ONLY  
ALL  
SECTION 10 FIRE PROTECTION ONLY  
ALL  
SECTION 11  
ALL  
SECTION 12  
ALL  
SECTION 13 FIR PROTECTION ONLY  
ALL  
SECTION 14  
ALL  
SECTION 15 FIRE PROTECTION ONLY  
TOWNSHIP 38 SOUTH, RANGE 15 EAST, W.M.

ALL  
SECTION 3  
ALL  
SECTION 4  
ALL  
SECTION 5  
ALL  
SECTION 6  
ALL  
SECTION 7  
ALL  
SECTION 8  
ALL  
SECTION 9  
TOWNSHIP 38 SOUTH, RANGE 16 EAST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced.

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

**Before Use of Water Takes Place**

Initial and Annual Measurements

The Department requires the permittee to submit an initial water level measurement in the month specified above once well construction is complete and annually thereafter until use of water begins; and

**After Use of Water has Begun**

Seven Consecutive Annual Measurements

Following the first year of water use, the user shall submit seven consecutive annual reports of static water level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and

- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non or restricted use shall continue until the annual water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

#### STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the well shall begin within one year from permit issuance, and shall be completed on or before October 1, 1998. Complete application of the water to the use shall be made on or before October 1, 1999.

Issued October 29, 1996

  
Martha O. Pagel, Director  
Water Resources Department