

STATE OF OREGON

COUNTY OF CROOK

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

AVION WATER COMPANY, INC.
60813 PARRELL RD
BEND, OREGON 97702

(541) 382-5342

The specific limits for the use are listed below along with conditions of use.

APPLICATION FILE NUMBER: G-13616

SOURCE OF WATER: TWO WELLS IN THE DRY RIVER BASIN

PURPOSE OR USE: QUASI-MUNICIPAL

MAXIMUM RATE: 0.53 CUBIC FOOT PER SECOND

PERIOD OF USE: YEAR ROUND

DATE OF PRIORITY: FEBRUARY 8, 1994

POINT OF DIVERSION LOCATION: NE 1/4 SE 1/4, SECTION 36, T15S, R14E, W.M.; WELL #1 - 1600 FEET NORTH AND 695 FEET WEST, WELL #2 - 1585 FEET NORTH AND 715 FEET WEST, BOTH FROM THE SE CORNER OF SECTION 36

The use of water under this permit along with any other is limited to a total of 0.53 CUBIC FOOT PER SECOND for the same lands.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

NE 1/4 NE 1/4
NW 1/4 NE 1/4
SW 1/4 NE 1/4
SE 1/4 NE 1/4
NE 1/4 NW 1/4
NW 1/4 NW 1/4
SW 1/4 NW 1/4
SE 1/4 NW 1/4
NE 1/4 SW 1/4
SW 1/4 SW 1/4
NE 1/4 SE 1/4
NW 1/4 SE 1/4
SW 1/4 SE 1/4
SE 1/4 SE 1/4

SECTION 36

TOWNSHIP 15 SOUTH, RANGE 14 EAST, W.M.

T-9525 A POF

Application G-13616 Water Resources Department

PERMIT G-12936

SE 1/4 NW 1/4
 NE 1/4 SW 1/4
 SE 1/4 SW 1/4
 SW 1/4 SE 1/4
 SECTION 30

NE 1/4 NW 1/4
 NW 1/4 NW 1/4
 SW 1/4 NW 1/4
 NE 1/4 SW 1/4
 SW 1/4 SW 1/4
 SECTION 31

TOWNSHIP 15 SOUTH, RANGE 15 EAST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

The water user shall develop a plan to monitor and report the impact of water use under this permit on water levels within the aquifer that provides water to the permitted well(s). The plan shall be submitted to the Department within one year of the date the permit is issued and shall be subject to the approval of the Department. At a minimum, the plan shall include a program to periodically measure static water levels within the permitted well(s) or an adequate substitute such as water levels in nearby wells. The plan shall also stipulate a reference water level against which any water-level declines will be compared. If a well listed on this permit (or replacement well) displays a total static water-level decline of 25 or more feet over any period of years, as compared to the reference level, then the water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s). Such action shall be taken until the water level recovers to above the 25-foot decline level or until the Department determines, based on the

water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

Use of water under authority of this permit may be regulated if analysis of data available after the permit is issued discloses that the appropriation will measurably reduce the surface water flows necessary to maintain the free-flowing character of a scenic waterway in quantities necessary for recreation, fish and wildlife in effect as of the priority date of the right or as those quantities may be subsequently reduced.

Within 3 years of permit issuance, the permittee shall submit a water management and conservation plan consistent with OAR Chapter 690, Division 86.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

