

PLACED IN U.S. MAIL

NOV 15 1996

STATE OF OREGON  
COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS OREGON WATER RESOURCES DEPT

THIS PERMIT IS HEREBY ISSUED TO

CHARLES D. WAVRA  
8167 OAK LANE  
MT. ANGEL, OREGON 97362

(503) 845-6185

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-13735

SOURCE OF WATER: TWO WELLS IN PUDDING RIVER BASIN

PURPOSE OR USE: PRIMARY IRRIGATION OF 10.5 ACRES AND SUPPLEMENTAL IRRIGATION OF 6.7 ACRES

MAXIMUM RATE: 0.21 CUBIC FOOT PER SECOND TOTAL, FROM BOTH WELLS

PERIOD OF USE: MARCH 1 THROUGH APRIL 30 FROM WELL 1, AND MARCH 1 THROUGH OCTOBER 31 FROM WELL 2

DATE OF PRIORITY: JULY 5, 1994

POINT OF DIVERSION LOCATION: SW 1/4 NE 1/4, NE 1/4 SE 1/4, SECTION 15, T6S, R1W, W.M.; WELL 1 - 1720 FEET NORTH AND 500 FEET WEST; WELL 2 - 3900 FEET NORTH AND 1750 FEET WEST; BOTH FROM THE SE CORNER OF SECTION 15

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 3.0 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

	<u>PRIMARY</u>	<u>SUPPLEMENTAL</u>
NE 1/4 NE 1/4	5.0 ACRES	2.0 ACRES
SE 1/4 NE 1/4	0.8 ACRE	
SECTION 22		
NW 1/4 NW 1/4	4.0 ACRES	4.7 ACRES
SW 1/4 NW 1/4	0.7 ACRE	
SECTION 23		
TOWNSHIP 6 SOUTH, RANGE 1 WEST, W.M.		

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as

approved by the Director. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water use information, including the place and nature of use of water under the permit.

- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area.

This right is limited to any deficiency in the available supply of any prior right existing for the same land.

The use may be restricted if the quality of the source stream, namely the Pudding River, decreases to the point that it no longer meets state and federal water quality standards due to reduced flows.

#### **THE FOLLOWING CONDITIONS APPLY TO WELL 1**

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

##### **Before Use of Water Takes Place**

###### Initial and Annual Measurements

The Department requires the permittee to submit an initial water level measurement in the month specified above once well construction is complete and annually thereafter until use of water begins; and

##### **After Use of Water has Begun**

###### Seven Consecutive Annual Measurements

Following the first year of water use, the user shall submit seven consecutive annual reports of static water level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of 3 or more feet per year for five consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non or restricted use shall continue until the annual water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department. If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

#### **THE FOLLOWING CONDITIONS APPLY TO WELL 2**

Use of water from the well, as allowed herein, shall be controlled or shut off if the well displays:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A total water level decline of fifteen or more feet; or

- (C) A hydraulic interference decline of fifteen or more feet in any neighboring well providing water for senior exempt uses or wells covered by prior rights.

The water user shall install a meter or other measuring device suitable to the Director, and shall submit an annual report of water used to the Department by December 1 of each year.

The permittee/appropriator shall be responsible for complying with each of the following requirements for measuring water levels in the well.

- (A) Use of water from a new well shall not begin until an initial static water level in the well has been measured and submitted to the Department.
- (B) In addition to the measurement required in subsection (a) of this section, a water level measurement shall be made each year during the period March 1 through March 31.
- (C) All water level measurements shall be made by a qualified individual. Qualified individuals are certified water rights examiners, registered geologists, registered professional engineers, licensed land surveyors, licensed water well constructor, licensed pump installer, or the permittee/appropriator.
- (D) Any qualified individual measuring a well shall use standard methods of procedure and equipment designed for the purpose of well measurement. The equipment used shall be well suited to the conditions of construction at the well. A list of standard methods of procedure and suitable equipment shall be available from the Department.
- (E) The permittee/appropriator shall submit a record of the measurement to the Department on a form available from the Department. The record of measurement shall include both measurements and calculations, shall include a certification as to their accuracy signed by the individual making the measurements, and shall be submitted to the Department within 90 days from the date of measurement. The Department shall determine when any of the declines cited in section (1) are evidenced by the well measurement required in section (3).

#### STANDARD CONDITIONS

#### THE FOLLOWING CONDITIONS APPLY TO BOTH WELL 1 AND WELL 2

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the wells shall begin within one year from permit issuance and shall be completed on or before October 1, 1998. Complete application of the water to the use shall be made on or before October 1, 1999.

Issued October 31, 1996

  
Martha O. Pagel, Director  
Water Resources Department