

STATE OF OREGON

COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

NORPAC FOODS, INC.
PO BOX 458
STAYTON, OREGON 97383

(503) 769-2101

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-14105

SOURCE OF WATER: EIGHT WELLS IN PUDDING RIVER BASIN

PURPOSE OR USE: 71.6 ACRES PRIMARY IRRIGATION AND 43.2 ACRES
SUPPLEMENTAL IRRIGATION TO BRING UP IRRIGATION TO FULL RATE AND DUTY

MAXIMUM RATE: 1.43 CUBIC FEET PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: JUNE 26, 1995

POINT OF DIVERSION LOCATION: SE 1/4 NE 1/4, SE 1/4 SW 1/4, NW 1/4 SE
1/4, SW 1/4 SE 1/4, SECTION 8, NW 1/4 NE 1/4, NE 1/4 NW 1/4, SECTION 17,
T6S, R2W, W.M.; WELL #1 - 570 FEET NORTH AND 2850 FEET EAST; WELL #2 -
1050 FEET SOUTH AND 2280 FEET EAST; WELL #3 - 2840 FEET SOUTH AND 2710
FEET EAST; WELL #4 - 920 FEET SOUTH AND 2280 FEET EAST; WELL #5 - 890
FEET SOUTH AND 2990 FEET EAST; WELL #6 - 2380 FEET NORTH AND 3930 FEET
EAST; WELL #7 - 2640 FEET SOUTH AND 1390 FEET EAST; WELL #8 - 210 FEET
SOUTH AND 1680 FEET EAST, ALL FROM THE RE-ENTRANT CORNER OF AUGUSTUS
LAMBERT DLC 61

The amount of water used for irrigation under this right, together with
the amount secured under any other right existing for the same lands, is
limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or
its equivalent) and 2.5 acre-feet for each acre irrigated during the
irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

	<u>PRIMARY</u>	<u>SUPPLEMENTAL</u>
NE 1/4 SW 1/4	0.5 ACRE	0.5 ACRE
NW 1/4 SW 1/4	37.2 ACRES	2.0 ACRES
SW 1/4 SW 1/4		22.3 ACRES
SE 1/4 SW 1/4		1.3 ACRES
SECTION 17		
NE 1/4 SE 1/4	26.3 ACRES	1.3 ACRES
SW 1/4 SE 1/4	0.8 ACRE	
SE 1/4 SE 1/4	6.8 ACRES	15.8 ACRES
SECTION 18		

TOWNSHIP 6 SOUTH, RANGE 2 WEST, W.M.

Application G-14105 Water Resources Department

PERMIT G-13063

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

This right is limited to any deficiency in the available supply of any prior right existing for the same land.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Before Use of Water Takes PlaceInitial and Annual Measurements

The Department requires the permittee to submit an initial water level measurement in the month specified above once well construction is complete and annually thereafter until use of water begins; and

After Use of Water has BegunReference Water Level Determination

Following the first year of water use, the user shall submit one static water level measurement in the month specified above which will establish the reference level against which future annual measurements

will be compared. The water user is not required to measure additional water levels after the reference level has been determined unless required by the Director. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of 3 or more feet per year for 5 consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than 5 consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non or restricted use shall continue until the annual water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the well shall begin within one year from permit issuance, and shall be completed on or before October 1, 1998. Complete application of the water to the use shall be made on or before October 1, 1999.

Issued December 18, 1996


Martha O. Pagel, Director
Water Resources Department

Application G-14105 Water Resources Department
Basin 02 Volume 14, Lake Labish Ditch & Misc.
MGMT.CODES 7BG, 7BR, 7EG, 7ER

PERMIT G-13063
District 16