

STATE OF OREGON

COUNTY OF CLACKAMAS

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

ILARION EFIMOFF
34885 S. BARLOW RD.
WOODBURN, OREGON 97071

(503) 634-2813

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-12831

SOURCE OF WATER: A WELL IN THE BUTTE CREEK BASIN

PURPOSE OR USE: IRRIGATION OF 50.1 ACRES AND SUPPLEMENTAL IRRIGATION OF 10.9 ACRES

PERIOD OF ALLOWED USE: MARCH 1 THROUGH OCTOBER 31

RATE OF USE: 0.76 CUBIC FOOT PER SECOND (CFS)

DATE OF PRIORITY: MARCH 23, 1992 FOR 0.11 CFS FOR IRRIGATION OF 40.0 ACRES; MAY 6, 1992 FOR 0.22 CFS FOR IRRIGATION OF 49.4 ACRES; OCTOBER 20, 1992 FOR 0.29 CFS FOR IRRIGATION OF 49.4 ACRES; MAY 11, 1995 FOR 0.14 CFS FOR IRRIGATION OF 61.0 ACRES

POINT OF DIVERSION LOCATION: SW 1/4 SW 1/4, SECTION 30, T5S, R1E, W.M.; 330 FEET NORTH AND 910 FEET EAST FROM THE SW CORNER OF SECTION 30

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

PRIMARY IRRIGATION

SE 1/4 SE 1/4 6.8 ACRES
SECTION 25
TOWNSHIP 5 SOUTH, RANGE 1 WEST, W.M.

NW 1/4 SW 1/4 19.0 ACRES
SW 1/4 SW 1/4 24.3 ACRES
SECTION 30
TOWNSHIP 5 SOUTH, RANGE 1 EAST, W.M.

Application G-12831 Water Resources Department

PERMIT G-13100

SUPPLEMENTAL IRRIGATION

SW 1/4 SW 1/4 10.9 ACRES
SECTION 30
TOWNSHIP 5 SOUTH, RANGE 1 EAST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

This right is limited to any deficiency in the available supply of any prior right existing for the same land.

The well shall be developed from no shallower than 100 feet below the land surface.

Limited Water Level Decline/Interference Condition

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to make and report annual static water level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Before Use of Water Takes Place

Initial and Annual Measurements

The Department requires the permittee to submit an initial water level measurement in the month specified above once well construction is complete and annually thereafter until use of water begins; and

After Use of Water has Begun**Seven Consecutive Annual Measurements**

Following the first year of water use, the user shall submit seven consecutive annual reports of static water level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require that the user obtain and report additional annual static water level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor, or pump installer licensed by the Construction Contractors Board and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- (A) Identify each well with its associated measurement; and
- (B) Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- (C) Specify the method used to obtain each well measurement; and
- (D) Certify the accuracy of all measurements and calculations submitted to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if annual water level measurements reveal any of the following events:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A water level decline of 15 or more feet in fewer than five consecutive years; or
- (C) A water level decline of 25 or more feet; or
- (D) Hydraulic interference leading to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non or restricted use shall continue until the annual water level rises above the decline level which triggered the action or until the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.


The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the well shall begin on or before January 15, 1998 and shall be completed on or before October 1, 1999. The reservoirs shall be filled and complete application of water shall be made on or before October 1, 2000.

SEE NEXT PAGE

This permit is issued to modify the maximum allowable water level decline associated with the use of water under this permit. Permit 13079, dated January 15, 1997, is superseded by this instrument and is of no further force or effect.

Issued February 26, 1997



for Martha O. Pagel, Director
Water Resources Department

Application G-12831 Water Resources Department
Basin 2 Volume 15 Butte Creek & Misc.
MGMT CODES 7DG, 7DR

PERMIT G-13100
District 02