

STATE OF OREGON

COUNTY OF COLUMBIA

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

WARREN WATER ASSOCIATION  
PO BOX 1014  
ST HELENS, OREGON 97051

(503)397-3280

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-14193

SOURCE OF WATER: THREE WELLS IN COLUMBIA RIVER BASIN

PURPOSE OR USE: QUASI-MUNICIPAL

MAXIMUM RATE: 1.67 CUBIC FEET PER SECOND (CFS), BEING 0.557 CFS EACH FROM BLAHA WELL, ELLISON WELL AND GORIN WELL

PERIOD OF USE: YEAR ROUND

DATE OF PRIORITY: OCTOBER 30, 1995

POINT OF DIVERSION LOCATION: NE 1/4 NE 1/4, SECTION 22, T4S, R2W, W.M.; 569 FEET SOUTH AND 1088 FEET EAST FROM SW CORNER, N 1/2, NE 1/4 NE 1/4, SECTION 22; NW 1/4 NW 1/4, SECTION 24, T4S, R2W, W.M.; 1100 FEET SOUTH & 450 FEET EAST FROM NW CORNER, SECTION 24; SW 1/4 NW 1/4, SECTION 19, T4S, R1W, W.M.; 180 FEET NORTH & 860 FEET EAST FROM SW CORNER, G T FOSTER DLC

The amount of water used under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of 2.42 cubic feet per second.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SW 1/4 SW 1/4  
SECTION 17  
SW 1/4 NE 1/4  
SW 1/4 NW 1/4  
SE 1/4 NW 1/4  
NE 1/4 SW 1/4  
NW 1/4 SW 1/4  
SE 1/4 SW 1/4  
NE 1/4 SE 1/4  
NW 1/4 SE 1/4  
SW 1/4 SE 1/4  
SE 1/4 SE 1/4

SECTION 18

TOWNSHIP 4 NORTH RANGE 1 WEST

ALL

SECTION 19

NW 1/4 NW 1/4

SECTION 20

NW 1/4 NE 1/4

NE 1/4 NW 1/4

NW 1/4 NW 1/4

SW 1/4 NW 1/4

SE 1/4 NW 1/4

NE 1/4 SW 1/4

NW 1/4 SW 1/4

SECTION 30

TOWNSHIP 4 NORTH RANGE 1 WEST

SW 1/4 NE 1/4

SE 1/4 NE 1/4

SE 1/4 NW 1/4

NE 1/4 SW 1/4

SE 1/4 SW 1/4

NE 1/4 SE 1/4

NW 1/4 SE 1/4

SW 1/4 SE 1/4

SE 1/4 SE 1/4

SECTION 13

NE 1/4 NE 1/4

NW 1/4 NE 1/4

SW 1/4 NE 1/4

SE 1/4 NE 1/4

NE 1/4 NW 1/4

SE 1/4 NW 1/4

SE 1/4 SW 1/4

NE 1/4 SE 1/4

NW 1/4 SE 1/4

SECTION 23

ALL

SECTION 24

NE 1/4 NE 1/4

NW 1/4 NE 1/4

SW 1/4 NE 1/4

SE 1/4 NE 1/4

NE 1/4 NW 1/4

NW 1/4 NW 1/4

SW 1/4 NW 1/4

SE 1/4 NW 1/4

NE 1/4 SW 1/4

SE 1/4 SW 1/4

NE 1/4 SE 1/4

NW 1/4 SE 1/4

SW 1/4 SE 1/4

SE 1/4 SE 1/4

SECTION 25

TOWNSHIP 4 NORTH RANGE 2 WEST

SW 1/4 NE 1/4  
 SE 1/4 NE 1/4  
 NE 1/4 SE 1/4  
 NW 1/4 SE 1/4

## SECTION 26

NE 1/4 NE 1/4  
 SW 1/4 NE 1/4  
 SE 1/4 NE 1/4  
 NE 1/4 NW 1/4  
 NW 1/4 NW 1/4

## SECTION 36

TOWNSHIP 4 NORTH RANGE 2 WEST

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

The water user shall develop a plan to monitor and report the impact of water use under this permit on water levels within the aquifer that provides water to the permitted well(s). The plan shall be submitted to the Department within one year of the date the permit is issued and shall be subject to the approval of the Department. At a minimum, the plan shall include a program to periodically measure static water levels within the permitted well(s) or an adequate substitute such as water levels in nearby wells. The plan shall also stipulate a reference water level against which any water-level declines will be compared. If a well listed on this permit (or replacement well) displays a total static water-level decline of 25 or more feet over any period of years, as compared to the reference level, then the water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s). Such action shall be taken until the water level recovers to above the 25-foot decline level or until the Department determines, based on the water user's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit.

Groundwater production shall be from **no shallower** than 290 feet below land surface for the **Ellison Well**, **no shallower** than 200 feet below land surface for the **Blaha Well** and groundwater production shall only occur from the basalt groundwater reservoir between 400 feet and 700 feet below land surface for the **Gorin Well**.

Within TWO YEARS of permit issuance, the permittee shall submit a water management and conservation plan consistent with OAR Chapter 690, Division 86.

#### STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.


The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

SEE NEXT PAGE

Actual construction of the well shall begin within one year from permit issuance, and shall be completed on or before October 1, 1999. Complete application of the water to the use shall be made on or before October 1, 2000.

Issued March 12, 1997

  
for Martha O. Pagel, Director  
Water Resources Department