

STATE OF OREGON

COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

KEVIN CROSBY
16826 BUTTEVILLE RD. NE
WOODBURN, OREGON 97071

PHONE: (503) 981-9088

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-14329

SOURCE OF WATER: A WELL WITHIN THE WILLAMETTE BASIN

PURPOSE OR USE: IRRIGATION OF 62.6 ACRES

MAXIMUM RATE: 0.78 CUBIC FOOT PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: JUNE 12, 1996

POINT OF DIVERSION LOCATION: SE 1/4 NE 1/4, SECTION 30, T4S, R1W, W.M.;
1000 FEET NORTH & 250 FEET WEST FROM E1/4 CORNER, SECTION 30

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SE 1/4 SE 1/4 2.1 ACRES
SECTION 19
SW 1/4 SW 1/4 18.5 ACRES
SECTION 20
NW 1/4 NW 1/4 17.1 ACRES
SW 1/4 NW 1/4 1.0 ACRE
SECTION 29
NE 1/4 NE 1/4 18.1 ACRES
SE 1/4 NE 1/4 5.8 ACRES
SECTION 30

TOWNSHIP 4 SOUTH, RANGE 1 WEST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.

Application G-14329 Water Resources Department

PERMIT G-13143

- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

Groundwater production shall be from no shallower than 100 feet below land surface.

The well shall be continuously cased and sealed to a minimum of 100 feet. If the material at 100 feet is not clay layer, then the casing and seal should be extended into the next lower clay layer that is at least 5 feet thick.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

Application G-14329 Water Resources Department PERMIT G-13143


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the well shall begin within one year from permit issuance. Complete application of the water to the use shall be made on or before October 1, 2001.

Issued June 18, 1997



for Martha O. Pagel, Director
Water Resources Department

Application G-14329
Basin 02
LKS

Water Resources Department
Volume 18B UNNAMED STREAM
MGMT.CODES 7BG, 7BR

PERMIT G-13143
District 16