

STATE OF OREGON

COUNTY OF CLACKAMAS

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

SANDELIE GOLF CLUB, INC.  
28333 SW MOUNTAIN ROAD  
WEST LINN, OREGON 97068

503-656-3091

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-12317

SOURCE OF WATER: THREE WELLS WITHIN THE WILLAMETTE RIVER BASIN

PURPOSE OR USE: IRRIGATION OF 203.9 ACRES AND SUPPLEMENTAL IRRIGATION OF 51.5 ACRES

MAXIMUM RATE: 3.19 CUBIC FEET PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: NOVEMBER 29, 1990

POINT OF DIVERSION LOCATION: SW 1/4 NW 1/4, NE 1/4 SW 1/4, SECTION 16, SE 1/4 NE 1/4, SECTION 17, T 3 S, R 1 E, W.M.; WELL 1 - 2050 FEET SOUTH AND 1560 FEET WEST, WELL 2 - 3780 SOUTH AND 360 FEET WEST, WELL 3 - 1585 FEET SOUTH AND 3280 FEET WEST, ALL FROM THE N 1/4 CORNER, SECTION 16.

The amount of water used for irrigation, together with the amount secured under any other right existing for the same lands, shall be limited to ONE-EIGHTIETH of one cubic foot per second per acre, or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 2.5 acre-feet per acre for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

	PRIMARY WELLS 1,2&3	SUPPLEMENTAL WELL 3
NE 1/4 NW 1/4	19.1 ACRES	11.8 ACRES
SW 1/4 NW 1/4	27.4 ACRES	12.4 ACRES
SE 1/4 NW 1/4	15.2 ACRES	15.5 ACRES
NE 1/4 SW 1/4	13.6 ACRES	7.6 ACRES
NW 1/4 SW 1/4	34.4 ACRES	4.2 ACRES
SW 1/4 SW 1/4	1.4 ACRES	
SECTION 16		
NE 1/4 NE 1/4	19.2 ACRES	
SE 1/4 NE 1/4	40.0 ACRES	
NE 1/4 SE 1/4	1.5 ACRES	

SECTION 17

TOWNSHIP 3 SOUTH, RANGE 1 EAST, W.M.

Application G-12317 Water Resources Department

Superseded by  
PERMIT ~~G-12317~~

G-15085

## Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

The water user shall report a March static water level in the well(s) to the Groundwater/Hydrology Section of the Water Resources Department by April 15 of each year. The measurement shall be made and calculations detailed by a certified water rights examiner, registered professional geologist, certified engineering geologist, professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board.

Use of water from the well(s) shall not be allowed if the well(s) display (A) a water level decline of 10 or more feet, or (B) a hydraulic interference decline of 25 or more feet in any neighboring well with senior priority which provides water for an authorized use.

The Water Resources Department has determined that the initial water level in the well(s) are those of the March 1997 report. That is the level from which the cited declines in (A) above will be referenced.

This permit shall expire June 2, 2002. This permit may be extended for an additional five year periods if the Director finds the resource can probably support the extended use.

It is unlikely that this permit can be extended for an additional five years based upon water level declines in the groundwater resource. The permittee shall pursue steps for obtaining a long term water supply.

**STANDARD CONDITIONS**

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

Application G-12317 Water Resources Department

Supersedes by  
PERMIT G-12317  
6-15095

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

This permit supersedes Permit G-11529 which expired June 2, 1997.

Issued August 26, 1997



Martha O. Pagel, Director  
Water Resources Department

Application G-12317 Water Resources Department  
Basin 2 Volume 25 Willamette River N 1/2 & Misc. N 1/2 District 16

Superseded by  
PERMIT ~~G-12317~~

G-15085