

STATE OF OREGON

COUNTY OF MARION

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

ROBERT E. ROTH
12513 HOBART RD
SILVERTON, OREGON 97381

(503)873-4862

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-14426

SOURCE OF WATER: WELL 1 AND WELL 2 BOTH IN THE WILLAMETTE RIVER BASIN

PURPOSE OR USE: SUPPLEMENTAL IRRIGATION, TO MAKE UP A DEFICIENCY IN RATE FOR PERMIT G-11434, OF 158.0 ACRES

MAXIMUM RATE: 1.18 CUBIC FOOT PER SECOND (CFS) FROM WELL 1 AND 1.98 CFS FROM WELL 2, NOT TO EXCEED A MAXIMUM CUMULATIVE TOTAL OF 1.98 CFS

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: DECEMBER 20, 1996

POINT OF DIVERSION LOCATION: SE 1/4 NE 1/4, NW 1/4 SE 1/4, SECTION 28, T6S, R1W, W.M.; WELL 1 - 1975 FEET SOUTH & 25 FEET WEST FROM NE 1/4 CORNER SECTION 28; WELL 2 - 1500 FEET SOUTH & 70 FEET WEST FROM NW CORNER DLC 44

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2 1/2 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SW 1/4 NW 1/4 12.5 ACRES
NW 1/4 SW 1/4 27.8 ACRES
SW 1/4 SW 1/4 26.3 ACRES
SECTION 27
SW 1/4 NE 1/4 0.2 ACRE
SE 1/4 NE 1/4 1.2 ACRE
NE 1/4 SE 1/4 31.0 ACRES
NW 1/4 SE 1/4 10.1 ACRES
SW 1/4 SE 1/4 19.2 ACRES
SE 1/4 SE 1/4 29.7 ACRES
SECTION 28

TOWNSHIP 6 SOUTH, RANGE 1 WEST, W.M.

Application G-14426 Water Resources Department

PERMIT G-13335

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

If the number, location, or construction of any well deviates from that proposed in the permit application or permit conditions, the conclusions of the Technical Review, Initial Review or Proposed Final Order under which this permit was granted may be revised, conditions may be appropriately revised, or this permit may not be valid.

- (1) Use of water from the well, as allowed herein, shall be controlled or shut off if the well displays:
 - (a) An average water level decline of three or more feet per year for five consecutive years; or
 - (b) A total water level decline of fifteen or more feet; or
 - (c) A hydraulic interference decline of fifteen or more feet in any neighboring well providing water for senior exempt uses or wells covered by prior rights.
- (2) The water user shall install a meter or other measuring device suitable to the Director, and shall submit an annual report of water used to the Department by December 1 of each year.
- (3) The permittee/appropriator shall be responsible for complying with each of the following requirements for measuring water levels in the well.

- (a) Use of water from a new well shall not begin until an initial static water level in the well has been measured and submitted to the Department.
- (b) In addition to the measurement required in subsection (a) of this section, a water level measurement shall be made each year during the period March 1 through March 31.
- (c) All water level measurements shall be made by a qualified individual. Qualified individuals are certified water rights examiners, registered geologists, registered professional engineers, licensed land surveyors, licensed water well constructor, licensed pump installer, or the permittee/appropriator.
- (d) Any qualified individual measuring a well shall use standard methods of procedure and equipment designed for the purpose of well measurement. The equipment used shall be well suited to the conditions of construction at the well. A list of standard methods of procedure and suitable equipment shall be available from the Department.
- (e) The permittee/appropriator shall submit a record of the measurement to the Department on a form available from the Department. The record of measurement shall include both measurements and calculations, shall include a certification as to their accuracy signed by the individual making the measurements, and shall be submitted to the Department within 90 days from the date of measurement. The Department shall determine when any of the declines cited in section (1) are evidenced by the well measurement required in section (3).

Ground water for use under this permit shall be produced from the basalt aquifer between approximately 350 and 700 feet below land surface. Neither well may be perforated above the basalt aquifer.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use(s) of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Actual construction of the well shall begin within one year from permit issuance. Complete application of water to the use shall be made on or before October 1, 2002.

Issued February 25, 1998



Martha O. Pagel, Director
Water Resources Department

Application G-14426 Water Resources Department
Basin 02 Volume 13 Pudding River & Misc
RWK MGMT.CODES 7BG 7BR 7FG 7FR 7IG 7IR

PERMIT G-13335
DISTRICT 16