

STATE OF OREGON

COUNTY OF LINN

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

KENT GOAR  
38242 GOAR ROAD  
SCIO, OREGON 97374

(503) 394-3779

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-14277

SOURCE OF WATER: TWO WELLS IN THOMAS CREEK BASIN

PURPOSE OR USE: NURSERY OPERATIONS ON 26.0 ACRES

MAXIMUM RATE: 0.67 CUBIC FOOT PER SECOND, BEING 0.16 CFS FROM WELL 1 AND 0.51 CFS FROM WELL 2

PERIOD OF USE: YEAR-ROUND

DATE OF PRIORITY: MARCH 25, 1996

POINT OF DIVERSION LOCATIONS: NW 1/4 NW 1/4, SECTION 24, T10S, R2W, W.M., WELL 1 - 1572 FEET NORTH AND 476 FEET EAST; WELL 2 - 1351 FEET NORTH AND 12 FEET EAST, BOTH FROM THE W1/4 CORNER OF SECTION 24

The amount of water used for NURSERY OPERATIONS is limited to a diversion of 0.15 cubic foot per second per acre. For the irrigation of **containerized nursery plants**, the amount of water diverted is limited to ONE-FORTIETH of one cubic foot per second (or its equivalent) and 5.0 acre feet per acre per year. For the irrigation of **in ground nursery plants** the amount of water diverted is limited to ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre feet per acre per year. The use of water for NURSERY OPERATIONS may be made at anytime of the year that the use is beneficial. For the irrigation of **any other crop**, the amount of water diverted is limited to ONE-EIGHTIETH of one cubic foot per second (or its equivalent) and 2.5 acre feet per acre during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SE 1/4 NE 1/4 10.0 ACRES  
SECTION 23  
SW 1/4 NW 1/4 16.0 ACRES  
SECTION 24  
TOWNSHIP 10 SOUTH, RANGE 2 WEST, W.M.

Application G-14277 Water Resources Department

PERMIT G-13504

## Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The Director may require the permittee to keep and maintain a record of the amount (volume) of water used and may require the permittee to report water use on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The new well(well 2) must encounter the 74 feet of clay near the surface as found in well LINN 14514. The requirement above may be overcome if the applicant works with the Department's groundwater/hydrology section, prior to permanently installing casing or sealing material, and is able to construct the well in such a manner as to preclude the potential for substantial interference to the Department's satisfaction.

**STANDARD CONDITIONS**

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

