

STATE OF OREGON

COUNTY OF LAKE

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

JAMES WILLIAM VOTTO
93905 PIKE LN
LAKEVIEW OR 97630

This permit expires on October 1, 2014, or when the Governor's February 13, 2014 declaration of drought emergency for Lake County is terminated, whichever comes first.

The permittee assumes all liability associated with use of water under the permit in the event claims of injury or claims for compensation are filed.

If injury to existing rights or detriment to the public interest is observed, the Department may regulate water use under this permit to mitigate such injury or detriment, or cancel this permit if mitigation is not possible.

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17857

SOURCE OF WATER: WELL 1 IN GOOSE LAKE SWALE BASIN

PURPOSE OR USE: SUPPLEMENTAL IRRIGATION OF 93.0 ACRES

MAXIMUM RATE: 1.16 CUBIC FEET PER SECOND

PERIOD OF USE: PERMIT ISSUANCE THROUGH OCTOBER 1

DATE OF PRIORITY: MAY 12, 2014

WELL LOCATION: NW $\frac{1}{4}$ NE $\frac{1}{4}$, SECTION 14, T39S, R19E, W.M.; 132 FEET SOUTH AND 2112 FEET WEST FROM NE CORNER, SECTION 14

This right is limited to any deficiency in the available supply of any prior right existing for the same land.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 3.0 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

NE ¼ NE ¼ 8.8 ACRES
NW ¼ NE ¼ 16.4 ACRES
SW ¼ NE ¼ 31.8 ACRES
SE ¼ NE ¼ 36.0 ACRES

SECTION 14

TOWNSHIP 39 SOUTH, RANGE 19 EAST, W.M.

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the meter in good working order.
- B. The permittee shall keep a complete record of the amount of water used each month, and shall submit a report which includes the recorded water use measurements to the Department by November 15, 2014. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- C. The permittee shall allow the watermaster access to the meter; provided however, where any meter is located within a private structure, the watermaster shall request access upon reasonable notice.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

Dedicated Measuring Tube: Wells with pumps shall be equipped with a minimum 3/4-inch diameter, unobstructed, dedicated measuring tube pursuant to figure 200-5 in OAR 690-200. If a pump has been installed prior to the issuance of this permit, and if static water levels and pumping levels can be measured using an electrical tape, then the installation of the measuring tube can be delayed until such time that water levels cannot be measured or the pump is repaired or replaced.

The static ground water level at the well(s) must be measured to the nearest 0.10 foot (one-inch), recorded and reported to the Department within 7 days prior to beginning drought ground water pumping at the well(s), and subsequently measured to the nearest 0.10 foot (one-inch), recorded and reported to the Department at the end of drought ground water pumping at the well(s). The last measurement must be reported to the Department by November 15, 2014.

The well(s) shall be constructed to obtain ground water only from the predominantly basin-fill unit as proposed in the drought ground water permit application, not from the underlying predominantly volcanic/basalt unit.

Within one month from the start of use of water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may be subject to cancellation, unless the Department authorizes the change in writing.


If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

Issued June 11, 2014



for Phillip C. Ward, Director
Water Resources Department

Note: The Director may require the applicant to submit a plan and evidence showing conservation and water use curtailment measures have been taken before use is made of an emergency use permit.

Issuance of this permit does not confirm the validity of any underlying right or claim.