

STATE OF OREGON

COUNTY OF YAMHILL

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

CITY OF DUNDEE
PO BOX 220
DUNDEE, OREGON 97115

(503) 538-6700

This superseding permit is issued to describe an amendment for an additional point of appropriation proposed under Permit Amendment Application T-11928 and approved by Special Order Vol. 96, Page ~~812-813~~ entered August 17, 2015, and to describe an extension of time for complete application of water approved September 29, 2006 and a Water Management and Conservation Plan approved on November 21, 2012. This permit supersedes Permit G-12736.

The specific limits for the use are listed below along with conditions of use.

APPLICATION FILE NUMBER: G-14066

SOURCE OF WATER: TWO WELLS IN HARVEY CREEK BASIN

PURPOSE OR USE: MUNICIPAL USE

MAXIMUM RATE: 0.5 CUBIC FOOT PER SECOND

PERIOD OF USE: YEAR ROUND

DATE OF PRIORITY: MAY 19, 1995

POINT OF DIVERSION LOCATION:

Twp	Rng	Mer	Sec	Q-Q	Measured Distance
3 S	3 W	WM	22	SW SE	TEST WELL-(YAMH 56803) 285 FEET NORTH AND 1810 FEET WEST FROM THE SE CORNER OF SECTION 22
3 S	3 W	WM	27	NW NE	CITY WELL 11- 460 FEET SOUTH AND 1830 FEET WEST FROM THE NE CORNER OF SECTION 27

THE PLACE OF USE IS LOCATED AS FOLLOWS:

WITHIN THE CITY OF DUNDEE SERVICE AREA

Permit Amendment T-11928 conditions:

The combined quantity of water diverted at the new points of appropriation, together with that diverted at the old point of appropriation (City Well 11), shall not exceed the quantity of water lawfully available at the original point of appropriation (City Well 11).

Water shall be acquired from the same aquifer as the original point of appropriation (City Well 11).

Water Management and Conservation Plan Conditions:

A progress report is due no later than November 21, 2017, and an updated Water Management and Conservation Plan must be submitted to the Department no later than November 21, 2021.

Original Permit Conditions:

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a meter or other suitable measuring device as approved by the Director. The permittee shall maintain the meter or measuring device in good working order, shall keep a complete record of the amount of water used each month and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water use information, including the place and nature of use of water under the permit.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.

Ground water production shall be from no shallower than 50 feet below land surface. Ground water production shall be from the Columbia River Basalt, 50 to 400 feet below land surface.

Use of water from the well, as allowed herein, shall be controlled or shut off if the well displays:

- (A) An average water level decline of three or more feet per year for five consecutive years; or
- (B) A total water level decline of fifteen or more feet; or
- (C) A hydraulic interference decline of fifteen or more feet in any neighboring well providing water for senior exempt uses or wells covered by prior rights.

The water user shall install a meter or other measuring device suitable to the Director, and shall submit an annual report of water used to the Department by December 1 of each year.

The permittee/appropriator shall be responsible for complying with each of the following requirements for measuring water levels in the well.

- (A) Use of water from a new well shall not begin until an initial static water level in the well has been measured and submitted to the Department.
- (B) In addition to the measurement required in subsection (a) of this section, a water level measurement shall be made each year during the period March 1 through March 31.
- (C) All water level measurements shall be made by a qualified individual. Qualified individuals are certified water rights examiners, registered geologists, registered professional engineers, licensed land surveyors, licensed water well constructor, licensed pump installer, or the permittee/appropriator.

- (D) Any qualified individual measuring a well shall use standard methods of procedure and equipment designed for the purpose of well measurement. The equipment used shall be well suited to the conditions of construction at the well. A list of standard methods of procedure and suitable equipment shall be available from the Department.
- (E) The permittee/appropriator shall submit a record of the measurement to the Department on a form available from the Department. The record of measurement shall include both measurements and calculations, shall include a certificate as to their accuracy signed by the individual making the measurements, and shall be submitted to the Department within 90 days from the date of measurement. The Department shall determine when any of the declines cited above are evidenced by the well measurement required herein.

STANDARD CONDITIONS

The wells shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

The use shall conform to such reasonable rotation system as may be ordered by the proper state officer.

Prior to receiving a certificate of water right, the permit holder shall submit the results of a pump test meeting the department's standards, to the Water Resources Department. The Director may require water level or pump test results every ten years thereafter.

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.


By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The use of water shall be limited when it interferes with any prior surface or ground water rights.

The Director finds that the proposed use of water described by this permit, as conditioned, will not impair or be detrimental to the public interest.

Complete application of the water to the use shall be made on or before October 1, 2025.

Issued August 17, 2015


 Dwight French, Water Right Services Administrator, for
 Thomas M. Byler, Director
 Oregon Water Resources Department

Application G-14070/T-11928
 Basin 02

Water Resources Department
 Volume 17, CHEHALEM CREEK & MISC.
 MGMT.CODES 7IG, 7IR

PERMIT G-17484
 District 16