

STATE OF OREGON

COUNTY OF BAKER

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

HAY INC. AND JASON WILLIAMS

48857 HWY 30

NORTH POWDER, OR 97867

This superseding permit is issued to describe an amendment for additional points of appropriation proposed under Permit Amendment Application T-12542 and approved by Special Order Vol. 105, Page 768, entered September 7th, 2017, and to describe an extension of time for complete application of water approved June 21, 2016. This permit supersedes Permit G-16687.

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-17198

SOURCE OF WATER: WELL 1 OR WELL 1 (ALTERNATE POINT 1) AND WELLS A, B, C AND D WITHIN WARM SPRINGS CREEK BASIN

PURPOSE OR USE: SUPPLEMENTAL IRRIGATION USE ON 1399.6 ACRES

MAXIMUM RATE: 3.34 CUBIC FEET PER SECOND

PERIOD OF USE: MARCH 1 THROUGH OCTOBER 31

DATE OF PRIORITY: MARCH 30, 2009

WELL LOCATIONS:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
7 S	39 E	WM	4	NE SE	WELL 1 – 1600 FEET NORTH AND 1275 FEET WEST FROM THE SE CORNER OF SECTION 4
7 S	39 E	WM	4	SE SE	WELL 1 (ALTERNATE POINT 1) – 1000 FEET NORTH AND 1275 FEET WEST FROM THE SE CORNER OF SECTION 4
7 S	39 E	WM	3	NW SE	WELL A – 2330 FEET NORTH AND 2970 FEET EAST FROM THE SE CORNER OF SECTION 4
7 S	39 E	WM	3	NE NE	WELL B – 4525 FEET NORTH AND 5240 FEET EAST FROM THE SE CORNER OF SECTION 4
6 S	39 E	WM	35	SE SW	WELL C – 5290 FEET NORTH AND 6995 FEET EAST FROM THE SE CORNER OF SECTION 4, TOWNSHIP 7 SOUTH, RANGE 39 EAST
7 S	39 E	WM	2	NW SW	WELL D – 2590 FEET NORTH AND 5955 FEET EAST FROM THE SE CORNER OF SECTION 4

The amount of water used for irrigation under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 3.0 acre-feet for each acre irrigated during the irrigation season of each year

THE PLACE OF USE IS LOCATED AS FOLLOWS:

SUPPLEMENTAL IRRIGATION						Acres
Twp	Rng	Mer	Sec	Q-Q		
6 S	39 E	WM	34	NE NE		40.0
6 S	39 E	WM	34	NW NE		39.0
6 S	39 E	WM	34	SW NE		35.0
6 S	39 E	WM	34	SE NE		40.0
6 S	39 E	WM	34	NE SE		40.0
6 S	39 E	WM	34	NW SE		39.1
6 S	39 E	WM	34	SW SE		34.4
6 S	39 E	WM	34	SE SE		39.1
6 S	39 E	WM	35	NW NW		18.6
6 S	39 E	WM	35	SW NW		38.1
6 S	39 E	WM	35	SE NW		3.8
6 S	39 E	WM	35	NE SW		24.4
6 S	39 E	WM	35	NW SW		40.0
6 S	39 E	WM	35	SW SW		39.1
6 S	39 E	WM	35	SE SW		37.8
6 S	39 E	WM	35	SW SE		5.5
7 S	39 E	WM	2	NW NW		38.0
7 S	39 E	WM	2	SW NW		37.4
7 S	39 E	WM	2	NW SW		30.0
7 S	39 E	WM	2	SW SW		40.0
7 S	39 E	WM	3	NE NE		39.5
7 S	39 E	WM	3	NW NE		38.3
7 S	39 E	WM	3	SW NE		39.0
7 S	39 E	WM	3	SE NE		40.0
7 S	39 E	WM	3	NE SW		19.0
7 S	39 E	WM	3	NW SW		22.0
7 S	39 E	WM	3	SW SW		40.0
7 S	39 E	WM	3	SE SW		39.0
7 S	39 E	WM	3	NE SE		39.5
7 S	39 E	WM	3	NW SE		39.0
7 S	39 E	WM	3	SW SE		39.0
7 S	39 E	WM	4	NE SE		30.0
7 S	39 E	WM	4	SE SE		40.0
7 S	39 E	WM	9	NE NE		40.0
7 S	39 E	WM	9	SE NE		40.0
7 S	39 E	WM	10	NE NW		39.0
7 S	39 E	WM	10	NW NW		40.0
7 S	39 E	WM	10	SW NW		39.0
7 S	39 E	WM	10	SE NW		39.0
Total						1399.6

Permit Amendment T-12542 Conditions:

The combined quantity of water diverted at the new points appropriation (Wells A through D) shall not exceed the quantity of water lawfully available at the original point of appropriation (Well 1 and Well 1 (Alternative Point 1)).

Water shall be acquired from the same aquifer as the original point of appropriation (Well 1 and Well 1 (Alternative Point 1)).

Existing Conditions:

Measurement, recording and reporting conditions:

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter or other suitable measuring device as approved by the Director at each point of appropriation. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall keep a complete record of the amount of water used each month, and shall submit a report which includes the recorded water use measurements to the Department annually or more frequently as may be required by the Director. Further, the Director may require the permittee to report general water-use information, including the place and nature of use of water under the permit.
- C. The permittee shall allow the watermaster access to the meter or measuring device; provide however, where any meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- D. The Director may provide an opportunity of the permittee to submit alternative measuring and reporting procedures for review and approval.

The well(s) shall produce ground water only from the bedrock ground water reservoir.

The Department requires the water user to obtain, from a qualified individual (see below), and report annual static water levels for each well on the permit. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

The permittee shall report an initial March static water level measurement once well construction is complete and annual measurements thereafter. Annual measurements are required whether or not the well is used. The first annual measurement will establish a reference level against which future measurements will be compared. However, the Director may establish the reference level based on an analysis of other water-level data. The Director may require the user to obtain and report additional water levels each year if more data are needed to evaluate the aquifer system.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements shall be submitted on forms provided by, or specified by, the Department. Measurements shall be made with equipment that is accurate to at least the standards specified in OAR 690-217-0045. The Department requires the individual performing the measurement to:

- A. Associate each measurement with an owner's well name or number and a Department well log ID; and
- B. Report water levels to at least the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method of measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer than five consecutive years; or
- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or causing substantial interference with senior water rights. The water user shall not allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of sue under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.

STANDARD CONDITIONS

Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.

If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.

The well(s) shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port, and may also include an air line and pressure gauge adequate to determine water level elevation in the well at all times.

If the riparian area is disturbed in the process of developing a point of appropriation, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR 635-415, shall be followed.

The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.

Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

Prior to receiving a certificate of water right, the permit holder shall submit to the Water Resources Department the results of a pump test meeting the Department's standards for each point of appropriation (well), unless an exemption has been obtained in writing under OAR 690-217. The Director may require water-level or pump-test data every ten years thereafter.

This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.

By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.

The original permit was issued April 22, 2010. Actual construction work was to be within five years from issuance of the original permit. By Extension of Time Final Order dated June 21, 2016, the deadline for completing construction and for complete application of water to use was extended to October 1, 2020.

Within one year after complete application of water to the proposed use, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner (CWRE).

Issued September 7th, 2017


Dwight French, Water Right Services Administrator, for
Thomas M. Byler, Director
Oregon Water Resources Department