

STATE OF OREGON

COUNTY OF YAMHILL

PERMIT TO APPROPRIATE THE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO

SARBANAND ENTERPRISES LLC
786 RD 188
DELANO, CA 93215

This superseding permit is issued to describe an amendment for an additional point of appropriation proposed under Permit Amendment Application T-13594 and approved by Special Order Vol. 125, Page 106, entered May 19, 2022. This permit supersedes Permit G-18272.

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: G-18712

SOURCE OF WATER: EAST AIRPORT WELL (YAMH 54493/L82396) AND EAST AIRPORT WELL 2 (YAMH 6833/50997) IN WEST FORK PALMER CREEK BASIN

PURPOSE OR USE: IRRIGATION OF 254.8 ACRES

MAXIMUM RATE: 0.31 CUBIC FOOT PER SECOND

PERIOD OF USE: APRIL 1 THROUGH SEPTEMBER 30

DATE OF PRIORITY: JULY 9, 2018

WELL LOCATIONS:

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
4 S	3 W	WM	30	SW NW	EAST AIRPORT WELL - 1864 FEET SOUTH AND 621 FEET EAST FROM THE NW CORNER OF SECTION 30
4 S	4 W	WM	25	SE NE	EAST AIRPORT WELL 2 - 1620 FEET SOUTH AND 850 FEET WEST FROM THE NE CORNER OF SECTION 25

The amount of water used for irrigation use under this right, together with the amount secured under any other right existing for the same lands, is limited to a diversion of ONE-EIGHTIETH of one cubic foot per second and 2.5 acre-feet for each acre irrigated during the irrigation season of each year.

THE PLACE OF USE IS LOCATED AS FOLLOWS:

IRRIGATION					
Twp	Rng	Mer	Sec	Q-Q	Acres
4 S	3 W	WM	30	NW NW	14.8
4 S	3 W	WM	30	SW NW	11.0
4 S	4 W	WM	25	NE NE	25.1
4 S	4 W	WM	25	NW NE	9.1
4 S	4 W	WM	25	SW NE	35.0
4 S	4 W	WM	25	SE NE	10.4
4 S	4 W	WM	25	NE NW	13.6
4 S	4 W	WM	25	SE NW	36.5
4 S	4 W	WM	25	NE SW	40.2
4 S	4 W	WM	25	NW SW	0.8
4 S	4 W	WM	25	SW SW	1.1
4 S	4 W	WM	25	SE SW	12.9
4 S	4 W	WM	25	NW SE	33.9
4 S	4 W	WM	25	SW SE	10.4
Total					254.8

Permit Amendment T-13594 Conditions:

The combined quantity of water diverted at the new additional point of appropriation (East Airport Well 2), together with that diverted at the old point of appropriation (East Airport Well), shall not exceed the quantity of water lawfully available at the original point of appropriation (East Airport Well).

Water shall be acquired from the same aquifer as the original points of appropriation.

Existing Permit Conditions:**1. Water Use Measurement, Recording and Reporting Conditions:**

- A. Before water use may begin under this permit, the permittee shall install a totalizing flow meter at each point of appropriation. The permittee shall maintain the meter or measuring device in good working order.
- B. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- C. The permittee shall keep a complete record of the volume of water used each month, and shall submit an annual report which includes the recorded water-use measurements to the Department annually, or more frequently as may be required by the Director. Further, the Director may require the water user to report general water use information, including the place and nature of use of water under the permit.
- D. The Director may provide an opportunity for the permittee to submit alternative measuring and reporting procedures for review and approval.

2. Static Water Level Conditions

To monitor the effect of water use from the well(s) authorized under this permit, the Department requires the water user to obtain, from a qualified individual (see below), and report annual static water-level measurements. The static water level shall be measured in the month of March. Reports shall be submitted to the Department within 30 days of measurement.

Measurements must be made according to the following schedule:

Before Use of Water Takes Place

Initial and Annual Static Water Level Measurements

The Department requires the permittee to report an initial water-level measurement in the month specified above once well construction is complete, and annually thereafter until use of water begins; and

After Use of Water has Begun

Seven Consecutive Annual Static Water Level Measurements

Following the first year of water use, the user shall report seven consecutive annual static water-level measurements. The first of these seven annual measurements will establish the reference level against which future annual measurements will be compared. Based on an analysis of the data collected, the Director may require the user to obtain and report additional annual static water-level measurements beyond the seven year minimum reporting period. The additional measurements may be required in a different month. If the measurement requirement is stopped, the Director may restart it at any time.

All measurements shall be made by a certified water rights examiner, registered professional geologist, registered professional engineer, licensed well constructor or pump installer licensed by the Construction Contractors Board. Measurements and be submitted to the Department on forms provided by the Department. The Department requires the individual performing the measurement to:

- A. Identify each well with its associated measurement; and
- B. Measure and report water levels to the nearest tenth of a foot as depth-to-water below ground surface; and
- C. Specify the method used to obtain each well measurement; and
- D. Certify the accuracy of all measurements and calculations reported to the Department.

The water user shall discontinue use of, or reduce the rate or volume of withdrawal from, the well(s) if any of the following events occur:

- A. Annual water-level measurements reveal an average water-level decline of three or more feet per year for five consecutive years; or
- B. Annual water-level measurements reveal a water-level decline of 15 or more feet in fewer

than five consecutive years; or

- C. Annual water-level measurements reveal a water-level decline of 25 or more feet; or
- D. Hydraulic interference leads to a decline of 25 or more feet in any neighboring well with senior priority.

The period of non-use or restricted use shall continue until the water level rises above the decline level which triggered the action or the Department determines, based on the permittee's and/or the Department's data and analysis, that no action is necessary because the aquifer in question can sustain the observed declines without adversely impacting the resource or senior water rights. The water user shall in no instance allow excessive decline, as defined in Commission rules, to occur within the aquifer as a result of use under this permit. If more than one well is involved, the water user may submit an alternative measurement and reporting plan for review and approval by the Department.

3. Groundwater production shall only be from the alluvial groundwater reservoir.

4. Well Identification Tag Condition:

Prior to using water from any well listed on this permit, the permittee shall ensure that the well has been assigned an OWRD Well Identification Number (Well ID tag), which shall be permanently attached to the well. The Well ID shall be used as a reference in any correspondence regarding the well, including any reports of water use, water level, or pump test data.


STANDARD CONDITIONS

1. Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.
2. If the number, location, source, or construction of any well deviates from that proposed in the permit application or required by permit conditions, this permit may be subject to cancellation, unless the Department authorizes the change in writing.
3. If substantial interference with a senior water right occurs due to withdrawal of water from any well listed on this permit, then use of water from the well(s) shall be discontinued or reduced and/or the schedule of withdrawal shall be regulated until or unless the Department approves or implements an alternative administrative action to mitigate the interference. The Department encourages junior and senior appropriators to jointly develop plans to mitigate interferences.
4. The well(s) shall be constructed and maintained in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon. The works shall be equipped with a usable access port adequate to determine water-level elevation in the well at all times.
5. Where two or more water users agree among themselves as to the manner of rotation in the use of water and such agreement is placed in writing and filed by such water users with the watermaster, and such rotation system does not infringe upon such prior rights of any water user not a party to such rotation plan, the watermaster shall distribute the water according to such agreement.

6. Prior to receiving a certificate of water right, the permit holder shall submit to the Water Resources Department the results of a pump test meeting the Department's standards for each point of appropriation (well), unless an exemption has been obtained in writing under OAR 690-217. The Director may require water-level or pump-test data every ten years thereafter.
7. This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.
8. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.
9. The original permit was issued October 1, 2019. Construction of the well shall begin on or before October 1, 2024. The deadline to begin construction may not be extended. This permit is subject to cancellation proceedings if the construction deadline to begin is missed.
10. The original permit was issued October 1, 2019. Complete application of the water shall be made on or before October 1, 2024. If beneficial use of permitted water has not been made before this date, the permittee may submit an application for extension of time, which may be approved based upon the merit of the application.
11. Within one year after complete application of water to the proposed use, the permittee shall submit a claim of beneficial use, which includes a map and report, prepared by a Certified Water Rights Examiner.

MAY 19 2022

Signed _____;



Lisa J. Jaramillo, Transfer and Conservation Section Manager, for
THOMAS M. BYLER, DIRECTOR
Oregon Water Resources Department

