

"CERTIFICATE NO. 55353"

Application No. G-8620

Permit No. G 7955

RECEIVED

STATE OF OREGON WATER RESOURCES DEPARTMENT

JAN 24 1978

Application for a Permit to Appropriate Ground Water

WATER RESOURCES DEPT
SALEM, OREGON

I, Robert Harrison
(Name of Applicant)

of P. O. Box 502 Mosier
(Mailing Address) (City)

State of Oregon 97040 Phone No. 478-3338 do hereby
(Zip Code)

make application for a permit to appropriate the following described ground waters of the State of Oregon:

1. The development will consist of One well
(Give number of wells, tile lines, infiltration galleries, etc.)

having a diameter of 8 inches and an estimated depth of 200 feet.

2. The well or other source is to be located 64 ft. S and 241 ft. E
(N. or S.) (E. or W.)

from the NW corner of 7 sections 7
(Public Land Survey Corner)

(If there is more than one well, each must be described)

being within the NW $\frac{1}{4}$ of the NW $\frac{1}{4}$ of
Sec. 7 Tp. 2 N R. 12 E, W. M., in the county of WASCO

3. Location of area to be irrigated, or place of use if use other than irrigation.

Township	Range	Section	List $\frac{1}{4}$ $\frac{1}{4}$ of Section	List use and/or number of acres to be irrigated
2 N	12 E	6	SW $\frac{1}{4}$ SW $\frac{1}{4}$	16.0
			SE $\frac{1}{4}$ SW $\frac{1}{4}$	9.1
		7	NE $\frac{1}{4}$ NW $\frac{1}{4}$	3.3
			NW $\frac{1}{4}$ NW $\frac{1}{4}$	18.0
			TOTAL	46.4

4. It is estimated that 200 feet of the well will require 180' steel & 20' screen casing.
(Kind)

5. Depth to water table is estimated 120 Well drilled by Robert Harrison
(Feet)

6. The amount of water which the applicant intends to apply to beneficial use is cubic feet per second or ..280..... gallons per minute.

7. The use to which the water is to be applied is Irrigation of Orchards, Hay crops

8. Pasture

8. If the flow to be utilized is artesian, the works to be used for the control and conservation of the supply when not in use must be described.

9. If the location of the well, or other development work is less than one-fourth mile from a natural stream channel, give the distance to the channel and the difference in elevation between the stream bed and the ground surface at the source of development.

810 ft. South to Dry Creek, 100 ft. in elevation above Dry Creek

10. DESCRIPTION OF WORKS

Include length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

EST. 20 H.P. Turbine Pump

Buried Mainline in the following sizes and lengths; 2280 ft. - 6-inch,

1420 ft. - 5-inch, 410 ft. - 4-inch. Using hand move lines. 300ft. 2-inch

hand line with 15 #20 heads. 15 x 5 GPM = 75 GPM.

1000 ft. 3 inch hand line with 25 #30 heads. 25 x 8 G.P.M. = 200 G.P.M.

200 G.P.M. + 75 G.P.M. = 275 G.P.M.

11. Construction work will begin on or before..... 1-1-78

12. Construction work will be completed on or before..... 1-1-79

13. The water will be completely applied to the proposed use on or before..... 7-1-79

14. If the ground water supply is supplemental to an existing supply, identify the supply and existing water right.

Application No. G-8620

Permit No. G 7955

Remarks: The size, Type and H.P. of the pump will depend on the static water level of the well and be determined after the well pumping and draw down test.

Robert Harrison
Signature of Applicant

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before, 19

WITNESS my hand this day of, 19

Water Resources Director

By

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the

24th day of January, 1978, at 11:00 o'clock A.M.

Application No. G-8620

Permit No. G 7955

G 1978

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same, **SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING MINIMUM FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD** and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.58 cubic feet per second measured at the point of diversion from the well or source of appropriation, or its equivalent in case of rotation with other water users, from a well

The use to which this water is to be applied is irrigation

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 3 acre feet per acre for each acre irrigated during the irrigation season of each year;

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon.

The works constructed shall include an air line and pressure gauge or an access port for measuring line, adequate to determine water level elevation in the well at all times.

The permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

The priority date of this permit is January 24, 1978

Actual construction work shall begin on or before April 11, 1979 and shall


thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1979

Extended to Oct. 1 1980 Extended to Oct. 1 1981 Extended to Oct. 1, 1982 Extended to Oct. 1, 1983

Complete application of the water to the proposed use shall be made on or before October 1, 1980

Extended to Oct. 1 1982 Extended to Oct. 1, 1983 Extended to Oct. 1, 1983

WITNESS my hand this 11th day of April, 1978


Water Resources Director