

"CERTIFICATE NO. 61380"

Application No. G-8928

Permit No. G 8320

STATE OF OREGON WATER RESOURCES DEPARTMENT

Application for a Permit to Appropriate Ground Water

I, Regional Park and Recreation Agency

(Name of Applicant)

of 555 Liberty Street, S.E., Salem

(Mailing Address)

(City)

State of Oregon 97301 Phone No. 588-6305 do hereby

(Zip Code)

make application for a permit to appropriate the following described ground waters of the State of Oregon:

1. The development will consist of One water well

(Give number of wells, tile lines, infiltration galleries, etc.)

having a diameter of 6" and an estimated depth of 80 feet.

2. The well or other source is to be located 1.050 ft. N. and 400 ft. W.

(N. or S.)

(E. or W.)

from the S., E., corner of Sec. 36

(Public Land Survey Corner)

(If there is more than one well, each must be described)

being within the S. E. $\frac{1}{4}$ of the S. E. $\frac{1}{4}$ of

Sec. 36 Tp. 2 W. R. 2 W., W. M., in the county of MARION

3. Location of area to be irrigated, or place of use if use other than irrigation.

Township	Range	Section	List $\frac{1}{4}$ $\frac{1}{4}$ of Section	List use and/or number of acres to be irrigated
7 S	2 W	31	(S.W.1/4 of the)	<u>1.907</u>
			(S.W.1/4 Sec. 31)	
7 S	3 W	36	(S.E.1/4 of the)	<u>6.382</u>
			(S.E.1/4 Sec. 36)	
				<u>8.289 Acres Total</u>

4. It is estimated that 80 feet of the well will require 6" Steel casing.

(Kind)

5. Depth to water table is estimated 13' Well drilled by Out for Bid

(Feet)

6. The amount of water which the applicant intends to apply to beneficial use is cubic feet per second or ...30..... gallons per minute.

Public Park use

7. The use to which the water is to be applied is ~~potable water~~ Irrigation

8. If the flow to be utilized is artesian, the works to be used for the control and conservation of the supply when not in use must be described.

9. If the location of the well, or other development work is less than one-fourth mile from a natural stream channel, give the distance to the channel and the difference in elevation between the stream bed and the ground surface at the source of development.

Distance from Channel is 600'. Ground surface elevation is 11' 0" higher than stream bed.

10. DESCRIPTION OF WORKS

Include length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

The supply line to irrigation zones consist of 1300' of 3" main and 600' of 2" water main.

Irrigation pump will be a 5 h.p., 3-phase, 220V, submersible pump.

Irrigation system will be a valve-in-head system, activated by field controllers. Water pump will not exceed 80 G.P.M. at any time.

11. Construction work will begin on or before.....September...1,...1978.....

12. Construction work will be completed on or before.....October...1,...1978.....

13. The water will be completely applied to the proposed use on or before...May...1...1979.....

14. If the ground water supply is supplemental to an existing supply, identify the supply and existing water right

Application No. G-8928

Permit No. G 8320

G 8320

Remarks:.....

Regional Parks & Recreation Agency
Signature of Applicant
by *James D. Bennett*

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for.....

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before....., 19.....

WITNESS my hand this day of....., 19.....

Water Resources Director

By

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the

15th day of *August*, 19 *78*, at *11:04* o'clock
A.M.

Application No. *G-8928*

Permit No. *G 8320*

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same, **SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING MINIMUM FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD** and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.07 cubic feet per second measured at the point of diversion from the well or source of appropriation, or its equivalent in case of rotation with other water users, from a well.

The use to which this water is to be applied is public park use.

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 2 1/2 acre feet per acre for each acre irrigated during the irrigation season of each year;

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon.

The works constructed shall include an air line and pressure gauge or an access port for measuring line, adequate to determine water level elevation in the well at all times.


The permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

The priority date of this permit is August 15, 1978

Actual construction work shall begin on or before November 7, 1979 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1980

Complete application of the water to the proposed use shall be made on or before October 1, 1981

WITNESS my hand this 7th day of November, 1978


Water Resources Director

Handwritten initials: BAF