

75922  
 "CERTIFICATE NO. 65873"

Application No. G-9209

Permit No. G 8600

**STATE OF OREGON WATER RESOURCES DEPARTMENT** RECEIVED

**Application for a Permit to Appropriate Ground Water** APR 23 1979

WATER RESOURCES DEPT.  
SALEM, OREGON

I, KENNETH & DOROTHY EMERY

(Name of Applicant)

of P.O. Box 57

(Mailing Address)

SILVER LAKE

(City)

State of OREGON, 97638

(Zip Code)

Phone No. 503 576-2222

do hereby make application for a permit to appropriate the following described ground waters of the State of Oregon:

1. The development will consist of 1 WELL & A CENTER PIVOT 2171 feet

(Give number of wells, tile lines, infiltration galleries, etc.)

having a diameter of 16 inches and an estimated depth of 46.2 feet.

2. The well or other source is to be located 2014 ft. S and 160 ft. W

(N. or S.)

(E. or W.)

from the NE corner of Section 30

(Public Land Survey Corner)

(If there is more than one well, each must be described)

being within the SE 1/4 1/4 of the NE 1/4 1/4 of

Sec. 30 Tp. 28 R. 15, W. M., in the county of LAKE

3. Location of area to be irrigated, or place of use if use other than irrigation.

Township	Range	Section	List 1/4 1/4 of Section	List use and/or number of acres to be irrigated
28 S	15 E	30	NW 1/4 NE 1/4	13.9
			NE 1/4 NE 1/4	37.2
			SW 1/4 NE 1/4	29.4
			SE 1/4 NE 1/4	40.0
			NW 1/4 SE 1/4	27.9
			NE 1/4 SE 1/4	40.0
			SE 1/4 SE 1/4	5.5
28 S	15 E	29	NW 1/4 NW 1/4	33.0
			NE 1/4 NW 1/4	4.5
			SW 1/4 NW 1/4	40.0 (SEE REMARKS)

4. It is estimated that 105 feet of the well will require Steel casing.

(Kind)

5. Depth to water table is estimated 49 Well drilled by MEL SEARCH

(Feet)

6. The amount of water which the applicant intends to apply to beneficial use is ..... cubic feet per second or 2150 gallons per minute.

7. The use to which the water is to be applied is IRRIGATION

8. If the flow to be utilized is artesian, the works to be used for the control and conservation of the supply when not in use must be described.

DNA

9. If the location of the well, or other development work is less than one-fourth mile from a natural stream channel, give the distance to the channel and the difference in elevation between the stream bed and the ground surface at the source of development.

10. DESCRIPTION OF WORKS

Include length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

This irrigation system consists of a 16" WELL, 150 hp VHS MOTOR with 75ft 10" column, 4 stage 13.5 inch bowl assembly. The water will be applied by using a 2,096 ft center pivot with a Nelson 100 end gun irrigation an additional 75ft giving a total radius of 2,171 ft. TOTAL IRRIGATED ACRES 339.8.

11. Construction work will begin on or before October 1, 1978

12. Construction work will be completed on or before April 1, 1979

13. The water will be completely applied to the proposed use on or before April 1, 1979

14. If the ground water supply is supplemental to an existing supply, identify the supply and existing water right. DNA


Application No. G-9209

Permit No. G 8600

Remarks:

285 15E 29 SE 1/4 NW 1/4 18.9  
 NW 1/4 SW 1/4 38.7  
 NE 1/4 SW 1/4 7.7  
 SW 1/4 SW 1/4 3.3

TOTAL INDICATED ACRES 339.8 ACRES

  
 Signature of Applicant

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for.....

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before....., 19.....

WITNESS my hand this..... day of....., 19.....

Water Resources Director

By.....

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the

23rd day of April, 19 79, at 8:00 o'clock  
 A.M.

Application No. G-9209 Permit No. G 8600

### Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same, **SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING MINIMUM FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD** and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 4.25 cubic feet per second measured at the point of diversion from the well or source of appropriation, or its equivalent in case of rotation with other water users, from a well.

The use to which this water is to be applied is irrigation.

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 3 acre feet per acre for each acre irrigated during the irrigation season of each year;

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon.

The works constructed shall include an air line and pressure gauge or an access port for measuring line, adequate to determine water level elevation in the well at all times.


The permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

The priority date of this permit is April 23, 1979

Actual construction work shall begin on or before July 13, 1980 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1980

Complete application of the water to the proposed use shall be made on or before October 1, 1981

WITNESS my hand this 13th day of July, 1979

  
Water Resources Director