

Application No. G-9393

Permit No. G 8664

STATE OF OREGON WATER RESOURCES DEPARTMENT

Application for a Permit to appropriate Ground Water **RECEIVED**

SEP 8 - 1979

I, Creature Enterprises, Inc. c/o Richard Bach
(Name of Applicant)

WATER RESOURCES DEPT
SALEM, OREGON

of 4001 Little Applegate Road Jacksonville
(Mailing Address) (City)

State of Oregon 97530 Phone No. 899-8198 do hereby
(Zip Code)

make application for a permit to appropriate the following described ground waters of the State of Oregon:

1. The development will consist of one well
(Give number of wells, tile lines, infiltration galleries, etc.)

having a diameter of 6 in. and an estimated depth of 400 feet.

2. The well or other source is to be located 1145 ft. N. and 150 ft. E.
(N. or S.) (E. or W.)

from the W¹/₄ corner of Section 19
(Public Land Survey Corner)

(If there is more than one well, each must be described)

being within the SW 1/₄ of the NW 1/₄ of
Sec. 19 Tp. 39S R. 2W, W. M., in the county of Jackson

3. Location of area to be irrigated, or place of use if use other than irrigation.

Township	Range	Section	List 1/4 1/4 of Section	List use and/or number of acres to be irrigated
39S	2W	19	SW ¹ / ₄ NW ¹ / ₄	4.60 primary irrig.
			SW ¹ / ₄ NW ¹ / ₄	2.70 suppl. irrig.
			SW ¹ / ₄ NW ¹ / ₄	1.40 suppl. irrig.
				8.70

4. It is estimated that 22 feet of the well will require 250 casing.
(Kind)

5. Depth to water table is estimated 135 Well drilled by Artesian Well Drilling
(Feet)

6. The amount of water which the applicant intends to apply to beneficial use is 0.10 cubic feet per second or gallons per minute.

7. The use to which the water is to be applied is Irrigation and supp. irrigation

8. If the flow to be utilized is artesian, the works to be used for the control and conservation of the supply when not in use must be described.

9. If the location of the well, or other development work is less than one-fourth mile from a natural stream channel, give the distance to the channel and the difference in elevation between the stream bed and the ground surface at the source of development.

Well is located 900' north of the Little Applegate River with a difference in elevation of plus 120 feet.

10. **DESCRIPTION OF WORKS**

Include length and dimensions of supply ditch or pipeline, size and type of pump and motor, type of irrigation system to adequately describe the proposed distribution system.

3 H.P. submersible pump,
800 feet 4-inch pipeline,
600 feet of 2-inch pipeline.

11. Construction work will begin on or before 1 year from date of priority

12. Construction work will be completed on or before Oct. 1, 1981

13. The water will be completely applied to the proposed use on or before Oct 1, 1982


14. If the ground water supply is supplemental to an existing supply, identify the supply and existing water right. Supplemental to 1.4 ac. of Certificate 38773 and 2.7 acres of Application No. 59265.

Application No. G-9393

Permit No. G 8664

Remarks:.....

.....
.....
.....
.....
.....
.....

x 
Signature of Applicant

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for.....

In order to retain its priority, this application must be returned to the Water Resources Director with corrections on or before....., 19.....

WITNESS my hand this day of....., 19.....

Water Resources Director

By

This instrument was first received in the office of the Water Resources Director at Salem, Oregon, on the 6th day of September, 1979, at 11:00 o'clock A.M.

Application No. G-9393.....

Permit No. G-8664.....

Permit to Appropriate the Public Waters of the State of Oregon

This is to certify that I have examined the foregoing application and do hereby grant the same, SUBJECT TO EXISTING RIGHTS INCLUDING THE EXISTING MINIMUM FLOW POLICIES ESTABLISHED BY THE WATER POLICY REVIEW BOARD and the following limitations and conditions:

The right herein granted is limited to the amount of water which can be applied to beneficial use and shall not exceed 0.1 cubic feet per second measured at the point of diversion from the well or source of appropriation, or its equivalent in case of rotation with other water users, from a well

The use to which this water is to be applied is irrigation and supplemental irrigation

If for irrigation, this appropriation shall be limited to 1/80th of one cubic foot per second or its equivalent for each acre irrigated and shall be further limited to a diversion of not to exceed 2 1/2 acre feet per acre for each acre irrigated during the irrigation season of each year; provided further that the right allowed herein shall be limited to any deficiency in the available supply of any prior right existing for the same land and shall not exceed the limitation allowed herein.

and shall be subject to such reasonable rotation system as may be ordered by the proper state officer.

The well shall be constructed in accordance with the General Standards for the Construction and Maintenance of Water Wells in Oregon.

The works constructed shall include an air line and pressure gauge or an access port for measuring line, adequate to determine water level elevation in the well at all times.


The permittee shall install and maintain a weir, meter, or other suitable measuring device, and shall keep a complete record of the amount of ground water withdrawn.

The priority date of this permit is September 6, 1979

Actual construction work shall begin on or before November 14, 1980 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1981

Complete application of the water to the proposed use shall be made on or before October 1, 1982

WITNESS my hand this 14th day of November, 1979


Water Resources Director

RAH A