



STATE OF OREGON

County of BENTON

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-68220 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Oregon Department of Fish and Wildlife of 506 SW Mill Street, Portland, Oregon 97208, phone 229-5701, for the construction of Adair Pond Reservoir and storage of water from an unnamed tributary of Calloway Creek, a tributary of Bowers Slough/Willamette River to be maintained by appropriation of water under Application 68221, Permit 49026 for warm water fish rearing and *

The dam will be LOCATED in the: SW 1/4 SE 1/4 of Section 30, Township 10 South, Range 4 West, WM, in the County of Benton.

The maximum height will be 17.0 feet above the stream bed or ground surface at the centerline. The top width will be 20.0 feet, slope of upstream face 3:1, slope of downstream face 6:1, and height of dam above water line when full 2.5 feet

The area submerged by the reservoir, when full, will be 6.4 acres, and the maximum depth of water will be 14.0 feet

* waterfowl refuge, and the dam shall be constructed under the supervision of a registered professional engineer.

The location and dimensions of the spillway are: Around the dam, the bottom width of the spillway will be 10.0 feet. The top width of the spillway will be 40.0 feet. The distance between the crest of the dam and the crest of the spillway will be 2.5 feet.

The location and dimension of the outlet conduit will be: 24 inch diameter galvanized corrugated steel pipe with a 13 foot vertical stand pipe as an inlet with a 24 inch Waterman gate for draining Reservoir.

The structure is in the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 43.0 acre-feet

The PRIORITY DATE of this permit is November 7, 1984

Actual construction work shall begin on or before December 28, 1985, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1986

Witness my hand this 28th day of December, 1984

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-68220

PERMIT R10061