



STATE OF OREGON

County of WASHINGTON

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-68323 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Oregon Garden Products, Inc. of 3150 SE Minter Bridge Road, Hillsboro, Oregon 97123, phone 640-4633, for the construction of the Joe Dober Reservoir and storage of water from Davis Creek, a tributary to Tualatin River, to be appropriated under Application 68324, Permit 49375 for related nursery uses. All flashboards to be removed from spillway during the period from October 1 to *

The dam will be LOCATED in the: NW 1/4 NW 1/4, Section 26, Township 1 South, Range 3 West, WM, in the County of Washington.

The maximum height will be 21.1 feet above the stream bed or ground surface at the centerline. The top width will be 12.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 5.0 feet without temporary flashboards; 3.0 feet with temporary flashboards.

The area submerged by the reservoir, when full, will be 15.0 acres, and the maximum depth of water will be 17.0 feet

* April 1 of each year.

The dimensions of the spillway are: The bottom width of the spillway will be 22.0 feet. The top width of the spillway will be 40.0 feet. The distance between the crest of the dam and the crest of the spillway will be 6.0 feet.

The location and dimension of the outlet conduit will be: A 12 inch diameter, steel pipe encased in reinforced concrete. Located 185 feet from west end of dam.

The dam is in the channel.

The dam will be earthfill construction with flashboards in spillway.

The right hereunder shall be limited to the storage of 37.5 acre-feet

The PRIORITY DATE of this permit is April 11, 1985

Actual construction work shall begin on or before July 2, 1986, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1987.

Witness my hand this 2nd day of July, 1985.

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-68323

"CERTIFICATE NO. 63320"

PERMIT

R10505