



STATE OF OREGON

County of WASHINGTON

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-68582 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Arnold Durazo of 13710 SW Hall Blvd., Tigard, Oregon 97223, phone 620-4338, for the construction of Arnold's Reservoir and storage of water from an unnamed drainage way to be appropriated under Application 68583, Permit 49558 for irrigation,

The dam will be LOCATED in the: SW 1/4 SW 1/4, Section 8, Township 2 South, Range 1 West, WM, in the County of Washington.

The maximum height will be 9.5 feet above the stream bed or ground surface at the centerline. The top width will be 9.0, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.5 feet

The area submerged by the reservoir, when full, will be 0.25 acres, and the maximum depth of water will be 14.0 feet

The dimensions of the spillway are: The bottom width of the spillway will be 5.5 feet. The top width of the spillway will be 11.0 feet. The distance between the crest of the dam and the crest of the spillway will be 2.5 feet.

The location and dimension of the outlet conduit will be: In the center of the dam it is 8 inch asphalt-dipped corrugated metal pipe with two cutoff collars and a slide gate.

The dam is in the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of 2.5 acre-feet annually during the nonirrigation season or when excess water is otherwise available.

The PRIORITY DATE of this permit is October 1, 1985.

Actual construction work shall begin on or before December 16, 1986, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1987.

Witness my hand this 16th day of December, 1985.

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-68582

"CERTIFICATE NO. 60683"

PERMIT

R10588