



STATE OF OREGON

County of WASHINGTON

"CERTIFICATE NO. 60827

**PERMIT to CONSTRUCT a RESERVOIR and to STORE
for BENEFICIAL USE the PUBLIC WATERS**

This is to certify that I have examined APPLICATION **R-68388** and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to **O.K. Tobey Sr., of 33003 SW T.V. Highway, Hillsboro, Oregon, 97123, phone 640-4911,** for the construction of Tobey Reservoir and storage of water from Christensen Creek to be maintained by appropriation of water under Application 68389, Permit 49601, tributary of Campbell Creek, for fish, and the dam shall be constructed under the supervision of a registered professional engineer.*

The dam will be LOCATED in the: **SW 1/4 NE 1/4 of Section 33, Township 1 South, Range 3 West, WM, in the County of Washington.**

The maximum height will be **19.0** feet above the stream bed or ground surface at the centerline. The top width will be **8.0** feet, slope of upstream face **2:1**, slope of downstream face **2.5:1**, and height of dam above water line when full **5.3 feet**.

The area submerged by the reservoir, when full, will be **1.11 acres** and the maximum depth of water will be **12.5 feet**.
* This permit is issued subject to the following conditions: the permittee shall 1-Cycle 8 inch gate annually to assure operation; 2-Keep embankment free of brush, trees and burrowing animals; 3-Maintain structure and appurtenances to configuration as shown on the plans and specifications.

The dimension of the spillway is: Twin 36" CMP through south embankment. The distance between the crest of the dam and the crest of the spillway will be 5.0 feet.

The location and dimension of the outlet conduit will be: 48" CMP Vertical, 42" CMP Horizontal, 8" Gate, Center of Stream.

The dam is in the channel.

The dam will be earthfill construction.

The right hereunder shall be limited to the storage of **6.3** acre-feet annually during the nonirrigation season or when excess water is otherwise available.

The PRIORITY DATE of this permit is **June 13, 1985** for storage of 4.0 acre feet and **February 4, 1986** for storage of 2.3 acre feet.

Actual construction work shall begin on or before **April 17, 1987** and shall thereafter be prosecuted with reasonable diligence and be completed on or before **October 1, 19 87**.

Witness my hand this **17th** day of **April**, 19 **86**.

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION **R-68388**

PERMIT

R10603