



STATE OF OREGON

County of MALHEUR

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-63233 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to Wayne J. Blaylock of Riverside, Oregon, 97917, phone 493-2461, for the enlargement of Reservoir #3 and storage of water from unnamed stream #2; Stream #2 to be supplemented by water from the South Fork Malheur River and construction of Reservoir #4 and storage of water from unnamed stream #1; to be supplemented by water from the South Fork Malheur River, tributaries of Malheur River all to be ap-*

The dam will be LOCATED in the: Reservoir #3- SE 1/4 SW 1/4 Section 20; Reservoir #4- SW 1/4 SW 1/4 Section 20, both in Township 24 South, Range 37 East, WM, in the County of Malheur.

The maximum height will be #3-23 #4-15 feet above the stream bed or ground surface at the centerline. The top width will be 10.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 2.5 feet, both

The area submerged by the reservoir, when full, will be #3-4.8 acres #4-2.0 acres, and the maximum depth of water will be #3-20.6 feet #4-12.6 feet

The dimensions of the spillways are: The bottom width of the spillway will be both-8.0 feet. The top width of the spillway will be both-20.0 feet. The distance between the crest of the dam and the crest of the spillway will be both-3.25 feet.

The locations and dimensions of the outlet conduits will be: Both-8 inch pipes located under reservoirs in center of drainage.

The dams are out of the channel.

The dam will be earthfill construction.

* propagated under Application 63234, Permit 49659 for irrigation.

** nonirrigation season or when excess water is otherwise available.

The right hereunder shall be limited to the storage of 10.0 acre-feet, being 3.5 acre-feet in the enlargement of Reservoir #3 and 6.5 acre feet in Reservoir #4, annually during the** February 5, 1986

The PRIORITY DATE of this permit is

Actual construction work shall begin on or before July 3, 1987, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1988.

Witness my hand this 3rd day of July, 1986.

/s/ WILLIAM H. YOUNG

WATER RESOURCES DIRECTOR

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.

APPLICATION R-63233

PERMIT

R10617