



STATE OF OREGON

County of GRANT

PERMIT to CONSTRUCT a RESERVOIR and to STORE for BENEFICIAL USE the PUBLIC WATERS

This is to certify that I have examined APPLICATION R-66820 and do hereby grant the same SUBJECT TO EXISTING RIGHTS AND THE FOLLOWING LIMITATIONS AND CONDITIONS:

This permit is issued to U.S., Malheur National Forest of 139 N.E. Dayton St., John Day, Oregon 97845, phone 575-7131, for the construction of the SL-20 Reservoir and storage of water from an unnamed stream, tributary of Slide Creek for livestock, and is subject to the installation and maintenance of an outlet pipe or to provide other means to evacuate the stored water when* The dam will be LOCATED in the: Lot 7 of Section 6, Township 10 South, Range 32 East, W.M., in the County of Grant.

The maximum height will be 8.5 feet above the stream bed or ground surface at the centerline. The top width will be 8.0 feet, slope of upstream face 3:1, slope of downstream face 2:1, and height of dam above water line when full 8.0 feet

The area submerged by the reservoir, when full, will be 0.6 acre, and the maximum depth of water will be 6.0 feet

The dimensions of the spillway are: The bottom width of the spillway will be 5.0 feet. The top width will be 11.0 feet. The distance between the crest of the dam and the crest of the spillway will be 2.5 feet.

The location and dimensions of the outlet conduit will be: none.

The dam is in the channel.

The dam will be earthfill construction.

* determined by the Water Resources Director to be necessary to satisfy prior downstream rights.

The right hereunder shall be limited to the storage of 0.2 acre-foot annually during the nonirrigation season or when excess water is otherwise available. The PRIORITY DATE of this permit is September 26, 1983

Actual construction work shall begin on or before October 20, 1988, and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1989.

Witness my hand this 20th day of October, 1987.

/s/ WILLIAM H. YOUNG
WATER RESOURCES DIRECTOR

"CERTIFICATE NO. 66395"

This permit, when issued, is for the beneficial use of water. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan. It is possible that the land use you propose may not be allowed if it is not in keeping with the goals and the acknowledged plan. Your city or county planning agency can advise you about the land-use plan in your area.