

STATE OF OREGON  
 COUNTY OF YAMHILL  
 PERMIT TO STORE PUBLIC WATERS

THIS PERMIT IS HEREBY ISSUED TO:

STEVE AND ROSALBA GOFFENA  
 16005 SW INVERURIE RD  
 LAKE OSWEGO OR 97035

**This superseding permit is issued to describe an amendment for a change in place of use proposed under Permit Amendment Application T-11435 and approved by Special Order Vol. 88, Page 249, entered July 26, 2012. This permit supersedes Permit R-14786.**

The specific limits and conditions of the use are listed below.

APPLICATION FILE NUMBER: R-87486

SOURCE OF WATER: UNNAMED STREAM AND RUNOFF, TRIBUTARIES TO ASH SWALE

STORAGE FACILITY: GOFFENA RESERVOIR

MAXIMUM VOLUME: 15.0 ACRE FEET

DATE OF PRIORITY: JUNE 29, 2009

WATER MAY BE APPROPRIATED AS FOLLOWS: NOVEMBER 1 THROUGH JUNE 30

USE: MULTIPLE PURPOSE

**Authorized Point of Diversion:**

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
5 S	4 W	WM	28	SE NE	2800 FEET SOUTH AND 500 FEET WEST FROM THE NE CORNER OF SECTION 28

**Dam Location:**

Twp	Rng	Mer	Sec	Q-Q	Measured Distances
5 S	4 W	WM	28	NE SE	2850 FEET SOUTH AND 750 FEET WEST FROM THE NE CORNER OF SECTION 28

**The Area To Be Submerged:**

Twp	Rng	Mer	Sec	Q-Q
5 S	4 W	WM	28	NE SE

Pursuant to ORS 537.211(4)(e), the use of water under the permit at the proposed place of use shall not occur until after August 20, 2012.

**Measurement, recording and reporting conditions:**

- A. Before water may be stored under this permit, a staff gage that measures the entire range between full reservoir level and dead-pool level must be installed in the reservoir. The staff gage shall be United States Geological Survey style porcelain enamel iron staff gage style A, C, E or I.

- B. Before water may be stored under this permit, the permittee shall install a totalizing flow meter or other suitable measuring device as approved by the Director at each point of diversion. The permittee shall maintain the meter or measuring device in good working order.
- C. The permittee shall allow the watermaster access to the meter or measuring device; provided however, where the meter or measuring device is located within a private structure, the watermaster shall request access upon reasonable notice.
- D. The Director may require the permittee to keep and maintain a record of the amount (volume) of water stored and may require the permittee to submit this report on a periodic schedule as established by the Director. In addition, the Director may require the permittee to report general water use information, the periods of water use and the place and nature of use of water under the permit.
- E. The Director may provide an opportunity for the permittee to submit alternative reporting procedures for review and approval.

The permittee shall not release stored water from the reservoir(s) July 1 through September 30 unless determined necessary by the Water Resources Department to satisfy prior downstream rights.

The storage of water allowed herein is subject to the installation and maintenance of an outlet pipe (with a minimum diameter of 8" for any in-channel reservoir). This requirement may be waived if the Department determines other means have been provided to evacuate water when necessary.

The permittee shall pass all live flow outside the storage season described above.

The Director may require the user to measure inflow and outflow, above and below the reservoir respectively, to ensure that live flow is not impeded outside the storage season. Measurement devices and their implementation must be acceptable to the Director, and the Director may require that data be recorded on a specified periodic basis and reported to the Department annually or more frequently.

The permittee shall not construct, operate or maintain any dam or artificial obstruction to fish passage in the channel of the subject stream without providing a fishway to ensure adequate upstream and downstream passage for fish, unless the permittee has requested and been granted a fish passage waiver by the Oregon Fish and Wildlife Commission. The permittee is hereby directed to contact an Oregon Department of Fish and Wildlife Fish Passage Coordinator, before beginning construction of any in-channel obstruction.

This permit allows an annual appropriation (not to exceed the specified volume). This permit does not provide for the appropriation of water for out-of-reservoir uses, the maintenance of the water level or maintaining a suitable freshwater condition. If any water is to be used for out-of-reservoir purposes, a secondary water right is required. If any additional live flow is to be appropriated to maintain either the water level or a suitable freshwater condition, an additional water right is required.

The permittee shall install, maintain, and operate fish screening and by-pass devices consistent with current Oregon Department of Fish and Wildlife (ODFW) standards. Fish screening is to prevent fish from entering the proposed diversion while by-pass devices provide adequate upstream and downstream passage for fish. The required screen and by-pass devices are to be in place and functional, and approved in writing by ODFW prior to diversion of any water. The permittee may submit evidence in writing that ODFW has determined screens and/or by-pass devices are not necessary.

## STANDARD CONDITIONS

1. Failure to comply with any of the provisions of this permit may result in action including, but not limited to, restrictions on the use, civil penalties, or cancellation of the permit.
2. This permit is for the beneficial use of water without waste. The water user is advised that new regulations may require the use of best practical technologies or conservation practices to achieve this end.
3. By law, the land use associated with this water use must be in compliance with statewide land-use goals and any local acknowledged land-use plan.
4. The use of water allowed herein may be made only at times when sufficient water is available to satisfy all prior rights, including prior rights for maintaining instream flows.
5. If the riparian area is disturbed in the process of developing a point of diversion, the permittee shall be responsible for restoration and enhancement of such riparian area in accordance with ODFW's Fish and Wildlife Habitat Mitigation Policy OAR 635-415. For purposes of mitigation, the ODFW Fish and Wildlife Habitat Mitigation Goals and Standards, OAR Chapter 635, Division 415, shall be followed.
6. The use may be restricted if the quality of downstream waters decreases to the point that those waters no longer meet existing state or federal water quality standards due to reduced flows.
7. If the volume of the completed reservoir is 9.2 acre feet or more and a dam is used to impound the water, the height of the dam shall be less than 10.0 feet.
8. Construction shall be completed and up to the permitted annual volume of water shall be stored within five years of the date of permit issuance.
9. Within one year after storage of water, the permittee shall submit a claim of beneficial use to the Oregon Water Resources Department.
10. The claim of beneficial use shall be prepared by a Certified Water Right Examiner in conformance with the requirements of OAR 690-014 if an associated secondary permit exists for the use of stored water under this permit, or if the reservoir capacity is equal to or greater than 9.2 acre-feet.
11. If no secondary permit exists and the reservoir capacity is less than 9.2 acre-feet of water, the claim of beneficial use need not be prepared by a Certified Water Right Examiner. The information submitted to the Oregon Water Resources Department shall include:
  - a. the dimensions of the reservoir;
  - b. the maximum capacity of the reservoir in acre-feet; and
  - c. a map identifying the location of the reservoir prepared in compliance with Water Resource Department standards.

Issued July 26, 2012

E. Timothy Wall for  
Dwight French, Water Right Services Administrator, for  
PHILLIP C. WARD, DIRECTOR