

* Reservoir Permit No. 2260

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, ELDON S. ALT (Name of Applicant)

of Rt 3, Box 142A SILVERTON (Mailing Address)

State of OREGON, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is UNAMED

2. The name of the stream from which the reservoir is to be filled and the appropriation made is

PUDDING RIVER tributary of WILLIAMITE RIVER

3. The amount of water to be stored is 9.0 acre feet.

4. The use to be made of the impounded water is IRRIGATION (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 34 NW 1/4 SEC. 7 (Give sections or townships to be subdivided)

Tp. 7E R. 14W W. M., in the county of MARION

(a) State whether situated in channel of running stream and give character of material at outlet

OFF CHANNEL RESERVOIR CLAY - HEAVY

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

TO BE PUMPED FULL FROM PUDDING RIVER

6. The dam will be located in 34 NW 1/4 SEC. 7 (Smallest legal subdivision) Sec. 7

Tp. 7E R. 14W W. M. The maximum height will be 5 feet above stream bed or ground

surface on center line of dam. The length on top will be 200 feet; length on

bottom 250 feet; width on top 6 feet; slope of front

or water side 3:1; slope on back 2:1; height of dam above water line

when full 2.0 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

2260

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: EARTH FILL, WAVE PROTECTION NOT NECESSARY

8. The location of wasteway with dimensions are as follows: AROUND DAM
(State whether over or around the dam)
10' BOTTOM WIDTH, 2' DEPTH, 1 1/2:1 SIDE SLOPE, 100' LENGTH

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: 8" CONDUIT UNDER DAM, EMERGED IN CONC. WITH CUTOFF COLLARS & 8" VALVE, 12" DIA. EN
(State whether through or around the proposed dam)

10. The area submerged by the proposed reservoir, when full, will be 2.2 acres, with a maximum depth of water of 6 feet; and approximate mean depth of water 4.1 feet.

11. The estimated cost of the proposed work is \$ 2,000.00

12. Construction work will begin on or before MAY 5, 1959

13. Construction work will be completed on or before MAY 5, 1960

Eldon S. Alt
(Name of applicant)

STATE OF OREGON, }
County of Marion. } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for correction or completion as follows:

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before _____, 19____.

WITNESS my hand this _____ day of _____, 19____.

STATE ENGINEER

Remarks: THE PURPOSE OF THIS DAM IS FOR SUPPLEMENTAL IRRIGATION FOR THE LAND LISTED UNDER PERMIT'S # 24660 & 21442. BECAUSE THE DRAINAGE AREA BEHIND THIS DAM IS ONLY 15 AC. (APPROX.) THE RESERVOIR WILL BE KEPT FULL WITH A SMALL PUMP ON PUDDING RIVER & THEN REPUMPED TO FIELDS FROM THE RESERVOIR.

STATE OF OREGON, |
County of Marion. | ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of a reservoir and the storage of water from Pudding River to be appropriated under application No. 33231, permit No. 26268 for irrigation.

The right hereunder shall be limited to the storage of 9.0 acre feet.

The priority date of this permit is July 13, 1959

Actual construction work shall begin on or before August 20, 1960

and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1961

WITNESS my hand this 20th day of August 1959

Edward H. Stanley
STATE ENGINEER

Application No. *R-33230*
Reservoir Permit No. *R-2260*

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *13th* day of *July*, 19 *59* at *4:00* o'clock *P* M.

Approved:

August 20, 1959
Recorded in Book No. *8* of
Reservoirs, on Page *3201*

LEWIS A. STANLEY
STATE ENGINEER

Drainage Basin No. *2* page *340*

Fees Paid

State Printing Dept. 31271