

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, OREGON STATE GAME COMMISSION (Name of Applicant)

of P. O. Box 4136, Portland 8, Oregon (Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is Lofton Enlargement of Lofton Reservoir.

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Fishhole Creek, tributary of Sprague River

3. The amount of water to be stored is 299 acre feet by the Game Commission and 250 acre feet by the applicant.

4. The use to be made of the impounded water is Recreational Fish propagation. (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 22 Tp. 38S, R. 16E, W. M., in the county of Lake. (Give sections or townships to be submerged)

(a) State whether situated in channel of running stream and give character of material at outlet Material for the outlet will be boulders.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in NW 1/4 of the NE 1/4, Sec. 22, Tp. 38S, R. 16E, W. M. The maximum height will be 23 feet above stream bed or ground surface on center line of dam. The length on top will be 250 feet; length on bottom 280 feet; width on top 15 feet; slope of front or water side 3 on 1; slope on back 2 on 1; height of dam above water line when full 3 feet.

\* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Material will be earth fill with dump riprap for wave protection.

8. The location of wasteway with dimensions are as follows: Wasteway will be on the left abutment around the dam, 180 feet long, 20 feet wide and 2 feet deep.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: Asbestos bonded C.M.C. 18" in diameter. Emptying into the spillway canal.

10. The area submerged by the proposed reservoir, when full, will be 41.4 acres, with a maximum depth of water of 20 feet; and approximate mean depth of water 13.3 feet.

11. The estimated cost of the proposed work is \$ 8500.00

12. Construction work will begin on or before September 1, 1959

13. Construction work will be completed on or before September 1, 1960.

P. W. Schneider (Signature of applicant)

OREGON STATE GAME COMMISSION P. W. SCHNEIDER, DIRECTOR

STATE OF OREGON, ss. County of Marion,

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for completion

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before November 2, 1959 June 7, 1960

WITNESS my hand this 1st day of September, 1959 6th day of May, 1960

LEWIS A. STANLEY STATE ENGINEER

By Walter N. Perry ASSISTANT

Remarks: This dam is a joint project between the Game Commission and Mr. Hunt. The Game Commission will control the lower 250 acre feet, which we will use for fish propagation. Mr. Hunt will irrigate with the top 250 acre feet, which he will control. The Soil Conservation Service is doing the engineering; preparing the plans which will be forwarded to your office for approval. Mr. Hunt will let the contract. The Game Commission will do the inspection during construction.

STATE OF OREGON, }  
 County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the ~~construction~~ enlargement of Lofton Reservoir and the storage of water from Fishhole Creek to be appropriated under application No. 33305, permit No. 222 for fish propagation, and the dam shall be constructed under the supervision of a registered professional engineer.

The right hereunder shall be limited to the storage of 299.0 acre feet.

The priority date of this permit is August 19, 1959

Actual construction work shall begin on or before July 15, 1961 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1962

WITNESS my hand this 15<sup>th</sup> day of July, 1960

*Lewis A. Stanley*  
 STATE ENGINEER

Application No. *R-33304*  
Reservoir Permit No. *R-2343*

### PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *19<sup>th</sup>* day of *August*, 19*29*, at *2.45* o'clock *P*. M.

Returned to applicant:

Approved:

*W. E. ...*

Recorded in Book No. *9* of  
Reservoirs, on Page *2343*

*W. E. ...*  
STATE ENGINEER

Drainage Basin No. *14* page *20A*.

Fees *6.00*