

RECEIVED
STATE ENGINEER
SALEM, OREGON

Reservoir Permit No. 2476

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

United States Bureau of Land Management
(Name of Applicant)

P. O. Box 37, Prineville, Oregon
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation.

Government Agency

1. The name of the proposed reservoir is Long Draw #2 Detention Dam

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Reservoir is to be filled from a draw feeding into Sears Canyon tributary of Crooked River through underground flow

3. The amount of water to be stored is 3 acre feet. to retain spring run off for

4. The use to be made of the impounded water is livestock consumption only
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 25
(Give sections or townships to be submerged)

Tp. 20 S., R. 21 E., W. M., in the county of Crook

(a) State whether situated in channel of running stream and give character of material at outlet

This reservoir is to be situated in a draw which is dry except for a short period during the spring run off.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

This reservoir will be filled from melted snow flowing down the channel in which the reservoir is to be constructed.

6. The dam will be located in SE 1/4, Sec. 25
(Smallest legal subdivision)

Tp. 20 S., R. 21 E., W. M. The maximum height will be 15 feet above stream bed or ground

surface on center line of dam. The length on top will be 164 feet; length on

bottom 35 feet; width on top 12 feet; slope of front

or water side 3.5:1; slope on back 2:1; height of dam above water line
(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

when full 5 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

2476

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: This dam will be constructed of a silty clay soil which contains some gravel and small rocks. No protection from wave action will be provided.

8. The location of wasteway with dimensions are as follows: The wasteway will be around the end of the dam. It will be 5 feet deep, 10 feet wide on the bottom and 20 feet wide on the top. The bottom 2 feet of depth will be in solid undisturbed earth and the top 3 feet will be composed of fill.

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: There is no existing normal flow in this channel only a peak lasting a very short period of time. No outlet conduit is to be provided. (All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time.)

10. The area submerged by the proposed reservoir, when full, will be 5 acres, with a maximum depth of water of 10 feet; and approximate mean depth of water 6.4 feet.

11. The estimated cost of the proposed work is \$ 489.62

12. Construction work will begin on or before November 30, 1960

13. Construction work will be completed on or before January 1, 1961

[Handwritten Signature]
(Signature of applicant)
District Manager

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections, on or before, 19.....

WITNESS my hand this day of, 19.....

STATE ENGINEER

Remarks:

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Long Draw No. 2 Detention Reservoir and storage of water from a tributary of Sears Canyon for livestock watering purposes.

The right of storage of water as granted herein is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the State Engineer to be necessary to satisfy prior downstream rights.

The right hereunder shall be limited to the storage of 3.0 acre feet.

The priority date of this permit is June 21, 1960

Actual construction work shall begin on or before October 20, 1961 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1962.

WITNESS my hand this 20th day of October, 1960.

[Signature]
STATE ENGINEER

Application No. *R-34041*
Reservoir Permit No. *R-2476*

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *21st* day of *June*, 19*60*, at *1:00* o'clock *P.*M.

Returned to applicant:

Approved:

October 20, 1960

Recorded in Book No. *9* of
Reservoirs, on Page *111*

LEWIS A. STANLEY
STATE ENGINEER

Drainage Basin No. *5* page *14D*