

*Reservoir Permit No. 2508

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, Bureau of Land Management
(Name of Applicant)

of Box 591 Baker, Oregon
(Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

U.S. Government

1. The name of the proposed reservoir is

Ruckles Creek Allotment Reservoir #1

2. The name of the stream from which the reservoir is to be filled and the appropriation made is

None

tributary of Ruckles Creek

3. The amount of water to be stored is .84 acre feet.

4. The use to be made of the impounded water is Stock Water
(Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 17
(Give sections or townships to be submerged)

Tp. 9S, R. 42E, W.M., in the county of Baker

(a) State whether situated in channel of running stream and give character of material at outlet

Not in a Running Stream

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions Filled by Spring Run-Off

6. The dam will be located in SW 1/4 SW 1/4, Sec. 17
(Smallest legal subdivision)

Tp. 9S, R. 42E, W.M. The maximum height will be 10 feet above stream bed or ground

surface on center line of dam. The length on top will be 146 feet; length on

bottom 146 feet; width on top 10 feet; slope on front

or water side 3:1; slope on back 2:1; height of dam above water line
(Feet horizontal to 1 vertical) (Feet horizontal to 1 vertical)

when full 4 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by addressing the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Built from rocky clay loam which exists at the site.
Protection of the front provided by the 3:1 slope.

8. The location of wasteway with dimensions are as follows: Around the dam, 150' long, 12' wide, and 4' deep.
(State whether over or around the dam)

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: None
(All dams across natural stream channels must be provided with an outlet conduit, of such capacity and location to pass the normal flow of the stream at any time)

10. The area submerged by the proposed reservoir, when full, will be .42 acres, with a maximum depth of water of 6 feet; and approximate mean depth of water 2 feet.

11. The estimated cost of the proposed work is \$ 330.75

12. Construction work will begin on or before July 1, 1961

13. Construction work will be completed on or before July 2, 1962

BUREAU OF LAND MANAGEMENT

(Signature of applicant)

Paul F. ...
District Manager

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before, 19.....

WITNESS my hand this day of, 19.....

STATE ENGINEER

By ASSISTANT

Remarks: This project is to be constructed under provisions of the Taylor Grazing Act of June 20, 1934, as amended.

The right of storage of water as granted herein is subject to the installation and maintenance of an outlet pipe or to provide other means to evacuate the stored water when determined by the State Engineer to be necessary to satisfy prior downstream rights.

STATE OF OREGON, } ss.
County of Marion, }

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of Ruckles Creek Allotment Reservoir No. 1 and storage of water from an unnamed tributary of Ruckles Creek for livestock watering purposes.

The right of storage of water as granted herein is subject to the installation and maintenance of an outlet pipe, or to provide other means to evacuate the stored water when determined by the State Engineer to be necessary to satisfy prior downstream rights.

The right hereunder shall be limited to the storage of 0.84 acre feet.

The priority date of this permit is September 2, 1960

Actual construction work shall begin on or before October 25, 1961 and

shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1962.

WITNESS my hand this 25th day of October, 1960

Lewis A. Stanley
STATE ENGINEER

Application No. *R-34294*
Reservoir Permit No. *R-2508*

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the *2nd* day of *September*, 19*60*, at *8:00* o'clock *A.*M.

Returned to applicant:

Approved:

October 25, 1960
Recorded in Book No. *2* of
Reservoirs, on Page *2508*

LEWIS A. STANLEY
State Engineer

Drainage Basin No. *9* page *34E*

Fees