

Reservoir Permit No. 2000

Application for a Permit to Construct a Reservoir and to Store for Beneficial Use the Unappropriated Waters of the State of Oregon

I, E. J. Belmont (Name of Applicant)

of Rte. 5 Box 710 Oregon City, Oregon (Mailing Address)

State of Oregon, do hereby make application for a permit to construct the following described reservoir and to store the unappropriated waters of the State of Oregon, subject to existing rights.

If the applicant is a corporation, give date and place of incorporation

1. The name of the proposed reservoir is

2. The name of the stream from which the reservoir is to be filled and the appropriation made is Un-named

tributary of Clackamas River

3. The amount of water to be stored is 3.6 acre feet

4. The use to be made of the impounded water is Irrigation (Irrigation, power, domestic supply, etc.)

5. The location of the proposed reservoir will be in Sec. 22 (Give sections or townships to be submerged)

Tp. 2S, R. 2E, W.M., in the county of Clatsop

(a) State whether situated in channel of running stream and give character of material at outlet Project is situated in channel of running stream. Material at outlet is sand, silt.

(b) If not in channel of running stream, state how it is to be filled. If through a feed canal, give name and dimensions

6. The dam will be located in Sec. 22, Tp. 2S, R. 2E, W.M. The maximum height will be 22 feet above stream bed or ground surface on center line of dam. The length on top will be 120 feet; length on bottom 150 feet; width on top 12 feet; slope on front or water side 3:1; slope on back 2:1; height of dam above water line when full 22 feet.

* A different form of application should be used for the appropriation of stored water to beneficial use. Such forms can be secured without charge, together with instructions, by communication to the State Engineer, Salem, Oregon.

7. The construction of dam, the material of which it is to be built, and method of protection from waves are as follows: Compacted earth fill. No protection from waves necessary

8. The location of wasteway with dimensions are as follows: The emergency spillway will be located in the left abutment of the structure. The dimensions of the spillway are: crest width = 12 ft.; slopes will be a min of 2:1

9. The location of outlet from the proposed reservoir, with character of construction and dimensions, are as follows: An outlet of 12" pipe will be installed. Conduit will be 12" pipe from 12" trickle tube and 12" from trickle tube to outlet. Siphon will be of 12" pipe. Trickle tube will be of 12" galvanized pipe.

10. The area submerged by the proposed reservoir, when full, will be 2.4 acres, with a maximum depth of water of 12 feet; and approximate mean depth of water 6.4 feet.

11. The estimated cost of the proposed work is \$ 2500.

12. Construction work will begin on or before Oct. 1, 1962

13. Construction work will be completed on or before Oct. 31, 1962

(Signature of applicant)

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application, together with the accompanying maps and data, and return the same for

In order to retain its priority, this application must be returned to the State Engineer, with corrections on or before 19

WITNESS my hand this day of 19

STATE ENGINEER

By ASSISTANT

Remarks: Plans for proposed project will be submitted to the Soil Conservation Service as soon as completed.

[Dotted lines for handwritten notes]

STATE OF OREGON, }
County of Marion, } ss.

This is to certify that I have examined the foregoing application and do hereby grant the same, subject to the following limitations and conditions: The right herein granted is limited to the construction of a reservoir and storage of water from an unincorporated stream to be appropriated under application No. 37099, permit No. 28117 for irrigation.

The right hereunder shall be limited to the storage of 3.6 acre feet.

The priority date of this permit is June 5, 1962

Actual construction work shall begin on or before August 31, 1963 and shall thereafter be prosecuted with reasonable diligence and be completed on or before October 1, 1964

WITNESS my hand this 31st day of August 1962

[Signature]
Deputy STATE ENGINEER

Application No. _____
Reservoir Permit No. **R-2993**

PERMIT

To construct a reservoir and store for beneficial use the unappropriated waters of the State of Oregon.

This instrument was first received in the office of the State Engineer at Salem, Oregon, on the _____ day of _____ 19____ at _____ o'clock _____ M.

Returned to applicant:

Approved:

_____ August 27, 1962 _____ of
Recorded in Book No. _____ 11 _____ of
Reservoirs, on Page **2993**.

_____ State Engineer

Drainage Basin No. _____ page **10 N.**

Fees _____